



**ADDENDUM NO. 2  
TO THE**

**OMWD AC AND CONCRETE PAVING MAINTENANCE AND SWPPP DRAINAGE IMPROVEMENT PROJECT  
FOR THE OLIVENHAIN MUNICIPAL WATER DISTRICT**

February 14, 2023

The following addendum shall be made part of the Bidding Opportunity.. **The deadline for submitting bid has not changed and remains at 2:00 p.m. Thursday February 23, 2023 at 1966 Olivenhain Road, Encinitas, CA 92024.**

**ADDENDUM SECTION 1 – QUESTIONS**

1. Q: Per Exhibit #4 – Heavy Equipment Yard  
Per exhibit #6 Detail 2 - Concrete Pad 6” concrete on 12” class 2 Base course – 18” Section being excavated  
Per exhibit #6 Detail 4 - Asphalt are 4” asphalt on 12” class 2 base course --- 16” section being excavated  
Excavation of excess soils for both Concrete & Asphalt sections to be hauled away offsite to legal landfill or stockpile onsite ?  
**A: Per Section 01710 and Section 02200 the Contractor shall make their own arrangements for legal disposal of excess materials. Disposal or burying onsite is not permitted.**
2. Q: Per Exhibit #4 Heavy Equipment yard, will there be surveyed limit Staking offsets and set elevations for G-1 Curb & G-2 curb for proper alignment?  
**A: Engineered survey will not be provided for the Heavy Equipment Yard. The Owner will establish a control point for the Contractor.**
3. Q: 3- Per Exhibit #2 Upper Lot Limits of new asphalt pavement: Per exhibit #6 calls out 4” asphalt on 8” class 2 base – excavated dirt and roots to be stockpiled onsite or haul away offsite to legal landfill ?  
**A: Per Section 01710 and Section 02200 the Contractor shall make their own arrangements for legal disposal of excess materials. Disposal or burying onsite is not permitted.**
4. Q: Are expansion barriers required?  
**A: Yes, provide expansion barrier per San Diego Regional Standards for G-01 and G-02 curb.  
For modified walkway in Upper Parking Lot, provide expansion barrier per Section 03000 for contact with existing concrete. For concrete mow curb and monolithic curb, provide expansion joints at limits of curb type.  
See updated Exhibit 4 for locations.**

**ADDENDUM DRAWING REVISIONS**

1. **DELETE** old Exhibit 4 – Heavy Equipment Yard – Rev. 1  
**REPLACE** Exhibit 4 – Heavy Equipment Yard – Rev. 2

**END OF ADDENDUM NO. 1**

Attachments:

- Exhibit 4 – Heavy Equipment Yard – Rev. 2

APPROVED:

**OLIVENHAIN MUNICIPAL WATER DISTRICT**



02/14/2023

---

Lindsey Stephenson, P.E.  
Engineering Manager

# PAVING MAINTENANCE & SWPPP DRAINAGE IMPROVEMENT PROJECT

## EXHIBIT 4 - HEAVY EQUIPMENT YARD - REV 2

