




Municipal Water District

RESIDUALS HANDLING BUILDING AS-BUILTS
Supplement to the DCMWTP Condition Assessment &
Improvement Recommendations RFP August 2022

DAVID C. McCOLLOM WATER TREATMENT PLANT LT2 IMPROVEMENTS



LOCATION MAP


NO SCALE

**FINAL DESIGN SUBMITTAL
DECEMBER 2010**

**Olivenhain Municipal Water District
1966 Olivenhain Road
Encinitas, CA 92024
(760) 753-6466**

BOARD OF DIRECTORS

EDMUND K. SPRAGUE, PRESIDENT
ROBERT F. TOPOLOVAC, VICE PRESIDENT
MARK A. MUIR, TREASURER
JACOB J. KRAUSS, SECRETARY
GERALD E. VARTY, DIRECTOR
KIMBERLY A. THORNER, GENERAL MANAGER



VICINITY MAP


NO SCALE

Prepared by:

CDM

Camp Dresser & McKee Inc.

consulting
engineering
construction
operations




GEORGE R. BRIEST, P.E. R.C.E. C048853

DATE


ORIGINAL SCALE IN INCHES 0 1 2 3 4

SHEET
1 / 218
OF SHEETS
G-1
WO 179950


1/8" = 1'-0"




EAST
ELEVATION
1/8" = 1'-0"



NORTH
ELEVATION
1/8" = 1'-0"



SOUTH
ELEVATION
1/8" = 1'-0"



WEST
ELEVATION
1/8" = 1'-0"

BID SCHEDULE B

DESIGN	DATE	BY	REVISIONS
JIT			
DRAW			
CHECK			
LCA			

CDM
David C. McCollom WTP
LT2 Improvements
Residuals Handling Building
Elevations

OLIVENTHAIN
Municipal Water District
Residuals Handling Building
Elevations

DAVID C. MCCOLLOM WTP
LT2 IMPROVEMENTS
RESIDUALS HANDLING BUILDING
ELEVATIONS

SHEET
55
OF SHEETS
218





WO 179950



CONFORMED

ORIGINAL SCALE IN INCHES


0 1 2 3 4

DWG: P:\Projects\WTP\0002\WTP LT2\Conformed Set\CDM\DWG\L12\A2-EL-SOLIDS.dwg
DATE: Jun 15, 2011 2:40pm
XREFS: 78666-DCMWP LT2-A-EL-SOLIDS 78666-DCMWP LT2-S-EL-SOLIDS 78666-DCMWP LT2-A-EL-SOLIDS 78666-DCMWP LT2-S-EL-SOLIDS
USER: jmcollum



SHEET 56 / 218 OF SHEETS						DAVID C. MCCOLLOM WTP LT2 IMPROVEMENTS						RESIDUALS HANDLING BUILDING SECTIONS						WO 179950																																																					
 OLIVENSHAIN Municipal Water District 1989 Olivenshain Road Encinitas, CA 92024 (760) 735-6468												<p>CDM</p> <p>Craig Dumas & Associates 1925 Parkway Oaks Way, Suite 300 San Marcos, CA 92069 Tel: (760) 438-7796 <i>consulting • engineering • construction • operations</i></p>												CONFORMED																																															
												DESIGN JIT												MARK 												DATE 6/11												BY IEC												REVISIONS ADDENDUM 3											
												DRAWN																																																											
												CHECK																																																											
												JIT																																																											
												LCA																																																											

DWG: P:\Projects\DWG\0002\DWG\LT2 Conformed SA\DWG\LT2 Conformed SA\DWG\LT2-75-01.dwg USER: jnordquist
DATE: Jun 15, 2011 2:17pm XREFS: 73556-DWMTP_L17-S-NP-RH02 73556-DWMTP_L17-S-NP-RH02





FOUNDATION
PLAN
3/16" = 1'-0"

NOTES:

- FOR GENERAL STRUCTURAL NOTES AND TYPICAL STRUCTURAL DETAILS SEE SHEETS S-1 THROUGH S-7.
- SIZING AND DESIGN OF THE BUILDING FRAME COLUMNS AND THE STRUCTURAL SUPPORT SYSTEM, LATERAL BRACING, BASE PLATES AND CAST-IN-PLACE ANCHOR BOLTS SHALL BE AS SPECIFIED BY PRE-ENGINEERED BUILDING SUPPLIER PER SPECIFICATION SECTION 13125.

- DESIGN ROOF DEAD LOAD: 30 PSF
DESIGN ROOF LIVE LOAD: 20 PSF
- DESIGN FLOOR LIVE LOAD: 300 PSF
- (C1) INDICATES HSS 6x6x1/2 COLUMNS AT PLATFORM. SEE FRAMING PLAN ON 7S-2.
- (C2) INDICATES HSS 5x5x5/16 COLUMNS AT PLATFORM. SEE FRAMING PLAN ON 7S-2.

BID SCHEDULE B



DAVID C. MCCOLLOM WTP
LT2 IMPROVEMENTS

RESIDUALS HANDLING BUILDING
FOUNDATION PLAN

OLIVENHAIN
Water District
10000 Wilshire Blvd.
Encinitas, CA 92024 (760) 948-4466


CDM
Beyaz & Patel, Inc.
10250 Wilshire Blvd., Suite 300
San Diego, California
Tel: (619) 438-7750
Fax: (619) 438-7750
consulting - engineering - construction - operations

CONFORMED


DESIGN CT
DRAWN JN
CHECK GH/YP

MARK
DATE 6/11
BY IEC
REVISIONS
ADDENDUM 2
ADDENDUM 6





SHEET 79 OF 218
7S-1
WO 179950



NOTES:

1. FOR GENERAL STRUCTURAL NOTES AND TYPICAL STRUCTURAL DETAILS SEE SHEETS S-1 THROUGH S-7.
2. BEAM LOCATIONS SHALL MATCH WITH CENTRIFUGE SUPPORTS. COORDINATE WITH CENTRIFUGE SUPPLIER. PROVIDE ADDITIONAL STRUCTURAL FRAMING/SUPPORTS PER SUPPLIER'S REQUIREMENTS TO SUPPORT CENTRIFUGE.
3. AT THE CENTRIFUGE PLATFORM: EXCITING FREQUENCY AFTER VIBRATION ISOLATORS FROM EQUIPMENT TRANSFERRED TO PLATFORM SHALL NOT EXCEED 3HZ.
4.  INDICATES MOMENT CONNECTION

BID SCHEDULE B



BID SCHEDULE B

ORIGINAL SCALE IN INCHES

[illegible]

CDM
Camp Dresser & McKee
1925 Palomar Oaks Way, Suite 300
San Diego, California 92108



OLIVENHAIN

DAVID C. MCCOLLOM WTP
LT2 IMPROVEMENTS


RESIDUALS HANDLING BUILDING SECTIONS

SHEET 81 OF SHEETS	7S-3
WO 179950	

```


DWC: P:\Projects\OWMD (0002)\00xx_L12_Conformed_Set\CAUS\04_Structural\04_Design_Services\NM_Bld\04_Structural\04_CADD\73656-DWCWMP_L12-75-03.dwg
DATE: Jun 15, 2011 2:18pm
XREFS: 73656-DWCWMP_L12-G-B5
       73656-DWCWMP_L12-S-SC-RH002
       73656-DWCWMP_L12-S-SC-RH003
       73656-DWCWMP_L12-S-SC-RH004
USER: jfordquist

```


PLAN - ADDL REINF AT COLUMN

DETAIL
3/8" = 1'-0"




PLAN - ADDL REINF AT CORNER COLUMN


DETAIL
3/8" = 1'-0"




SECTION 1
 $\frac{3}{4}" = 1'-0"$ 75-1



SECTION 2
 $3/4" = 1'-0"$ 7S-1




SECTION 3




COLUMN FOOTING

SECTION	4
3/4" = 1'-0"	-



SLAB EDGE WITH CURB
SECTION 5
3/4" = 1'-0" 7S-1




SLABS AT EJ

DETAIL


$3/4" = 1'-0"$

C


7S-3



DETAIL D
3/4" = 1'-0" 7S-3





DETAIL E
3/4" = 1'-0" 75-3




SLAB EDGE WITH AC BUMPS
SECTION 6
3/4" = 1'-0" 75-1

BID SCHEDULE B







12" CONCRETE CURB
DETAIL A
3/4" = 1'-0" 7S-3



TRENCH
DETAIL B
3/4" = 1'-0" 7S-3



SECTION 1
3/4" = 1'-0" 7S-1



SECTION 2
3/4" = 1'-0" 7S-1


BID SCHEDULE B

ORIGINAL SCALE IN INCHES

0 1 2 3 4

DESIGN	CT	BY	DATE	MARK	REVISIONS
DRAWN	JN				
CHECK	GH/VP				
CDM					
Beyaz & Patel, Inc.					
Civil & Structural Engineers					
San Diego, California					
CDM					
Group Designer & Engineer					
California State License No. 50488					
California License No. 60008					
consulting • engineering • construction • operations					
OLIVENHAIN					
Municipal Water District					
Bakersfield, CA 93304 (760) 753-6466					
DAVID C. MCCOLLOM WTP					
LT2 IMPROVEMENTS					
RESIDUALS HANDLING BUILDING					
SECTIONS AND DETAILS					
CONFORMED					
SHEET 83 OF 218 7S-5					
WO 179950					


DWG: P:\Projects\QMW\0002\Draws\LT2 Conformed Set\CAD\04 Structure\10 CAD\73555-DCMWP-LT2-7S-06.dwg
 DATE: Jun 15, 2011 2:19pm
 USER: jhorqust
 XREFS: 73555-DCMWP-LT2-S-PP-RH802 73555-DCMWP-LT2-S-NP-RH802



CENTRIFUGE PLATFORM FRAMING

SECTION 1
3/16" = 1'-0"


BID SCHEDULE "C"



CENTRIFUGE PLATFORM FRAMING

SECTION 2
3/16" = 1'-0"


BID SCHEDULE "C"



CENTRIFUGE PLATFORM FRAMING & STAIR LANDING


SECTION 3
3/16" = 1'-0"

BID SCHEDULE "C"



THIRD STAGE ACCESS PLATFORM FRAMING


SECTION 4
3/16" = 1'-0"



THIRD STAGE ACCESS PLATFORM FRAMING

SECTION 5
3/16" = 1'-0"


NOTE:
1. THIS FRAME OCCURS AT EACH SET OF COLUMNS IN THE NORTH/SOUTH DIRECTION (4 PLACES) ON THE THIRD STAGE ACCESS PLATFORM.



SECTION 6
3/4" = 1'-0"

FRAMING ELEVATION NOTES:

1. HSS 3x INDICATES HSS 3x3x5/16
2. HSS4x INDICATES HSS 4x4x5/16
3. HSS5x INDICATES HSS 5x5x5/16
3. HSS6x INDICATES HSS 6x6x1/2
4. W10 INDICATES W10 PER PLAN



BID SCHEDULE B

CDM
 David C. McCollom WTP
 1900 Olivewood Road
 Encinitas, CA 92024 (760)755-0466

OLIVENHAIN
 Consulting Engineers
 1900 Olivewood Road
 Encinitas, CA 92024 (760)755-0466

DAVID C. MCCOLLOM WTP
 LT2 IMPROVEMENTS
















RESIDUALS HANDLING BUILDING
 PLATFORM FRAMING ELEVATIONS

SHEET 84 / 218
 OF SHEETS

W0 179950

CONFORMED

ORIGINAL SCALE IN INCHES



BID SCHEDULE B

ORIGINAL SCALE IN INCHES

DWG: P:\Projects\OMWD (2002)\00x_LT2 Conformed Set\CADD\04 Design Services\NW_Bldg\04 Structural\10 CADD\73656-DOWMTP_LT2-7S-07.dwg
DATE: Jun 15, 2011 2:19pm
XREFS: 73656-DOWMTP_LT2-6S
USER: jrdquist

DESIGN	MARK	DATE	BY	REVISIONS
CT				
DRAWN				
JN				
CHECK				
GH/yp				

CDM
Camp Dresser & McKee
1925 Polaris Oaks Way, Suite 300
San Jose, California 95131
408/261-1000

OLIVENHAIN
Municipal Water District
1966 Olivenhain Road
Encinitas, CA 92024 (760)753-8466

DAVID C. MCCOLLOM WTP
LT2 IMPROVEMENTS


RESIDUALS HANDLING BUILDING SECTIONS AND DETAILS

CDM
Camp Dresser & McKee
1925 Polaris Oaks Way, Suite 300
San Jose, California 95131
408/261-1000

CONFORMED

SHEET 85 OF SHEETS	7S-7
WO 179950	

DWG: P:\Projects\01000\172_Improvements\04_Structure\10_CDD\172566-DCMWP.LT2-75-09.dwg
DATE: Jun 15, 2011 2:20pm
USER: jorquast
PREFS: 73556-DCMWP.LT2-75-09.dwg



REF EL 0'-0" =
EL 806.88 (TYP)


FLOOR SLOPES
PLAN
3/16" = 1'-0"

NOTES:

1. FOR GENERAL STRUCTURAL NOTES AND TYPICAL STRUCTURAL DETAILS SEE SHEETS S-1 THROUGH S-7.
2. FOR ADDITIONAL INFORMATION ON THE FOUNDATION PLAN SEE SHEET 7S-1.
3. SL INDICATES DIRECTION OF SLOPED CONCRETE.
4. FOR TOP OF CONCRETE ELEVATIONS AT PADS SEE MECHANICAL DRAWINGS.
5. PROVIDE NON-SHRINK GROUT CRICKET AROUND CONCRETE PADS AS NEEDED FOR WATER TO FLOW AWAY FROM THE PAD.

BID SCHEDULE B

ORIGINAL SCALE IN INCHES



CDM	Boyer & Patel, Inc. 1825 Palmer Oaks Way, Suite 300 San Diego, California Tel: (619) 444-7700 Fax: (619) 444-7701 consulting • engineering • construction • operations	DESIGN	CT	DRAWN	JN	CHECK	GH/YP
		MARK	Δ				
		DATE	6/13	BY	IEC	ADDENDUM	2
		REVISIONS					
OLIVERBRAIN	Michael R. Oliver 1908 Olivaria Road Encinitas, CA 92024 (760) 750-4468	DAVID C. McCOLLOM WTP LT2 IMPROVEMENTS					
RESIDUALS HANDLING BUILDING FLOOR SLOPE PLAN		SHEET 87 / 218 OF SHEETS					
		7S-9 WO 179950					

RF1-00105

NOTES:

1. FOR CONTINUATION, REFER TO DRAWING E
2. CENTRIFUGE MAIN AND BACK DRIVES SHALL ASSOCIATED CONTROL PANELS. EXACT LOCATION TO BE DETERMINED IN THE FIELD. COORDINATE WIRING REQUIREMENTS WITH POLYBLEND UNIT MAINTENANCE.
3. CENTRIFUGE FEED PUMPS SHALL BE CONTAINED INSIDE RH FACILITY. VFDs SHALL BE CONTAINED INSIDE RH FACILITY.
4. CONTRACTOR SHALL COORDINATE ALL INSTALLATION REQUIREMENTS WITH POLYBLEND UNIT MAINTENANCE.
5. ALL 120V CIRCUITS AND RECEPTACLES SHALL BE FED FROM PANEL "LP-RH".
6. CENTRIFUGE NO. 2 AND ALL ASSOCIATED ELECTRICAL COMPONENTS SHALL BE PART OF PREVIOUS NOTE 6

HOA not required.
Stub to 2 ea.
individual J-boxes
and sealtight to
owner provided
equipment.

5' x 5' Polymer
Scale. Located 6"
east from inside
FOC.

CONDUIT AND WIRE LEGEND
(NUMBERS REFERENCE THIS SHEET ONLY)


NO.	DESCRIPTION
①	3/4" C., 2#12, 1#12G.
②	3/4" C., 1-2/C#18T.S.
③	1" C., VENDOR CABLE
④	3/4" C., 3#8, 1#10G.
⑤	2" C., 4#1, 1#8G.
⑥	3 1/2" C., 200#14, 1#14G.

NO.	DESCRIPTION
⑦	3/4" C., 2-2/C#18T.S.
⑧	1" C., 10#14, 1#14G.
⑨	1" C., 20#14, 1#14G.
⑩	1" C., 4-2/C#18T.S.
⑪	3/4" C., 3#12, 1#12G.
⑫	3/4" C., 2#14, 1#14G.
⑬	2" C., 10-2/C#18T.S.
⑭	1" C., CAT 6 CABLE

Owner furnished
rack will include
Mixer timer,
Solenoid, Pump
and Scale
Readout.

Conduit to RHB to
be stubbed to
owner furnished
rack with the 2
other stubs
identified above.

Consolidate LP-RH
conduits.





NOTES:

- FOR CONTINUATION, REFER TO DRAWING E-2.
- CENTRIFUGE MAIN AND BACK DRIVES SHALL BE CONNECTED TO ASSOCIATED CONTROL PANELS. EXACT LOCATION TO BE DETERMINED IN THE FIELD. COORDINATE WIRING REQUIREMENTS WITH MANUFACTURER.
- CENTRIFUGE FEED PUMPS SHALL BE CONNECTED TO VFDS LOCATED INSIDE RH FACILITY. VFDS SHALL BE CONNECTED TO MCC-5.
- CONTRACTOR SHALL COORDINATE ALL INSTRUMENT FIELD WIRING REQUIREMENTS WITH POLYBLEND UNIT MANUFACTURER.
- ALL 120V CIRCUITS AND RECEPTACLES SHALL BE FED FROM PANEL "LP-RH".
- CENTRIFUGE NO. 2 AND ALL ASSOCIATED ELECTRICAL COMPONENTS SHALL BE PART OF BID SCHEDULE C.
PREVIOUS NOTE 6 DELETED.

CONDUIT AND WIRE LEGEND (NUMBERS REFERENCE THIS SHEET ONLY)	
NO.	DESCRIPTION
①	3/4"C., 2#12, 1#12G.
②	3/4"C., 1-2/C#16T.S.
③	1"C., VENDOR CABLE
④	3/4"C., 3#6, 1#10G.
⑤	2"C., 4#1, 1#8G.
⑥	3 1/2"C., 200#14, 1#14G.

NO.	DESCRIPTION
⑦	3/4"C., 2-2/C#16T.S.
⑧	1"C., 10#14, 1#14G.
⑨	1"C., 20#14, 1#14G.
⑩	1"C., 4-2/C#16T.S.
⑪	3/4"C., 3#12, 1#12G.
⑫	3/4"C., 2#14, 1#14G.
⑬	2"C., 10-2/C#16T.S.
⑭	1"C., CAT 6 CABLE



POWER AND GROUNDING
PLAN
1/4" = 1'-0"

BID SCHEDULE B

DAVID C. MCCOLLOM WTP
LT2 IMPROVEMENTS

ELECTRICAL R.H. BUILDING
POWER AND GROUNDING PLAN

OLIVER HAIN
Municipal Water District
1866 Olivarian Road
Escondido, CA 92024 (760) 752-6468

CDM
Camp Dresser & McKee
1655 River Street
San Jose, CA 95128
Tel: (408) 438-7750
Fax: (408) 438-7750
www.cdm.com

CONFORMED

REVISIONS	DATE	BY	MARK	DESIGN	DRAWN	CHECK	MM
ADDENDUM 6	6/11	IEC	Δ	MF	MF		
ADDENDUM 7	6/11	IEC	Δ	MF	MF		

SHEET
179
OF SHEETS
7E-1
WO 179950

DWG: P:\projects\OAWD\0002\000x.LT2\Conformed\SanDiego\DWG\LT2\LT2-1.dwg USER: jrodalast
DATE: Jun 15, 2011 3:22pm XREFS: 7866-DOWMTP-LT2-MSP-RES-BLDG01 7866-DOWMTP-LT2-A-H-SOLIDS 7866-DOWMTP-LT2-S-NP-RHD02

DCMWTP Active Assets

Asset	Description	Class	Commission Date
ACCT - 20097175000-1	RPP WTR TREATMENT PLANT #1	BACKFLOW	1/15/2009
ACCT - 20097175000-2	RPP WTR TREATMENT PLANT #1	BACKFLOW	1/15/2009
ACCT - 20097180000-1	RPP WTR TREATMENT PLANT #2	BACKFLOW	1/15/2009
ACCT - 20097180000-3	RPP WTR TREATMENT PLANT #2	BACKFLOW	1/15/2009
ACCT - 20097180000-4	RPP WTR TREATMENT PLANT #2	BACKFLOW	8/12/2010
ACCT - 20097180000-5	RPP WTR TREATMENT PLANT #2	BACKFLOW	8/12/2010
AFIF SITE	Ammonia Feed Injection Facility Site	SITE	1/28/2010
AFIF.AC.AC-1	AFIF Air Conditioning Unit AC-1	HVAC	11/1/2006
AFIF.BPV-6200	BPV-6200 Back Pressure Valve	VALVE	1/1/2016
AFIF.CHEM.NH3.CP-FP1	Ammonia Feed Pump P-6143 Control Panel	CONTROL	10/22/2015
AFIF.CHEM.NH3.CP-FP2	Control Panel Ammonia Feed Pump 2	OIT	1/1/2016
AFIF.CHEM.NH3.P-6143	P-6143 Ammonia Feed Pump 1	PUMP	3/2/2016
AFIF.CHEM.NH3.P-6143.PIPING	P-6143 Ammonia Feed Pump 1 Piping	PIPING	1/1/2016
AFIF.CHEM.NH3.P-6144	P-6144 Ammonia Feed Pump 2	PUMP	1/1/2016
AFIF.CHEM.NH3.P-6144.PIPING	P-6144 Ammonia Feed Pump 2 Piping	PIPING	1/1/2016
AFIF.CHEM.NH3.PIPING	PIPING Ammonia Storage Tank Piping	PIPING	1/1/2016
AFIF.CHEM.NH3.TK-6260	TK-6260 Ammonia Bulk Storage Tank	TANK	1/1/2016
AFIF.CHEM.NH3.TK-6280	TK-6280 Ammonia Scrubber Tank	TANK	1/1/2016
AFIF.INJ.VAULT	Ammonia Feed Injection Facility Vault	VAULT	3/25/2016
AFIF.INJ.VAULT.HATCH	Ammonia Feed Injection Vault Hatch	HATCH	1/1/2016
AFIF.INJ.VAULT.MIXINGPADDLE	Ammonia Feed Injection Vault Mixing Paddle	MIXER	1/1/2016
AFIF.INJ.VAULT.PIPING	Ammonia Feed Injection Vault Piping	PIPING	1/1/2016
AFIF.INJ.VAULT.QUILL	Ammonia Feed Injection Vault Quill	QUILL	1/1/2016
AFIF.INST.FLUOR.AIT-6255.PIPIN	AIT-6255 Fluoride residual analyzer Piping	PIPING	1/1/2016
AFIF.INST.FREECL2.AIT-6251.PIP	AIT-6251 Free Cl2 residual analyzer Piping	PIPING	1/1/2016
AFIF.INST.PIPING	Analyzer Sample Return Piping	PIPING	2/2/2007
AFIF.INST.POST.AIT-6253.PIPING	AIT-6253 APA-6000 Monochloramine analyzer Piping	PIPING	1/1/2016
AFIF.INST.TOTALCL2.AIT-6254.PI	AIT-6254 Total Cl2 residual analyzer Piping	PIPING	1/1/2016
AFIF.OIT	AFIF Operator Interface Terminal	OIT	5/14/2015
AFIF.PR-6200	PRV-6200 Pressure Relief Valve	VALVE	1/1/2016
AFIF.TK-6250	TK-6250 Ammonia Facility Holding Tank	TANK	1/1/2016
EYEWASH STATION AT FLOC BULK	EYEWASH AT FLOC BULK TANK AREA		1/30/2009
PIPING RAW WATER HYPO	WTP.CHEM.RW.HYPO.PIPING	PIPING	2/1/2002
VA57-VIBRATION	WTP Vibration Analysis	*	1/14/2010
WAAIF1001	AFIF GENERATOR BATTERY CHARGER	ELEC	3/18/2009
WAAIF1031	AFIF AUTOMATIC GATE SYSTEM	SECURITY	3/18/2009
WAAIF1033	AFIF AMMONIA SOLUTION DAY TANK	TANK	3/18/2009
WAAIF1036	AFIF GENERATOR TRANSFER SWITCH MAIN BREAKER	ELEC	3/18/2009
WAAIF1037	AFIF DIAPHRAGM METERING PUMP #1 P-6261	PUMP	3/18/2009
WAAIF1038	AFIF DIAPHRAGM METERING PUMP #2 P-6262	PUMP	3/18/2009
WAAIF1039	AFIF AMMONIA SOLUTION TRANSFER PUMP #1 P-6230	PUMP	3/18/2009
WAAIF1040	AFIF AMMONIA SOLUTION TRANSFER PUMP #2 P-6240	PUMP	3/18/2009
WAAIF1041	AFIF SAMPLE RETURN PUMP	PUMP	3/18/2009
WAAIF1044	AFIF SAMPLE RETURN TANK	TANK	3/18/2009
WAAIF1055	AFIF AMMONIUM SULFATE FEEDER 6210 AIR COMPRESSOR	COMPRESS	3/18/2009
WAAIF1056	AFIF AMMONIUM SULFATE FEEDER 6220 AIR COMPRESSOR	COMPRESS	3/18/2009
WAAIF1063	AFIF AMMONIA INJECTION DIFFUSER #1 Northside	DIFFUSER	3/18/2009
WAAIF1064	AFIF AMMONIA INJECTION DIFFUSER #2 Southside	DIFFUSER	3/18/2009
WAAIF1065	AFIF Building	FACILITY	3/23/2009

DCMWTP Active Assets

WAAFI1074	AFIF 480/3 GENERATOR MOUNTED MAIN BREAKER 100 AMP	ELEC	3/25/2009
WAAFI1075	AFIF BACKUP GENERATOR	GENERATE	3/25/2009
WAAFI6144	AFIF AMMONIA SOLUTION PUMP P-6144	PUMP	5/15/2013
WAAFIGATECAM	AFIF Gate Camera	SECURITY	6/17/2009
WAWTPGATECAM	WTP Horsewall Gate Camera	SECURITY	6/17/2009
WAWTPGATECAM2	WTP green slide gate camera	SECURITY	2/4/2021
WAWTPGATECOMM	WTP Horsewall Gate PBX Communications Interface	SECURITY	6/17/2009
WAWTPGATEDSX	WTP Horsewall Gate DSX System	SECURITY	6/17/2009
WAWTPGATEOPIN	WTP Horsewall Gate Operator - Enter	SECURITY	6/17/2009
WAWTPGATEOPOUT	WTP Horsewall Gate Operator - Exit	SECURITY	6/17/2009
WAWTPGATERDIN	WTP Horsewall Gate Reader - Enter	SECURITY	6/17/2009
WAWTPGATERDOUT	WTP Horsewall Gate Reader - Exit	SECURITY	6/17/2009
WTP 2ND STG REJECT TSS	2ND STAGE REJECT TSS METER	XDUCER	1/25/2010
WTP 3RD STG EFFLUENT TSS	3RD STAGE EFFLUENT TSS METER	XDUCER	7/1/2010
WTP 4TH STG EFFLUENT TSS	4TH STAGE EFFLUENT TSS METER	XDUCER	7/1/2010
WTP FCV-8860-A	Backpulse Tank Feed FCV 8860-A	VALVE	12/22/2010
WTP FCV-8860-B	Backpulse Tank Feed FCV 8860-B	VALVE	12/22/2010
WTP FEED PRIMING VACUUM PIPING	ZW1 & ZW2 VACUUM PIPING (FEED & MIT PRIMING)	PIPING	12/1/2010
WTP GENERATOR	GENERATOR, WTP	GENERATE	11/17/2009
WTP GENERATOR-1	GENERATOR FUEL TANK, WTP	TANK	6/9/2016
WTP HIGH BAY LITE (42)	WTP High Bay Lights (42) high press. sodium 400 watt 277V	FACILITY	7/13/2010
WTP LIT-7226	LIT-7226 1st stage reject channel level transmitter	XDUCER	11/22/2011
WTP LIT-7226S	LIT-7226 1st stage reject channel level transmitter spare	XDUCER	11/22/2011
WTP M-2010 MIXER	M-2010 CIP SYSTEM STATIC MIXER	MIXER	1/12/2010
WTP MAIN ELEC ROOM	WTP Main Electric Room	FACILITY	10/21/2008
WTP PERMEATE PUMP VFDS	WTP Permeate Pump VFD's 1-8	VFD	4/30/2009
WTP PIT- 9220A VAC SYS	PIT-9220A VACUUM SYS-PRIMING (ASV)	PIPING	12/1/2010
WTP PIT- 9220B VAC SYS	PIT-9220B VACUUM SYS-PRIMING (ZW1-1)	PIPING	12/1/2010
WTP PIT- 9221 VAC SYS	PIT-9221 VACUUM SYS-SIPHON (ASV)	PIPING	12/1/2010
WTP PRV NO.1 DCW	WTP PRV NO.1 DCW 1.25" Lowflow	VALVE	6/1/2002
WTP PRV NO.2 DCW	WTP PRV NO.2 DCW 2.5" Highflow	VALVE	6/1/2002
WTP SIPHON VACUUM PIPING	ZW1 & ZW2 VACUUM PIPING (FEED SIPHON)	PIPING	12/1/2010
WTP SM-35 STATIC MIXER	SM-35 STATIC MIXER - CFE (HYPO)	MIXER	1/12/2010
WTP SM-36 STATIC MIXER	SM-36 STATIC MIXER - CFE (AMMONIA)	MIXER	1/12/2010
WTP SM-85-A STATIC MIXER	SM-85-A STATIC MIXER - RAW (HYPO & ACH)	MIXER	1/12/2010
WTP SM-85-B STATIC MIXER	SM-85-B STATIC MIXER - RAW (NOT USED)	MIXER	1/12/2010
WTP-230004-CV	1st Stage P-35-2 Check Valve	VALVE	8/17/2010
WTP-GEN-POWER-MONITOR	WTP Generator Emergency Power Monitor	CONTROL	6/22/2012
WTP-PUMP MOTORS	WTP Pump Motor Parent Asset (ALL)	MOTOR	12/4/2008
WTP-SAFETY-1	BODY HARNESS, LARGE	SAFETY	12/1/2018
WTP-SAFETY-10	FALL ARREST/RETRIEVAL SYSTEM	SAFETY	8/26/2019
WTP-SAFETY-11	CONFINED SPACE BLOWER/FAN	SAFETY	6/1/2019
WTP-SAFETY-12	CONFINED SPACE BLOWER/FAN	SAFETY	6/1/2019
WTP-SAFETY-13	CONFINED SPACE BLOWER/FAN	SAFETY	7/1/2010
WTP-SAFETY-14	Fall Arrest System	SAFETY	7/30/2013
WTP-SAFETY-15	Fall Arrest System	SAFETY	7/30/2013
WTP-SAFETY-16	Fall Arrest System	SAFETY	7/30/2013
WTP-SAFETY-17	Fall Arrest System	SAFETY	7/30/2013
WTP-SAFETY-18	Fall Arrest System	SAFETY	7/30/2013
WTP-SAFETY-2	BODY HARNESS, LARGE	SAFETY	11/1/2018
WTP-SAFETY-3	BODY HARNESS, MEDIUM	SAFETY	6/7/2019
WTP-SAFETY-4	BODY HARNESS, MEDIUM	SAFETY	8/1/2012
WTP-SAFETY-5	BODY HARNESS, MEDIUM	SAFETY	8/1/2012

DCMWTP Active Assets

WTP-SAFETY-6	BODY HARNESS, MEDIUM	SAFETY	5/1/2017
WTP-SAFETY-7	BODY HARNESS, M/L	SAFETY	11/1/2011
WTP-SAFETY-8	BODY HARNESS, M/L	SAFETY	8/1/2010
WTP-SAFETY-9	FALL ARREST/RETRIEVAL SYSTEM	SAFETY	6/1/2019
WTP.DAVIT CRANE.DC-1	DAVIT CRANE.DC-1 (WTP) 1/2-TON	CRANE	1/1/2016
WTP.DAVIT CRANE.DC-2	DAVIT CRANE.DC-2 (RHB) 1/2-TON	CRANE	1/1/2016
WTP.AC-AC-MIT96B-AIRDRY	WTP.AC-MIT96B AirDryer	*	1/1/2013
WTP.AC.3H1	AC-3H1 INDOOR EVAP	EVAP	1/1/2016
WTP.AC.3H2	AC-3H2 INDOOR EVAP	EVAP	1/1/2016
WTP.AC.AC.1	AC.AC-1 AIR CONDITIONING UNIT	HVAC	1/1/2016
WTP.AC.AC.2	AC.AC-2 AIR CONDITIONING UNIT	HVAC	1/1/2016
WTP.AC.AC.MIT96A	WTP.AC.AC.MIT96A Air Compressor Oil Free	COMPRESS	1/1/2012
WTP.AC.AC.MIT96A-AIRDRY	WTP.AC.AC.MIT96A AIR DRYER	DRYER	1/1/2016
WTP.AC.AC.MIT96A-MTR	WTP.AC.AC.MIT96A MOTOR	MOTOR	1/1/2016
WTP.AC.AC.MIT96B-MTR	WTP.AC.AC.MIT96B MOTOR	MOTOR	1/1/2016
WTP.AC.AC9675A-COMP-1	PLANT AIR COMPRESSOR AC9675-A	COMPRESS	6/3/2019
WTP.AC.AC9675A-COMP-2	PLANT AIR DRYER AC9675-A	DRYER	6/3/2019
WTP.AC.AC9675B-COMP-1	PLANT AIR COMPRESSOR AC9675-B	COMPRESS	6/3/2019
WTP.AC.AC9675B-COMP-2	PLANT AIR DRYER AC9675-B	DRYER	6/3/2019
WTP.AC/CU.3H1	AC-3H-01 HEAT PUMP EVAPORATOR Elec. Rm. 2	HVAC	12/3/2012
WTP.AC/CU.3H2	AC-3H-02 HEAT PUMP EVAPORATOR Elec. Rm. 2	HVAC	8/21/2015
WTP.AHU.AHU.1A	AIR HANDLER AHU-1A (ERT ROOM)	AIRHANDLR	1/1/2016
WTP.AHU.AHU.2A	AIR HANDLER AHU-2A (BLOWER ROOM)	AIRHANDLR	1/1/2016
WTP.AHU.AHU.2B	AIR HANDLER AHU-2B (BLOWER ROOM)	AIRHANDLR	1/1/2016
WTP.AHU.MTR-AHU.1A	AHU-1A MOTOR	MOTOR	1/1/2016
WTP.AHU.MTR-AHU.2A	AHU-2A MOTOR	MOTOR	1/1/2016
WTP.AHU.MTR-AHU.2B	AHU-2B MOTOR	MOTOR	1/1/2016
WTP.AIR.AC-3	AC-3 Auxillary Compressor	COMPRESS	1/1/2016
WTP.AIR.SV-9671	SV-9671 Auxillary Air Solenoid valve from surge tank	VALVE	1/1/2016
WTP.AIR.SV-9672	SV-9672 Auxillary Air Solenoid valve to surge tank	VALVE	1/1/2016
WTP.BLWR.B-85-2A	WTP.BLOWER B-85-2b A/C repair	BLOWER	10/5/2017
WTP.BLWR.85-2A	WTP 2ND STAGE BLOWER B-85-2A	BLOWER	12/20/2013
WTP.BLWR.ACU-1A	B-85-1A.ACU Air Conditioning Unit	HVAC	1/1/2016
WTP.BLWR.ACU-1B	B-85-1B.ACU Air Conditioning Unit	HVAC	1/1/2016
WTP.BLWR.ACU-2A	B-85-2A.ACU Air Conditioning Unit	HVAC	1/1/2016
WTP.BLWR.ACU-2B	B-85-2B.ACU Air Conditioning Unit	HVAC	1/1/2016
WTP.BLWR.B-85-1A	WTP 1ST STAGE BLOWER B-85-1A	BLOWER	2/18/2015
WTP.BLWR.B-85-1B	WTP 1ST STAGE BLOWER B-85-1B	BLOWER	2/18/2015
WTP.BLWR.B-85-2A	B-85-2A 2nd Stage BLOWER Package	BLOWER	1/1/2016
WTP.BLWR.B-85-2B	WTP 2ND STAGE BLOWER B-85-2B	BLOWER	12/20/2013
WTP.BLWR.BFV-8566	BFV-8566 2nd Stage BLOWER Downstream Valve	VALVE	1/1/2016
WTP.BLWR.BFV-8568	BFV-8568 1st Stage BLOWER Downstream Valve	VALVE	1/1/2016
WTP.BLWR.BFV-8580-1A	BFV-8580-1A Downstream Isolation Valve	VALVE	1/1/2016
WTP.BLWR.BFV-8580-1B	BFV-8580-1B Downstream Isolation Valve	VALVE	1/1/2016
WTP.BLWR.BFV-8580-2A	BFV-8580-2A Downstream Isolation Valve	VALVE	1/1/2016
WTP.BLWR.BFV-8580-2B	BFV-8580-2B Downstream Isolation Valve	VALVE	1/1/2016
WTP.BLWR.COMP-85-1A	B-85-1A 1st Stage BLOWER Compressor	COMPRESS	1/1/2016
WTP.BLWR.COMP-85-1B	B-85-1B 1st Stage BLOWER Compressor	COMPRESS	1/1/2016
WTP.BLWR.CV-8585-1A	CV-8585-1A Swing Check Valve	VALVE	1/1/2016
WTP.BLWR.CV-8585-1B	CV-8585-1B Swing Check Valve	VALVE	1/1/2016
WTP.BLWR.CV-8585-2A	CV-8585-2A Swing Check Valve	VALVE	1/1/2016
WTP.BLWR.CV-8585-2B	CV-8585-2B Swing Check Valve	VALVE	1/1/2016
WTP.BLWR.DPI-D-8540-1A	DPI-8540-1A-Discharge Differential Pressure Gauge	PIT	1/1/2016
WTP.BLWR.DPI-I-8540-1A	DPI-8540-1A-Inlet Filter Differential Pressure Gauge	PIT	1/1/2016
WTP.BLWR.F-8504-2A	F-8504-2A Discharge Silencer	FILTER	1/1/2016

DCMWTP Active Assets

WTP.BLWR.F-D-8504-1A	F-8504-1A-Discharge Silencer	FILTER	1/1/2016
WTP.BLWR.F-D-8504-1B	F-8504-1B Discharge Silencer	FILTER	1/1/2016
WTP.BLWR.F-D-8504-2B	F-8504-2B Discharge Silencer	FILTER	1/1/2016
WTP.BLWR.F-D-8540-1B	DPI-8540-1B-Discharge Differential Pressure Gauge	PIT	1/1/2016
WTP.BLWR.F-I-8504-1A	F-8504-1A-Inlet Silencer w/ Filter	FILTER	1/1/2016
WTP.BLWR.F-I-8504-2B	F-8504-2B Inlet Silencer W/ Filter	FILTER	1/1/2016
WTP.BLWR.F-I-8540-1B	F-8540-1B-Inlet Silencer W/ Filter	PIT	1/1/2016
WTP.BLWR.MTR-85-1A	MTR-85-1A BLOWER Motor	MOTOR	1/1/2016
WTP.BLWR.MTR-85-1B	MTR-85-1B BLOWER Motor	MOTOR	1/1/2016
WTP.BLWR.MTR-85-2A	MTR-85-2A BLOWER Motor	MOTOR	1/1/2016
WTP.BLWR.MTR-85-2B	MTR-85-2B BLOWER Motor	MOTOR	1/1/2016
WTP.BLWR.PIPE	BLOWER Piping	PIPING	1/1/2016
WTP.BLWR.PR-1-8590-1A	PRV-1-8590-1A Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-1-8590-1B	PRV-1-8590-1B Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-1-8590-2A	PRV-1-8590-2A Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-1-8590-2B	PRV-1-8590-2B Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-2-8590-1A	PRV-2-8590-1A Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-2-8590-1B	PRV-2-8590-1B Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-2-8590-2A	PRV-2-8590-2A Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-2-8590-2B	PRV-2-8590-2B Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-3-8590-1A	PRV-3-8590-1A Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-3-8590-1B	PRV-3-8590-1B Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-3-8590-2A	PRV-3-8590-2A Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.PR-3-8590-2B	PRV-3-8590-2B Pressure Relief Valve	VALVE	1/1/2016
WTP.BLWR.VFD-85-1A	B-85-1A VFD	VFD	1/1/2016
WTP.BLWR.VFD-85-1B	B-85-1B VFD	VFD	1/1/2016
WTP.BLWR.VFD-85-2A	B-85-2A VFD	VFD	1/1/2016
WTP.BLWR.VFD-85-2B	B-85-2B VFD	VFD	1/1/2016
WTP.BP.BFV-380-1A	BFV-380-1A Upstream Isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-380-1B	BFV-380-1B Downstream Isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-380-2A	BFV-380-2A Upstream Isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-380-2B	BFV-380-2B Downstream Isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-8888-A	BFV-8888-A Tank A Downstream Isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-8888-B	BFV-8888-B Tank B Downstream Isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-8889-A	BFV-8889-A Tank A Upstream Isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-8889-B	BFV-8889-B Tank B Upstream Isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-8898-A	BFV-8898-A FCV A Upstream isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-8898-B	BFV-8898-B FCV B Upstream isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-8899-A	BFV-8899-A FCV A Downstream isolation Valve	VALVE	1/1/2016
WTP.BP.BFV-8899-B	BFV-8899-B FCV B Downstream isolation Valve	VALVE	1/1/2016
WTP.BP.CV-380-1	CV-380-1 Check Valve	VALVE	1/1/2016
WTP.BP.CV-380-2	CV-380-2 Check Valve	VALVE	1/1/2016
WTP.BP.FCV-8860-A	FCV-8860-A FCV A	VALVE	1/1/2016
WTP.BP.FCV-8860-B	FCV-8860-B FCV B	VALVE	1/1/2016
WTP.BP.FCV-8974	FCV-8974 2nd Stage Backpulse FCV	VALVE	1/1/2016
WTP.BP.P-380-1	P-380-1 First Stage Backpulse Pump	PUMP	1/1/2016
WTP.BP.P-380-1 MOTOR	P-380-1 First Stage Backpulse Pump Motor	MOTOR	1/1/2016
WTP.BP.P-380-2	P-380-2 First Stage Backpulse Pump	PUMP	1/1/2016
WTP.BP.P-380-2 MOTOR	P-380-2 First Stage Backpulse Pump Motor	MOTOR	1/1/2016
WTP.BP.PIPING	Backpulse Piping	PIPING	1/1/2016
WTP.BP.PR-380	PRV-380 1st Stage Backpulse PRV	VALVE	1/1/2016
WTP.BP.TK-88-A	TK-88-A Backpulse Tank A	TANK	1/1/2016
WTP.BP.TK-88-B	TK-88-B Backpulse Tank B	TANK	1/1/2016
WTP.BRIDGE CRANE.BC-1	BRIDGE CRANE.BC-1. 3- TON	CRANE	1/1/2016
WTP.BWEQ-P-410-2	Second Stage return pump P-410-2	PUMP	1/1/2013
WTP.BWEQ-P-410-3	Second Stage return pump 410-3		1/1/2013
WTP.BWEQ.BFV-410-1	BFV-410-1 Flow to Second Stage Membranes	VALVE	1/1/2016
WTP.BWEQ.BFV-410-1A	BFV-410-1A upstream P-410-1	VALVE	1/1/2016

DCMWTP Active Assets

WTP.BWEQ.BFV-410-1B	BFV-410-1B downstream P-410-1	VALVE	1/1/2016
WTP.BWEQ.BFV-410-2	BFV-410-2 Flow to Second Stage Membranes	VALVE	1/1/2016
WTP.BWEQ.BFV-410-2A	BFV-410-2A upstream P-410-2	VALVE	1/1/2016
WTP.BWEQ.BFV-410-2B	BFV-410-2B downstream P-410-2	VALVE	1/1/2016
WTP.BWEQ.BFV-410-3A	BFV-410-3A upstream P-410-3	VALVE	1/1/2016
WTP.BWEQ.BFV-410-3B	BFV-410-3B downstream P-410-3	VALVE	1/1/2016
WTP.BWEQ.BFV-415-1A	BFV-415-1B downstream P-415-1	VALVE	1/1/2016
WTP.BWEQ.BFV-415-2A	BFV-415-2A upstream P-415-2	VALVE	1/1/2016
WTP.BWEQ.BFV-415-2B	BFV-415-2B downstream P-415-2	VALVE	1/1/2016
WTP.BWEQ.BFV-8401-1	BFV-8401-1 Flow from Third Stage Decant	VALVE	1/1/2016
WTP.BWEQ.BFV-8401-2	BFV-8401-2 Flow from First Stage Reject	VALVE	1/1/2016
WTP.BWEQ.BFV-8401-3	BFV-8401-3 Tank Drain Valve	VALVE	1/1/2016
WTP.BWEQ.CV-410-1	CV-410-1 Check Valve downstream P-410-1	VALVE	1/1/2016
WTP.BWEQ.CV-410-2	CV-410-2 Check Valve downstream P-410-2	VALVE	1/1/2016
WTP.BWEQ.CV-410-3	CV-410-3 Check valve downstream P-410-3	VALVE	1/1/2016
WTP.BWEQ.CV-415-1	CV-415-1 Check Valve downstream P-415-1	VALVE	1/1/2016
WTP.BWEQ.CV-415-2	CV-415-2 Check Valve downstream P-415-2	VALVE	1/1/2016
WTP.BWEQ.MTR-410-1	MTR-410-1 Second Stage Return Motor	MOTOR	1/1/2016
WTP.BWEQ.MTR-410-2	MTR-410-2 Second Stage Return Motor	MOTOR	1/1/2013
WTP.BWEQ.MTR-410-3	MTR-410-3 Second Stage Return Motor	MOTOR	1/1/2016
WTP.BWEQ.MTR-415-1	MTR-415-1 Recirculation Mixing Motor	MOTOR	1/1/2016
WTP.BWEQ.MTR-415-2	MTR-415-2 Recirculation Mixing Motor	MOTOR	1/1/2016
WTP.BWEQ.P-410-1	P-410-1 Second Stage Return Pump #1	PUMP	1/1/2016
WTP.BWEQ.P-410-1/2	P-410-1 Second Stage Return Pump Motor #1	MOTOR	6/26/2019
WTP.BWEQ.P-410-2	P-410-2 Second Stage Return Pump #2	PUMP	1/1/2016
WTP.BWEQ.P-410-2/3	P-410-2 Second Stage Return Pump Motor #2	MOTOR	4/2/2019
WTP.BWEQ.P-410-3	P-410-3 Second Stage Return Pump #3	PUMP	1/1/2016
WTP.BWEQ.P-410-3/4	P-410-3 Second Stage Return Pump Motor #3	MOTOR	4/28/2020
WTP.BWEQ.P-415-1	P-415-1 Recirculation Mixing Pump	PUMP	1/1/2016
WTP.BWEQ.P-415-1/1	P-415-1 Recirculation Mixing Pump Motor	MOTOR	9/20/2018
WTP.BWEQ.P-415-2	P-415-2 Recirculation Mixing Pump	PUMP	1/1/2016
WTP.BWEQ.P-415-2/2	P-415-2 Recirculation Mixing Pump Motor	MOTOR	9/20/2018
WTP.BWEQ.TNK-8401	TNK-8401-Backwash Equalization Tank	TANK	1/1/2016
WTP.CHEM.ACH.CP-FP-1	Control Panel ACH Feed Pump 1	CONTROL	1/1/2016
WTP.CHEM.ACH.CP-FP-2	Control Panel ACH Feed Pump 2	CONTROL	1/1/2016
WTP.CHEM.ACH.P-815-1	ACH Chemical pump P-815-1	PUMP	1/1/2013
WTP.CHEM.ACH.P-815-2	ACH Chemical Pump P-815-2	PUMP	1/1/2013
WTP.CHEM.ACH.PIPING	PIPING ACH	PIPING	1/1/2016
WTP.CHEM.ACH.TKS	TKS ACH Storage Tank	TANK	1/1/2016
WTP.CHEM.CEB.CP.LCP-310-1	CP CEB Feed Pump Control Panel 310-1	CONTROL	1/1/2016
WTP.CHEM.CEB.CP.LCP-310-2	CP CEB Feed Pump Control Panel 310-2	CONTROL	1/1/2016
WTP.CHEM.CEB.P-310-1	P-310-1 CEB Hypo Pump 1	PUMP	1/1/2016
WTP.CHEM.CEB.P-310-2	P-310-2 CEB Hypo Pump 2	PUMP	1/1/2016
WTP.CHEM.CEB.PIPING	PIPING CEB Hypo	PIPING	1/1/2016
WTP.CHEM.CIP.BISF.CP	CP Bisulfite CIP Feed Pump Control Panel	CONTROL	1/1/2016
WTP.CHEM.CIP.BISF.CP-FP	Control Panel CIP Bisulfite Feed Pumps	CONTROL	1/1/2016
WTP.CHEM.CIP.BISF.P-5341	P-5341 CIP Bisulfite Feed Pump 1	PUMP	1/1/2016
WTP.CHEM.CIP.BISF.P-5342	P-5342 CIP Bisulfite Feed Pump 2	PUMP	1/1/2016
WTP.CHEM.CIP.BISF.PIPING	PIPING CIP Bisulfite	PIPING	1/1/2016
WTP.CHEM.CIP.BISF.TK-5301	TK-5301 CIP Bisulfite Day Tank	TANK	1/1/2016
WTP.CHEM.CIP.CAUSTIC.CP-FP1	Control Panel CIP Caustic Feed Pumps	CONTROL	1/1/2016
WTP.CHEM.CIP.CAUSTIC.P-5541	P-5541 CIP Caustic Feed Pump 1	PUMP	1/1/2016
WTP.CHEM.CIP.CAUSTIC.P-5542	P-5542 CIP Caustic Feed Pump 2	PUMP	1/1/2016
WTP.CHEM.CIP.CAUSTIC.PIPING	PIPING CIP Caustic	PIPING	1/1/2016
WTP.CHEM.CIP.CAUSTIC.TK-5501	TK-5501 CIP Caustic Day Tank	TANK	1/1/2016
WTP.CHEM.CIP.CITRIC.P-6021	CIP Citric Acid Feed Pump P-6021	PUMP	10/23/2015
WTP.CHEM.CIP.CITRIC.PIPING	PIPING CIP Citric	PIPING	1/1/2016
WTP.CHEM.CIP.FCV-315-1	FCV-315-1 CIP Fill Valve	VALVE	3/3/2016
WTP.CHEM.CIP.HYPO.P-5424	P-5424 CIP Hypo Feed Pump	PUMP	1/1/2016

DCMWTP Active Assets

WTP.CHEM.CIP.HYPO.PIPING	PIPING CIP Hypo	PIPING	1/1/2016
WTP.CHEM.FLUOR.CP-FP1	Control Panel Sodium Fluoride Feed Pump 1	CONTROL	1/1/2016
WTP.CHEM.FLUOR.CP-FP2	Control Panel Sodium Fluoride Feed Pump 2	CONTROL	1/1/2016
WTP.CHEM.FLUOR.CP-TP1	Control Panel Sodium Fluoride Transfer Pump 1	CONTROL	1/1/2016
WTP.CHEM.FLUOR.CRANE	Fluoride Loading Platform Hoist/Crane	CRANE	1/1/2012
WTP.CHEM.FLUOR.FFS-TKD-1	FFS-TKD-1 Sodium Fluoride Day Tank	TANK	1/1/2016
WTP.CHEM.FLUOR.FFS-TKS-1	FFS-TKS-1 Sodium Fluoride Feed Saturation Tanks	TANK	1/1/2013
WTP.CHEM.FLUOR.P-110	P-110 Sodium Fluoride Transfer Pump 1	PUMP	1/1/2016
WTP.CHEM.FLUOR.P-210	P-210 Sodium Fluoride Feed Pump 1	PUMP	6/7/2016
WTP.CHEM.FLUOR.P-220	P-220 Sodium Fluoride Feed Pump 2	PUMP	6/7/2016
WTP.CHEM.FLUOR.PIPING	PIPING Sodium Fluoride	PIPING	1/1/2016
WTP.CHEM.FLUOR.STORAGE	Sodium Fluoride Storage	CHEM	7/1/2013
WTP.CHEM.FLUOR.SV-055	SV-055 SF Saturation Tank Soft Water Supply Solenoid Valve	VALVE	1/1/2016
WTP.CHEM.FW.HYPO.CP-FP-1	Control Panel Finished Water Hypo Feed Pump 1	CONTROL	1/1/2016
WTP.CHEM.FW.HYPO.P-5445	P-5445 Finished Water Hypo Feed Pump 1	PUMP	1/1/2016
WTP.CHEM.FW.HYPO.P-5445-MTR1	P-5445 Finished Water Hypo Feed Motor 1	MOTOR	1/1/2016
WTP.CHEM.FW.HYPO.P-5446	P-5446 Finished Water Hypo Feed Pump 2	PUMP	1/1/2016
WTP.CHEM.FW.HYPO.P-5446-MTR1	P-5446 Finished Water Hypo Feed Pump Motor 2	MOTOR	1/1/2016
WTP.CHEM.FW.HYPO.PIPING	Piping Finished Water Hypo	PIPING	4/14/2015
WTP.CHEM.FW.WTP.CHEM.FW.CAUSTI	WTP Finished Water Caustic Feed System	CHEM	10/17/2019
WTP.CHEM.RW.HYPO.CP-FP1	Control Panel Raw Water Hypo Feed	CONTROL	1/1/2016
WTP.CHEM.RW.HYPO.P-5441	P-5441 Raw water hypo feed pump 1	PUMP	1/1/2013
WTP.CHEM.RW.HYPO.P-5441-MTR1	P-5441 Raw Water Hypo Feed Motor 1	MOTOR	1/1/2016
WTP.CHEM.RW.HYPO.P-5442	P-5442 Raw Water Hypo feed pump2	PUMP	9/8/2015
WTP.CHEM.RW.HYPO.P-5442-MTR2	P-5442 Raw Water Hypo Feed Motor 2	MOTOR	1/1/2016
WTP.CHEM.RW.HYPO.PIPING	PIPING Raw Water Hypo	PIPING	2/2/2016
WTP.CIP.BFV-315C	BFV-315 Butterfly valve CIP tanks transfer	VALVE	1/1/2016
WTP.CIP.E-315	E-315 CIP Eductor	EDUCTOR	6/9/2018
WTP.CIP.FV-315-1A	FV-315-1A Potable Water Flow valve CIP Inlet	VALVE	1/1/2016
WTP.CIP.FV-315-1B	FV-315-1B CIP Return Flow valve Inlet	VALVE	1/1/2016
WTP.CIP.FV-315-1C	FV-315-1C Flow valve CIP Outlet	VALVE	1/1/2016
WTP.CIP.FV-315-2A	FV-315-2A Potable Water Flow valve CIP Inlet	VALVE	1/1/2016
WTP.CIP.FV-315-2B	FV-315-2B CIP Return Flow valve Inlet	VALVE	1/1/2016
WTP.CIP.FV-315-2C	FV-315-2C Flow valve CIP Outlet	VALVE	1/1/2016
WTP.CIP.P-315-1	CIP.P-315-1 CIP Pump #1	PUMP	1/1/2012
WTP.CIP.P-315-2	WTP.CIP.P-315-2 CIP Pump #2	PUMP	1/1/2016
WTP.CIP.PIPE	CIP Piping	PIPING	12/1/2012
WTP.CIP.TNK-315-1	CIP.TANK-315-1 CIP Tank #1	TANK	1/1/2016
WTP.CIP.TNK-315-2	CIP.TANK-315-2 CIP Tank #2	TANK	1/1/2016
WTP.CIP.TNK.FCV-315-1	FCV-315-1 Flow Control Valve	VALVE	3/3/2016
WTP.COMP.OILSEP	WTP.PLANT AIR OIL/WATER SEPARATOR	DRYER	3/14/2018
WTP.COMP.OILSEP-1	WTP.PLANT AIR OIL/WATER SEPARATOR-1	DRYER	3/15/2018
WTP.CU.3H1	AC-3H-01 HEAT PUMP CONDENSOR Elec. Rm. 2	HVAC	8/21/2015
WTP.CU.3H2	AC-3H-02 HEAT PUMP CONDENSOR Elec. Rm. 2	HVAC	8/21/2015
WTP.EF.EF.1	EXHAUST FAN EF-1A (RAW WATER HYPO ROOM)	EXHSTFN	1/1/2016
WTP.EF.EF.11	WTP.EF.EF.11 EXHAUST FAN	*	12/2/2013
WTP.EF.EF.2	WTP.EF.EF-2 EXHAUST FAN	*	12/20/2012
WTP.EF.EF.3	EXHAUST FAN EF-3 (FINISHED WATER HYPO ROOM)	EXHSTFN	1/1/2016
WTP.EF.EF.316.1	EXHAUST FAN EF-316.1 (TRAIN 1)	EXHSTFN	1/1/2016
WTP.EF.EF.316.10	EXHAUST FAN EF-316.10 (TRAIN 10)	EXHSTFN	1/1/2016
WTP.EF.EF.316.11	EXHAUST FAN EF-316.11 (SECOND STAGE TRAINS)	EXHSTFN	1/1/2016
WTP.EF.EF.316.2	EXHAUST FAN EF-316.2 (TRAIN 2)	EXHSTFN	1/1/2016
WTP.EF.EF.316.3	EXHAUST FAN EF-316.3 (TRAIN 3)	EXHSTFN	1/1/2016
WTP.EF.EF.316.4	EXHAUST FAN EF-316.4 (TRAIN 4)	EXHSTFN	1/1/2016
WTP.EF.EF.316.5	EXHAUST FAN EF-316.5 (TRAIN 5)	EXHSTFN	1/1/2016

DCMWTP Active Assets

WTP.EF.EF.316.6	EXHAUST FAN EF-316.6 (TRAIN 6)	EXHSTFN	1/1/2016
WTP.EF.EF.316.7	EXHAUST FAN EF-316.7 (TRAIN 7)	EXHSTFN	1/1/2016
WTP.EF.EF.316.8	EXHAUST FAN EF-316.8 (TRAIN 8)	EXHSTFN	1/1/2016
WTP.EF.EF.316.9	EXHAUST FAN EF-316.9 (TRAIN 9)	EXHSTFN	1/1/2016
WTP.EF.EF.4	EXHAUST FAN EF-4 (BATHROOMS)	EXHSTFN	1/1/2016
WTP.ELECT.MSB2.DECK	Deck Monitoring	ELEC	9/7/2017
WTP.ELECT.ROOM	WTP Electrical Room	ELEC	1/1/2012
WTP.ELECT.SDCWA.TRANSFORMER	SDCWA Emergency Generator Transformer	ELEC	1/1/2002
WTP.ERF.BFV-120A	BFV-120A Upstream Isolation Valve	VALVE	1/1/2016
WTP.ERF.BFV-121	BFV-122 Downstream Isolation Valve	VALVE	1/1/2016
WTP.ERF.BFV-123A	BFV-123A Upstream Isolation Valve	VALVE	1/1/2016
WTP.ERF.BFV-123B	BFV-123B Upstream Isolation Valve	VALVE	1/1/2016
WTP.ERF.BFV-123C	BFV-123C Downstream Isolation Valve	VALVE	1/1/2016
WTP.ERF.BFV-124A	BFV-124A Upstream Isolation Valve	VALVE	1/1/2016
WTP.ERF.BFV-124B	BFV-124B Upstream Isolation Valve	VALVE	1/1/2016
WTP.ERF.BFV-124C	BFV-124C Downstream Isolation Valve	VALVE	1/1/2016
WTP.ERF.ERT-123	ERT-123	TURBINE	1/1/2016
WTP.ERF.ERT-124	ERT-124	TURBINE	1/1/2016
WTP.ERF.ERT-124.	Energy Recovery Turbine 124	TURBINE	12/6/2013
WTP.ERF.GEN-123	GEN-123 Induction Generator	MOTOR	1/1/2016
WTP.ERF.GEN-124	GEN-124 Induction Generator	MOTOR	1/1/2016
WTP.ERF.HPU-123	WTP.ERF.HPU-123	PUMP	6/30/2015
WTP.ERF.HPU-124	HPU-124	PUMP	12/28/2011
WTP.ERF.OWS-2	WTP.ERF.OIL WATER SEPARATOR-2	TANK	1/1/2016
WTP.ERF.PIP	ERF Piping	PIPING	1/1/2016
WTP.ERF.PLG-120	PLG-120 ERF Plunger Valve	VALVE	1/1/2016
WTP.ERT.HPU-123	WTP.ERT.HPU-123	PUMP	12/2/2013
WTP.HOLDING.TANK	WTP.HOLDING.TANK (THE PIT)	TANK	1/1/2016
WTP.HP.HP.1	HP.HP-1 HEAT PUMP UNIT	HEATPUMP	1/1/2016
WTP.HP.HP.2	HP.HP-2 HEAT PUMP UNIT	HEATPUMP	1/1/2016
WTP.HP.HP.3	HP.HP-3 HEAT PUMP UNIT	HEATPUMP	1/1/2016
WTP.INST.ERT.AIT-PIPING	AIT-PIPING ERT Effluent Analyzer	PIPING	1/1/2016
WTP.INST.FW.IAP.PIPING	PIPING Finished Water Analyzer	PIPING	1/1/2016
WTP.INST.FW.ICP-3	ICP-3 PLC	PLCPANEL	10/5/2021
WTP.INST.RW.TNK.AIT-PIPING	AIT PIPING Raw Water Tank Analyzer	PIPING	1/1/2016
WTP.MCC7	WTP MCC 7	PS	3/30/2017
WTP.MIT.PIP	MIT Air Piping System	PIPING	6/3/2015
WTP.OSG.BLOWER1	BLOWER 1 TK-5400 SHC Storage	BLOWER	1/1/2016
WTP.OSG.BLOWER1-MTR	BLOWER 1 Motor TK-5400 SHC Storage	MOTOR	1/1/2016
WTP.OSG.BLOWER1-PIPING	BLOWER 1 PIPING TK-5400 SHC Storage	PIPING	1/1/2016
WTP.OSG.BLOWER2	BLOWER 2 TK-5401 SHC Storage	BLOWER	1/1/2016
WTP.OSG.BLOWER2-MTR	BLOWER 2 Motor TK-5401 SHC Storage	MOTOR	1/1/2016
WTP.OSG.BLOWER2-PIPING	BLOWER 2 PIPING TK-5400 SHC Storage	PIPING	1/1/2016
WTP.OSG.BLOWER3	BLOWER 3 TK-5500 SHC Storage	BLOWER	1/1/2016
WTP.OSG.BLOWER3-MTR	BLOWER 3 Motor TK-5500 SHC Storage	MOTOR	1/1/2016
WTP.OSG.BLOWER3-PIPING	BLOWER 3 PIPING TK-5400 SHC Storage	PIPING	1/1/2016
WTP.OSG.BLOWER4	BLOWER 4 OSG System Stack	BLOWER	11/7/2019
WTP.OSG.BLOWER4-MTR	BLOWER 4 Motor Stack	MOTOR	1/1/2016
WTP.OSG.BLOWER4-PIPING	BLOWER 4 PIPING Stack	PIPING	1/1/2016
WTP.OSG.BLOWERC	BLOWER Control Panel SHC Storage	CONTROL	1/1/2016
WTP.OSG.HYDROGENBLOWER	Hydrogen Dilution BLOWER	BLOWER	1/1/2016
WTP.OSG.MICROCLOR.BRINEPUMP1	BRINE TRANSFER PUMP 1	PUMP	1/1/2012
WTP.OSG.MICROCLOR.BRINETNK	BRINETNK Brine tank	TANK	1/1/2016
WTP.OSG.MICROCLOR.BRINPMP-MTR1	Brine Pump Motor	MOTOR	1/1/2016
WTP.OSG.MICROCLOR.BRINPUMP-VFD	Brine Pump VFD	VFD	1/1/2016
WTP.OSG.MICROCLOR.CELL1	Cell 1 MICROCLOR	GEN CELL	1/1/2016
WTP.OSG.MICROCLOR.CELL10	Cell 10 MICROCLOR	GEN CELL	4/8/2012

DCMWTP Active Assets

WTP.OSG.MICROCLOR.CELL2	Cell 2 MICROCLOR	GEN CELL	1/1/2016
WTP.OSG.MICROCLOR.CELL3	Cell 3 MICROCLOR	GEN CELL	1/1/2016
WTP.OSG.MICROCLOR.CELL4	Cell 4 MICROCLOR	GEN CELL	1/1/2016
WTP.OSG.MICROCLOR.CELL5	Cell 5 MICROCLOR	GEN CELL	1/1/2016
WTP.OSG.MICROCLOR.CELL6	Cell 6 MICROCLOR	GEN CELL	9/15/2013
WTP.OSG.MICROCLOR.CELL7	Cell 7 MICROCLOR	GEN CELL	9/15/2013
WTP.OSG.MICROCLOR.CELL8	Cell 8 MICROCLOR	GEN CELL	9/15/2013
WTP.OSG.MICROCLOR.CELL9	Cell 9 MICROCLOR	GEN CELL	9/15/2013
WTP.OSG.MICROCLOR.EXHSTFAN	EXHAUST FAN EF-2B (HYPO GENERATOR ROOM)	EXHSTFN	1/1/2016
WTP.OSG.MICROCLOR.FLOWCELL	Flow Meter Cell	METER	1/1/2016
WTP.OSG.MICROCLOR.OIT	MICROCLOR OIT	OIT	1/1/2016
WTP.OSG.MICROCLOR.PIPING	MicrOclor OSG System Piping	PIPING	5/15/2015
WTP.OSG.MICROCLOR.PLC	MicrOclor PLC	PLCPANEL	5/6/2015
WTP.OSG.MICROCLOR.RECTIFIER	Rectifier MICROCLOR	RECTFR	1/1/2016
WTP.OSG.MICROCLOR.ROTOMETER	Rotometer Brine	METER	1/1/2016
WTP.OSG.MICROCLOR.SOLENOIDVALV	Solenoid Valve	VALVE	1/1/2016
WTP.OSG.MICROCLOR.SYSTEM	MicrOclor System	OSGCELL	1/1/2013
WTP.OSG.TK-5400	TK-5400 Onsite generation SHC Storage Tank 1	TANK	1/1/2013
WTP.OSG.TK-5400.PIPING	TK-5400 Onsite Generation SHC Storage Tank 1 PIPING	PIPING	1/1/2016
WTP.OSG.TK-5401	TK-5401 Onsite Generation SHC Storage Tank 2	TANK	1/1/2016
WTP.OSG.TK-5401.PIPING	TK-5401 Onsite Generation SHC Storage Tank 1 PIPING	PIPING	1/1/2016
WTP.OSG.TK-5500	TK-5500 Onsite Generation SHC Storage Tank 3	TANK	1/1/2016
WTP.OSG.TK-5500.PIPING	TK-5500 Onsite Generation SHC Storage Tank 3 PIPING	PIPING	1/1/2016
WTP.PERMEATE.PIPE	Plant CFE Permeate Piping	PIPING	1/1/2002
WTP.PLANT.AIR.PIPE	Plant Air Piping System	PIPING	1/14/2016
WTP.PROCESS.BLDG.	PROCESS BUILDING	BUILDING	1/1/2016
WTP.RHB.3RD-STG-M-7024	M-7024 3rd Stage Sludge Thickener Rake	RAKE	1/1/2014
WTP.RHB.3RD-STG.GRDRV-7002	GRDRV-7002 3rd Stage Rapid Mixer Gear Drive	GEARDRVE	1/1/2016
WTP.RHB.3RD-STG.GRDRV-7003	GRDRV-7003 3rd Stage Flocculator Gear Drive	GEARDRVE	1/1/2016
WTP.RHB.3RD-STG.GRDRV-7004	GRDRV-7004 3rd Stage Sludge Rake Gear Drive	GEARDRVE	1/1/2016
WTP.RHB.3RD-STG.GRDRV-7022	GRDRV-7022 3rd Stage Rapid Mixer Gear Drive	GEARDRVE	1/1/2016
WTP.RHB.3RD-STG.GRDRV-7023	GRDRV-7023 3rd Stage Flocculator Gear Drive	GEARDRVE	1/1/2016
WTP.RHB.3RD-STG.GRDRV-7024	GRDRV-7024 3rd Stage Flocculator Gear Drive	GEARDRVE	1/1/2016
WTP.RHB.3RD-STG.GRDRV-7042	GRDRV-7042 3rd Stage Rapid Mixer Gear Drive	GEARDRVE	1/1/2016
WTP.RHB.3RD-STG.GRDRV-7043	GRDRV-7043 3rd Stage Flocculator Gear Drive	GEARDRVE	1/1/2016
WTP.RHB.3RD-STG.GRDRV-7044	GRDRV-7044 3rd Stage Flocculator Gear Drive	GEARDRVE	1/1/2016
WTP.RHB.3RD-STG.HV-710-A	HV-710-A Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-710-B	HV-710-B Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-710-C	HV-710-C Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-710-D	HV-710-D Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-710-E	HV-710-E Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-711-A	HV-711-A Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-711-B	HV-711-B Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-711-C	HV-711-C Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-711-D	HV-711-D Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-711-E	HV-711-E Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-712-A	HV-712-A Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-712-B	HV-712-B Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-712-C	HV-712-C Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-712-D	HV-712-D Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.HV-712-E	HV-712-E Sand Piper Sludge Pump Hand Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.M-7002	M-7002 3rd Stage Rapid Mixer	MIXER	1/1/2016
WTP.RHB.3RD-STG.M-7003	M-7003 3rd Stage Flocculator	FLOCLATR	1/1/2016
WTP.RHB.3RD-STG.M-7004	M-7004 3rd Stage Sludge Rake	RAKE	1/1/2016
WTP.RHB.3RD-STG.M-7022	M-7022 Rapid Mixer	MIXER	1/1/2016

DCMWTP Active Assets

WTP.RHB.3RD-STG.M-7023	M-7023 3rd Stage Flocculator	FLOCLATR	1/1/2016
WTP.RHB.3RD-STG.M-7024	M-7024 3rd Stage Sludge Rake, Settler #2	PUMP	1/1/2013
WTP.RHB.3RD-STG.M-7042	M-7042 3rd Stage Rapid Mixer	MIXER	1/1/2016
WTP.RHB.3RD-STG.M-7043	M-7043 3rd Stage Flocculator	FLOCLATR	1/1/2016
WTP.RHB.3RD-STG.M-7044	M-7044 3rd Stage Sludge Rake	RAKE	1/1/2016
WTP.RHB.3RD-STG.MOV-710-1	MOV-710-1 3rd Stage Inlet Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.MOV-710-2	MOV-710-2 3rd Stage Outlet Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.MOV-711-1	MOV-711-1 3rd Stage Inlet Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.MOV-711-2	MOV-711-2 3rd Stage Outlet Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.MOV-712-1	MOV-712-1 3rd Stage Inlet Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.MOV-712-2	MOV-712-2 3rd Stage Outlet Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.MTR-7002	MTR-7002 3rd Stage Rapid Mixer Motor	MOTOR	1/1/2016
WTP.RHB.3RD-STG.MTR-7003	MTR-7003 3rd Stage Flocculator Motor	MOTOR	1/1/2016
WTP.RHB.3RD-STG.MTR-7004	MTR-7004 3rd Stage Sludge Rake Motor	MOTOR	1/1/2016
WTP.RHB.3RD-STG.MTR-7022	MTR-7022 3rd Stage Rapid Mixer Motor	MOTOR	1/1/2016
WTP.RHB.3RD-STG.MTR-7023	MTR-7023 3rd Stage Flocculator Motor	MOTOR	1/1/2016
WTP.RHB.3RD-STG.MTR-7024	MTR-7024 3rd Stage Flocculator Motor	MOTOR	1/1/2016
WTP.RHB.3RD-STG.MTR-7042	MTR-7042 3rd Stage Rapid Mixer Motor	MOTOR	1/1/2016
WTP.RHB.3RD-STG.MTR-7043	MTR-7043 3rd Stage Flocculator Motor	MOTOR	1/1/2016
WTP.RHB.3RD-STG.MTR-7044	MTR-7044 3rd Stage Flocculator Motor	MOTOR	1/1/2016
WTP.RHB.3RD-STG.PIPING	3RD-STG.PIPING-PVC	PIPING	1/1/2016
WTP.RHB.3RD-STG.PV-710	PV-710 3rd Stage Settler 1 Outlet Plug Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.PV-711	PV-711 3rd Stage Settler 2 Outlet Plug Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.PV-712	PV-712 3rd Stage Settler 3 Outlet Plug Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.SV-710	SV-710 3rd Stage Solenoid Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.SV-711	SV-711 3rd Stage Solenoid Valve	VALVE	1/1/2016
WTP.RHB.3RD-STG.SV-712	SV-712 3rd Stage Solenoid Valve	VALVE	1/1/2016
WTP.RHB.BLDG.	RESIDUAL HANDLING BUILDING	BUILDING	1/1/2016
WTP.RHB.CENTRFGE.MFCV1.CIP.FLU	MFCV1.CIP.Flush Manual control valve 1 CIP Flush	VALVE	1/1/2013
WTP.RHB.CENTRFGE.MFCV1.FLUSH	MFCV1.FLUSH Manual control valve 1 FLUSH	VALVE	1/1/2013
WTP.RHB.CENTRT.BCV-740-1	BCV-740-1 Centrate Ball Check Valve Pump 1	VALVE	1/1/2016
WTP.RHB.CENTRT.BCV-740-2	BCV-740-2 Centrate Ball Check Valve Pump 2	VALVE	1/1/2016
WTP.RHB.CENTRT.BV-740-1A	BV-740-1A Centrate Ball Valve Inlet Pump 1	VALVE	1/1/2016
WTP.RHB.CENTRT.BV-740-1B	BV-740-1B Centrate Ball Valve Outlet Pump 1	VALVE	1/1/2016
WTP.RHB.CENTRT.BV-740-2A	BV-740-2A Centrate Ball Valve Inlet Pump 2	VALVE	1/1/2016
WTP.RHB.CENTRT.BV-740-2B	BV-740-2B Centrate Ball Valve Outlet Pump 2	VALVE	1/1/2016
WTP.RHB.CENTRT.MTR-740-1	MTR-740-1 Centrate Pump 1	MOTOR	1/1/2016
WTP.RHB.CENTRT.MTR-740-2	MTR-740-2 Centrate Pump 2	MOTOR	1/1/2016
WTP.RHB.CENTRT.P-740-1	P-740-1 Centrate Pump	PUMP	1/1/2016
WTP.RHB.CENTRT.P-740-1/1	P-740-1 Centrate Pump Motor	MOTOR	10/18/2018
WTP.RHB.CENTRT.P-740-2	P-740-2 Centrate Pump	PUMP	1/1/2016
WTP.RHB.CENTRT.P-740-2/2	P-740-2 Centrate Pump Motor	MOTOR	10/18/2018
WTP.RHB.CENTRT.PIPING	CENTRT.PIPING	PIPING	1/1/2016
WTP.RHB.CENTRT.PV-740	PV-740 Centrate Plug Valve Drain	VALVE	1/1/2016
WTP.RHB.CENTRT.TNK-740	TNK-740 Centrate Storage Tank	TANK	1/1/2016
WTP.RHB.CENTRT.TNK-STND-740	TNK-STND-740 Centrate Storage Tank Stand	STAND	1/1/2016
WTP.RHB.CNTRFG-FD.BCKDRV-731-1	CNTRFG-FD.BCKDRV-731-1 Centrifuge 1 Back drive Motor	MOTOR	1/1/2016
WTP.RHB.CNTRFG-FD.BCV-726-1B	BCV-726-1B Centrifuge Feed Ball Check Valve	VALVE	1/1/2016
WTP.RHB.CNTRFG-FD.BCV-726-2B	BCV-726-2B Centrifuge Feed Ball Check Valve	VALVE	1/1/2016
WTP.RHB.CNTRFG-FD.C-731-A	C-731-A Fresh Water Solenoid Coil	COIL	1/1/2016
WTP.RHB.CNTRFG-FD.C-731-B	C-731-B Fresh Water Solenoid Coil	COIL	1/1/2016
WTP.RHB.CNTRFG-FD.CEN-731	CEN-731 Centrifuge System 1	CNTIFUGE	1/1/2013
WTP.RHB.CNTRFG-FD.MFCV1.CIP.F	MFCV1.CIP.FLUSH Manual Flow Control Valve 1 CIP Flush	ROTOMTR	1/1/2016
WTP.RHB.CNTRFG-FD.MFCV1.FLUSH	MFCV1.FLUSH Manual Flow Control Valve 1 Flush	ROTOMTR	1/1/2016
WTP.RHB.CNTRFG-FD.MNDRV-731-2	CNTRFG-FD.MAINDRV-731-2 Centrifuge 1 Main drive Motor	MOTOR	1/1/2016

DCMWTP Active Assets

WTP.RHB.CNTRFG-FD.MTR-726-1	MTR-726-1 Centrifuge Feed Pump 1 Motor	MOTOR	1/1/2016
WTP.RHB.CNTRFG-FD.MTR-726-2	MTR-726-2 Centrifuge Feed Pump 2 Motor	MOTOR	1/1/2016
WTP.RHB.CNTRFG-FD.P-726-1	P-726-1 Centrifuge Feed Pump	PUMP	1/1/2012
WTP.RHB.CNTRFG-FD.P-726-1/1	P-726-1 Centrifuge Feed Pump Motor	MOTOR	10/18/2018
WTP.RHB.CNTRFG-FD.P-726-2	P-726-2 Centrifuge Feed Pump	PUMP	1/1/2016
WTP.RHB.CNTRFG-FD.P-726-2/2	P-726-2 Centrifuge Feed Pump Motor	MOTOR	10/18/2018
WTP.RHB.CNTRFG-FD.PIPING	CNTRFG-FD.PIPING	PIPING	1/1/2016
WTP.RHB.CNTRFG-FD.PV-726-1A	PV-726-1A Centrifuge Feed Plug Valve	VALVE	1/1/2016
WTP.RHB.CNTRFG-FD.PV-726-1C	PV-726-1C Centrifuge Feed Plug Valve	VALVE	1/1/2016
WTP.RHB.CNTRFG-FD.PV-726-2A	PV-726-2A Centrifuge Feed Plug Valve	VALVE	1/1/2016
WTP.RHB.CNTRFG-FD.PV-726-2C	PV-726-2C Centrifuge Feed Plug Valve	VALVE	1/1/2016
WTP.RHB.CNTRFG-FD.PV-726-4	PV-726-4 Centrifuge Feed Plug Valve	VALVE	1/1/2016
WTP.RHB.CNTRFG-FD.PV-726-5	PV-726-5 Centrifuge Feed Plug Valve	VALVE	1/1/2016
WTP.RHB.CNTRFG-FD.SV-731-A	SV-731-A Fresh Water Solenoid Valve	VALVE	1/1/2016
WTP.RHB.CNTRFG-FD.SV-731-B	SV-731-B Fresh Water Solenoid Valve	VALVE	1/1/2016
WTP.RHB.COAG.BV-750A	BV-750 Coagulant Tank Drain Ball Valve	VALVE	1/1/2016
WTP.RHB.COAG.BV-750B	BV-750 Coagulant Tank Outlet Ball Valve	VALVE	1/1/2016
WTP.RHB.COAG.BV-754-1A	BV-754-1A Coagulant Ball Valve	VALVE	1/1/2016
WTP.RHB.COAG.BV-754-1B	BV-754-1B Coagulant Ball Valve	VALVE	1/1/2016
WTP.RHB.COAG.BV-754-1C	BV-754-1C Coagulant Ball Valve	VALVE	1/1/2016
WTP.RHB.COAG.BV-754-2A	BV-754-2A Coagulant Ball Valve	VALVE	1/1/2016
WTP.RHB.COAG.BV-754-2B	BV-754-2B Coagulant Ball Valve	VALVE	1/1/2016
WTP.RHB.COAG.BV-754-2C	BV-754-2C Coagulant Ball Valve	VALVE	1/1/2016
WTP.RHB.COAG.BV-754-C	BV-754-C Coagulant Ball Valve	VALVE	1/1/2016
WTP.RHB.COAG.CV-750	CV-750 Coagulant Tank Inlet Fill Check Valve	VALVE	1/1/2016
WTP.RHB.COAG.GV-750	GV-750 Coagulant Tank Inlet Fill Gate Valve	VALVE	1/1/2016
WTP.RHB.COAG.MTR-754-1	MTR-754-1 Coagulant Metering Pump 1 Motor	MOTOR	1/1/2016
WTP.RHB.COAG.MTR-754-2	MTR-754-2 Coagulant Metering Pump 2 Motor	MOTOR	1/1/2016
WTP.RHB.COAG.P-754-1	P-754-1 Coagulant metering pump 1	PUMP	1/1/2013
WTP.RHB.COAG.P-754-2	P-754-2 Coagulant Metering Pump 2	PUMP	1/1/2016
WTP.RHB.COAG.PD-754-1	PD-754-1 Coagulant Pulsation Dampner	DAMPNER	1/1/2016
WTP.RHB.COAG.PD-754-2	PD-754-2 Coagulant Pulsation Dampner	DAMPNER	1/1/2016
WTP.RHB.COAG.PIPING	COAG.PIPING	PIPING	1/1/2016
WTP.RHB.COAG.RM-754-1	RM-754-1 Coagulant Rotometer	ROTOMTR	1/1/2016
WTP.RHB.COAG.RM-754-2	RM-754-2 Coagulant Rotometer	ROTOMTR	1/1/2016
WTP.RHB.COAG.STC.MXR	Coagulant 6" Static Mixer	MIXER	1/1/2016
WTP.RHB.COAG.TNK-750	TNK-750 Coagulant Tank	TANK	1/1/2016
WTP.RHB.EXHST-FAN-EF-7H-01-FAN	EF-7H-01-FAN Exhaust Fan Assembly South End of RHB	EXHSTFN	1/1/2016
WTP.RHB.EXHST-FAN-EF-7H-01-MTR	EF-7H-01-MTR Exhaust Motor Assembly South End of RHB	MOTOR	1/1/2016
WTP.RHB.EXHST-FAN-EF-7H-02-FAN	EF-7H-02-FAN Exhaust Fan Assembly South End of RHB	EXHSTFN	1/1/2016
WTP.RHB.EXHST-FAN-EF-7H-02-MTR	EF-7H-02-MTR Exhaust Motor Assembly South End of RHB	MOTOR	1/1/2016
WTP.RHB.INST.3RD-STG.AIT-710-1	AIT-710-1 3RD Stage Turbidity Meter	METER	1/1/2016
WTP.RHB.INST.3RD-STG.AIT-710-2	AIT-710-2 3RD Stage Streaming Current Monitor	MONITOR	1/1/2016
WTP.RHB.INST.3RD-STG.AIT-710-3	AIT-710-3 3RD Stage Streaming Current Monitor	MONITOR	4/30/2019
WTP.RHB.INST.3RD-STG.AIT-711	AIT-711 Third Stage Treatment Units Decant TSS Meter	METER	1/1/2016
WTP.RHB.INST.3RD-STG.FIT-711	FIT-711 Third Stage Decant Flow Totalizer	METER	1/1/2016
WTP.RHB.INST.3RD-STG.FIT-712	FIT-712 Third Stage Flow to Sludge Storage Totalizer	METER	1/1/2016
WTP.RHB.INST.CENTRT.AIT-740	AIT-740 Centrate Storage Tank Turbidity Meter	METER	1/1/2016
WTP.RHB.INST.CNTRFG.FIT-726-1	FIT-726-1 Centrifuge Feed Pump 1 Discharge Flow Totalizer	METER	1/1/2016
WTP.RHB.INST.CNTRFG.FIT-726-2	FIT-726-2 Centrifuge Feed Pump 2 Discharge Flow Totalizer	METER	1/1/2016
WTP.RHB.INST.SLDG-TK.AIT-720-1	AIT-720-1 Sludge Storage Tank 1 TSS Meter	METER	1/1/2016

DCMWTP Active Assets

WTP.RHB.INST.SLDG-TK.AIT-720-2	AIT-720-2 Sludge Storage Tank 2 TSS Meter	METER	1/1/2016
WTP.RHB.OWS-3	WTP.RHB.OIL WATER SEPARATOR-3	TANK	1/1/2016
WTP.RHB.POLY.BV-751	BV-751 Polymer Tank Outlet Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-752	BV-752 Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-755-1A	BV-755-1A Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-755-1B	BV-755-1B Polymer Metering Pump 1Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-755-1C	BV-755-1C Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-755-1D	BV-755-1D Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-755-2A	BV-755-1A Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-755-2B	BV-755-2B Polymer Metering Pump 2 Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-755-2D	BV-755-1D Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-756-1A	BV-756-1A Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-756-1B	BV-756-1B Polymer Metering Pump 1 Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-756-1C	BV-756-1C Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-756-1D	BV-756-1D Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-756-2A	BV-756-2A Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-756-2B	BV-756-2B Polymer Metering Pump 2 Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-756-2C	BV-756-2C Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.BV-756-2D	BV-756-2D Polymer Ball Valve	VALVE	1/1/2016
WTP.RHB.POLY.CM-752-2	CM-752-2 Polymer Control Mixing System	POLYPW	1/1/2013
WTP.RHB.POLY.CNTRL-PNL-751	Cntrl-Pnl-751 Poly Control Panel	CONTROL	1/1/2016
WTP.RHB.POLY.MTR-755-1	MTR-755-1 Polymer Metering Pump 1 Motor	MOTOR	1/1/2016
WTP.RHB.POLY.MTR-755-2	MTR-755-2 Polymer Metering Pump 2 Motor	MOTOR	1/1/2016
WTP.RHB.POLY.MTR-756-1	MTR-756-1 Polymer Metering Pump 1 Motor	MOTOR	1/1/2016
WTP.RHB.POLY.MTR-756-2	MTR-756-2 Polymer Metering Pump 2 Motor	MOTOR	1/1/2016
WTP.RHB.POLY.P-752-1	P-752-1 Polymer Blend System Pump	PUMP	1/1/2016
WTP.RHB.POLY.P-755-1	P-755-1 Polymer Metering Pump 1	PUMP	1/1/2013
WTP.RHB.POLY.P-755-2	P-755-2 Polymer metering pump 2	PUMP	1/1/2013
WTP.RHB.POLY.P-756-1	P-756-1 Polymer Metering Pump 1	PUMP	9/16/2015
WTP.RHB.POLY.P-756-2	P-756-2 Polymer Metering Pump	PUMP	9/16/2015
WTP.RHB.POLY.PD-755-1	PD-755-1 Polymer Pulsation Dampner Pump 1	DAMPNER	1/1/2016
WTP.RHB.POLY.PD-755-2	PD-755-2 Polymer Pulsation Dampner Pump 2	DAMPNER	1/1/2016
WTP.RHB.POLY.PD-756-1	PD-756-1 Polymer Pulsation Dampner Pump 1	DAMPNER	1/1/2016
WTP.RHB.POLY.PD-756-2	PD-756-2 Polymer Pulsation Dampner Pump 2	DAMPNER	1/1/2016
WTP.RHB.POLY.PIPING	Polymer Feed System Piping	PIPING	4/15/2016
WTP.RHB.POLY.RECIRC-P-751	Recirc-P-751 Poly Recirc Pump 1	PUMP	1/1/2016
WTP.RHB.POLY.RM-755-1	RM-755-1 Polymer Rotometer	ROTOMTR	1/1/2016
WTP.RHB.POLY.RM-755-2	RM-755-2 Polymer Rotometer	ROTOMTR	1/1/2016
WTP.RHB.POLY.RM-756-1	RM-756-1 Polymer Rotometer	ROTOMTR	1/1/2016
WTP.RHB.POLY.RM-756-2	RM-756-2 Polymer Rotometer	ROTOMTR	1/1/2016
WTP.RHB.POLY.RTMTR-751	RM-751 Poly Rotometer	ROTOMTR	1/1/2016
WTP.RHB.POLY.STC.MXR	Polymer 6" Static Mixer	MIXER	1/1/2016
WTP.RHB.POLY.SV-752	SV-752 Polymer Blend Solenoid Valve	VALVE	1/1/2016
WTP.RHB.POLY.SV-753	SV-753 Polymer Blend Solenoid Valve	VALVE	1/1/2016
WTP.RHB.POLY.TNK-751	TNK-751 Polymer Tank	TANK	1/1/2016
WTP.RHB.POLY.TNK-753	TNK-753 Polymer Day Tank	TANK	1/1/2016
WTP.RHB.POLY.WIT-751	WIT-751 Polymer Tote Weight Scale	SCALE	1/1/2016
WTP.RHB.ROLL-UP-DOOR	RHB Roll up door	ROLLUP	1/1/2016
WTP.RHB.SLDG-REC.BV-725-1E	BV-725-1E Potable Water Ball Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.BV-725-2E	BV-725-2E Potable Water Ball Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.BV-725-3E	BV-725-3E Potable Water Ball Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.MTR-725-1	MTR-725-1 Sludge Recirc Pump 1 Motor	MOTOR	1/1/2016
WTP.RHB.SLDG-REC.MTR-725-2	MTR-725-2 Sludge Recirc Pump 2 Motor	MOTOR	1/1/2016
WTP.RHB.SLDG-REC.MTR-725-3	MTR-725-3 Sludge Recirc Pump 3 Motor	MOTOR	1/1/2016
WTP.RHB.SLDG-REC.P-725-1	P-725-1 Solids Mixing Pump	PUMP	1/1/2016
WTP.RHB.SLDG-REC.P-725-1/1	P-725-1 Solids Mixing Pump Motor	MOTOR	10/9/2018
WTP.RHB.SLDG-REC.P-725-2	P-725-2 Solids Mixing Pump	PUMP	1/1/2016
WTP.RHB.SLDG-REC.P-725-2/2	P-725-2 Solids Mixing Pump Motor	MOTOR	10/9/2018
WTP.RHB.SLDG-REC.P-725-3	P-725-3 Solids Mixing Pump	PUMP	1/1/2016

DCMWTP Active Assets

WTP.RHB.SLDG-REC.P-725-3/3	P-725-3 Solids Mixing Pump Motor	MOTOR	10/9/2018
WTP.RHB.SLDG-REC.PV-725-1A	PV-725-1A Sludge Recirc Pump 1 Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.PV-725-1B	PV-725-1B Sludge Recirc Pump 1 Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.PV-725-1C	PV-725-1C Sludge Recirc Pump 1 Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.PV-725-1D	PV-725-1D Sludge Recirc Pump 1 Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.PV-725-2A	PV-725-2A Sludge Recirc Pump 2 Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.PV-725-2B	PV-725-2B Sludge Recirc Pump 2 Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.PV-725-2C	PV-725-2C Sludge Recirc Pump 2 Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.PV-725-2D	PV-725-2D Sludge Recirc Pump 2 Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.PV-725-3A	PV-725-3A Sludge Recirc Pump 3 Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.PV-725-3B	PV-725-3B Sludge Recirc Pump 3 Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.SV-725-1	SV-725-1 Sludge Recirc Pump 1 PW Solenoid Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.SV-725-2	SV-725-2 Sludge Recirc Pump 2 PW Solenoid Valve	VALVE	1/1/2016
WTP.RHB.SLDG-REC.SV-725-3	SV-725-3 Sludge Recirc Pump 3 PW Solenoid Valve	VALVE	1/1/2016
WTP.RHB.SLDG-RECIRC.PIPING	SLDG-RECIRC.PIPING	PIPING	1/1/2016
WTP.RHB.SLDG-TNK-720-1	TNK-720-1 Sludge Storage Tank 1	TANK	1/1/2016
WTP.RHB.SLDG-TNK-720-2	TNK-720-2 Sludge Storage Tank 2	TANK	1/1/2016
WTP.RHB.SLDG-TNK-STND-720-1	TNK-STND-720 Tank Stand	STAND	1/1/2016
WTP.RHB.SLDG-TNK-STND-720-2	TNK-STND-720-2 Tank Stand	STAND	1/1/2016
WTP.RHB.SLDG-TNK.PV-720-1A	PV-720-1A Sludge Tank Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-TNK.PV-720-1B	PV-720-1B Sludge Tank Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-TNK.PV-720-1C	PV-720-1C Sludge Tank Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-TNK.PV-720-1D	PV-720-1D Sludge Tank Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-TNK.PV-720-1E	PV-720-1E Sludge Tank Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-TNK.PV-720-2A	PV-720-2A Sludge Tank Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-TNK.PV-720-2B	PV-720-2B Sludge Tank Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-TNK.PV-720-2C	PV-720-2C Sludge Tank Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-TNK.PV-720-2D	PV-720-2D Sludge Tank Plug Valve	VALVE	1/1/2016
WTP.RHB.SLDG-TNK.PV-720-2E	PV-720-2E Sludge Tank Plug Valve	VALVE	1/1/2016
WTP.RHB.SNDPPR.P-710	P-710 Sand Piper Sludge Pump	PUMP	1/1/2016
WTP.RHB.SNDPPR.P-711	P-711 Sand Piper Sludge pump	PUMP	1/1/2016
WTP.RHB.SNDPPR.P-712	P-712 Sand Piper Sludge pump	PUMP	1/1/2016
WTP.RHB.STTLR.PSU-7000	PSU-7000 Plate Settler #1	SETTLER	1/1/2016
WTP.RHB.STTLR.PSU-7020	PSU-7040 Plate Settler #2	SETTLER	6/7/2018
WTP.RHB.STTLR.PSU-7040	PSU-7040 Plate Settler #3	SETTLER	1/1/2016
WTP.RHB.SUPP-FAN-SF-7H-01	SF-7H-01-FAN SUPPLY FAN ASSEMBLY NORTH END OF RHB	HVAC	12/2/2013
WTP.RHB.SUPP-FAN-SF-7H-01-FAN	SF-7H-01-FAN Supply Fan Assembly North End of RHB	EXHSTFN	1/1/2016
WTP.RHB.SUPP-FAN-SF-7H-01-MTR	SF-7H-01-MTR Supply Motor Assembly North End of RHB	MOTOR	1/1/2016
WTP.RHB.SUPP-FAN-SF-7H-02	SF-7H-02-FAN SUPPLY FAN ASSEMBLY NORTH END OF RHB	HVAC	5/11/2016
WTP.RHB.SUPP-FAN-SF-7H-02-FAN	SF-7H-02-FAN Supply Fan Assembly North End of RHB	EXHSTFN	1/1/2016
WTP.RHB.SUPP-FAN-SF-7H-02-MTR	SF-7H-02-MTR Supply Motor Assembly North End of RHB	MOTOR	1/1/2016
WTP.RHB.WSTE-SLDG.TNK-760	TNK-760 Waste Sludge Holding Tank	TANK	1/1/2016
WTP.RHBINST3RD-STG.FIT-710	FIT-710 3RD Stage Inlet Flow Meter	METER	1/1/2016
WTP.RWEQ.BFV-210	BFV-210 Upstream Isolation Valve	VALVE	1/1/2016
WTP.RWEQ.BFV-211	BFV-211 Upstream Isolation Valve	VALVE	1/1/2016
WTP.RWEQ.BFV-212	BFV-212 Downstream Isolation Valve	VALVE	1/1/2016
WTP.RWEQ.BFV-213	BFV-213 RWEQ Series Isolation Valve	VALVE	1/1/2016
WTP.RWEQ.BFV-214	BFV-214 Downstream Isolation Valve	VALVE	1/1/2016
WTP.RWEQ.BFV-215	BFV-215 RWEQ 1st Stage Isolation Valve	VALVE	1/1/2016
WTP.RWEQ.GV-211	GV-211 Drain Valve	VALVE	1/1/2016

DCMWTP Active Assets

WTP.RWEQ.GV-212	GV-212 Drain Valve	VALVE	1/1/2016
WTP.RWEQ.PIP	RWEQ Piping	PIPING	1/1/2016
WTP.RWEQ.TNK-211	TNK-211 West RWEQ Tank	TANK	1/1/2016
WTP.RWEQ.TNK-212	TNK-212 East RWEQ Tank	TANK	1/1/2016
WTP.SEWER.PIPING	WTP Sewer System Piping	PIPING	1/1/2001
WTP.STORAGE.BLDG.	STORAGE BUILDING	BUILDING	1/1/2016
WTP.STR.BFV-111A	BFV-111A Upstream Isolation Valve	VALVE	1/1/2016
WTP.STR.BFV-111B	BFV-111 Downstream Isolation Valve	VALVE	1/1/2016
WTP.STR.BFV-111C	FV-111 Backwash Valve	VALVE	1/1/2016
WTP.STR.BFV-112A	BFV-112A Upstream Isolation Valve	VALVE	1/1/2016
WTP.STR.BFV-112B	BFV-112 Downstream Isolation Valve	VALVE	1/1/2016
WTP.STR.BFV-112C	FV-112 Backwash Valve	VALVE	1/1/2016
WTP.STR.BFV-113A	BFV-113A Upstream Isolation Valve	VALVE	1/1/2016
WTP.STR.BFV-113B	BFV-113 Downstream Isolation Valve	VALVE	1/1/2016
WTP.STR.BFV-113C	FV-113 Backwash Valve	VALVE	1/1/2016
WTP.STR.FLT-111	FLT-111 Strainer Filter Elements	STRAINER	3/31/2016
WTP.STR.FLT-112	FLT-112 Strainer Filter Elements	STRAINER	3/31/2016
WTP.STR.FLT-113	FLT-113 Strainer Filter Elements	STRAINER	3/31/2016
WTP.STR.GV-110	GV-110 Strainer Backwash Gate Valve	VALVE	1/1/2016
WTP.STR.MTR-111	MTR-111 Backwash Motor	MOTOR	1/1/2016
WTP.STR.MTR-112	MTR-112 Backwash Motor	MOTOR	1/1/2016
WTP.STR.MTR-113	MTR-113 Backwash Motor	MOTOR	1/1/2016
WTP.STR.PIP	Strainer Piping	PIPING	1/1/2016
WTP.STR.STR-111	STR-111 Strainer Housing	STRAINER	1/1/2016
WTP.STR.STR-112	STR-112 Strainer Housing	STRAINER	3/31/2016
WTP.STR.STR-113	STR-113 Strainer Housing	STRAINER	3/31/2016
WTP.SUREG.TNK.BFV-9670-2	BFV-9670-2 24" BFV Inlet Valve to Surge Tank	VALVE	1/1/2016
WTP.SURGE.PNL	Surge Control Panel	CONTROL	1/1/2016
WTP.SURGE.TNK-9670	TNK-9670 Surge Tank	TANK	1/1/2016
WTP.SURGE.TNK.BFV-9670-1	BFV-9670-1 4" BFV Surge Tank Drain Valve	VALVE	1/1/2016
WTP.SURGE.TNK.CP	Surge Tank Control Panel	CONTROL	6/2/2015
WTP.TK-96-A	TK-96-A MIT TANK RECEIVER	TANK	1/1/2016
WTP.TK-96-B	TK-96-B MIT TANK RECEIVER	TANK	1/1/2016
WTP.TK9675.AR-DRY	TK 9675.AR DRY TANK RECEIVER	TANK	1/1/2016
WTP.TK9675.AR-WET	TK 9675.AR WET TANK RECEIVER	TANK	1/1/2016
WTP.TKDR.BFV-314-1A	BFV-314-1A Upstream Isolation Valve	VALVE	1/1/2016
WTP.TKDR.BFV-314-1B	BFV-314-1B Downstream Isolation Valve	VALVE	1/1/2016
WTP.TKDR.BFV-314-2A	BFV-314-2A Upstream Isolation Valve	VALVE	1/1/2016
WTP.TKDR.BFV-314-2B	BFV-314-2B Downstream Isolation Valve	VALVE	1/1/2016
WTP.TKDR.BFV-8401-2	BFV-8401-2 BWEQ Isolation Valve	VALVE	1/1/2016
WTP.TKDR.CV-314-1	CV-314-1 Check Valve	VALVE	1/1/2016
WTP.TKDR.CV-314-2	CV-314-2 Check Valve	VALVE	1/1/2016
WTP.TKDR.E-314	E-314 Tank Drain Eductor	EDUCTOR	1/1/2016
WTP.TKDR.EDUC-314	SV-314 Tank Drain Eductor	VALVE	1/1/2016
WTP.TKDR.M-314-1	P-314-1 Tank Drain Pump Motor	MOTOR	1/1/2016
WTP.TKDR.M-314-2	P-314-2 Tank Drain Pump Motor	MOTOR	1/1/2016
WTP.TKDR.P-314-1	P-314-1 Tank Drain Pump	PUMP	1/1/2016
WTP.TKDR.P-314-2	P-314-2 Tank Drain Pump	PUMP	1/1/2016
WTP.TKDR.PIP	Tank Drain Piping	PIPING	1/1/2016
WTP.TKDR.PIPING	Tank Drain Piping	PIPING	1/1/2016
WTP.TKDR.STR-314	STR-314 Tank Drain Strainer	STRAINER	1/1/2016
WTP.WTP.OWS-1	WTP.WTP.OIL WATER SEPARATOR-1	TANK	1/1/2016
WTP.ZW1-9.CASSETTE.A	ZW1-9 Cassette A 64M Frame	CASSETTE	8/3/2016
WTP.ZW1-9.CASSETTE.B	ZW1-9 Cassette B 64M Frame	CASSETTE	8/3/2016
WTP.ZW1-9.CASSETTE.C	ZW1-9 Cassette C 64M Frame	CASSETTE	8/3/2016
WTP.ZW1-9.CASSETTE.D	ZW1-9 Cassette D 64M Frame	CASSETTE	7/1/2016
WTP.ZW1-9.CASSETTE.E	ZW1-9 Cassette E 64M Frame	CASSETTE	7/13/2016
WTP.ZW1-9.CASSETTE.F	ZW1-9 Cassette F 64M Frame	CASSETTE	8/3/2016
WTP.ZW1-9.CASSETTE.G	ZW1-9 Cassette G 64M Frame	CASSETTE	7/19/2016

DCMWTP Active Assets

WTP.ZW1-P35-5.VFD	WTP.ZW1-P35-5.VFD	VFD	1/1/2016
WTP.ZW1.AIT-3537-1	AIT-3537-1 Turbidimeter	METER	8/25/2020
WTP.ZW1.AIT-3537-10C	AIT-3537-10 Turbidimeter Controller	CONTRLLR	1/1/2016
WTP.ZW1.AIT-3537-1C	AIT-3537-1 Turbidimeter Controller	CONTRLLR	1/1/2016
WTP.ZW1.AIT-3537-2	AIT-3537-2 Turbidimeter	METER	9/13/2020
WTP.ZW1.AIT-3537-2C	AIT-3537-2 Turbidimeter Controller	CONTRLLR	1/1/2016
WTP.ZW1.AIT-3537-3	AIT-3537-3 Turbidimeter	METER	1/1/2016
WTP.ZW1.AIT-3537-3C	AIT-3537-3 Turbidimeter Controller	CONTRLLR	1/1/2016
WTP.ZW1.AIT-3537-4	AIT-3537-4 Turbidimeter	METER	1/1/2016
WTP.ZW1.AIT-3537-4C	AIT-3537-4 Turbidimeter Controller	CONTRLLR	1/1/2016
WTP.ZW1.AIT-3537-5	AIT-3537-5 Turbidimeter	METER	8/24/2020
WTP.ZW1.AIT-3537-5C	AIT-3537-5 Turbidimeter Controller	CONTRLLR	1/1/2016
WTP.ZW1.AIT-3537-6	AIT-3537-6 Turbidimeter	METER	1/1/2016
WTP.ZW1.AIT-3537-6C	AIT-3537-6 Turbidimeter Controller	CONTRLLR	1/1/2016
WTP.ZW1.AIT-3537-7	AIT-3537-7 Turbidimeter	METER	1/1/2016
WTP.ZW1.AIT-3537-7C	AIT-3537-7 Turbidimeter Controller	CONTRLLR	1/1/2016
WTP.ZW1.AIT-3537-8	AIT-3537-8 Turbidimeter	METER	1/1/2016
WTP.ZW1.AIT-3537-8C	AIT-3537-8 Turbidimeter Controller	CONTRLLR	1/1/2016
WTP.ZW1.AIT-3537-9	AIT-3537-9 Turbidimeter	METER	1/1/2016
WTP.ZW1.AIT-3537-9C	AIT-3537-9 Turbidimeter Controller	CONTRLLR	1/1/2016
WTP.ZW1.CV-1	ZW1-1 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW1.CV-10	ZW1-10 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW1.CV-2	ZW1-2 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW1.CV-3	ZW1-3 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW1.CV-320-B10	ZW1-10 Back Pulse Check valve	VALVE	1/1/2016
WTP.ZW1.CV-320-B9	ZW1-9 Back Pulse Check valve	VALVE	1/1/2016
WTP.ZW1.CV-3470-1	ZW1-1 Back Pulse Check valve	VALVE	1/1/2016
WTP.ZW1.CV-3470-2	ZW1-2 Back Pulse Check valve	VALVE	1/1/2016
WTP.ZW1.CV-3470-3	ZW1-3 Back Pulse Check valve	VALVE	1/1/2016
WTP.ZW1.CV-3470-4	CV-3470-4 Train 4 Backpulse Checkvalve	VALVE	8/4/2015
WTP.ZW1.CV-3470-5	ZW1-5 Back Pulse Check valve	VALVE	1/1/2016
WTP.ZW1.CV-3470-6	ZW1-6 Back Pulse Check valve	VALVE	1/1/2016
WTP.ZW1.CV-3470-7	ZW1-7 Back Pulse Check valve	VALVE	1/1/2016
WTP.ZW1.CV-3470-8	ZW1-8 Back Pulse Check valve	VALVE	1/1/2016
WTP.ZW1.CV-4	ZW1-4 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW1.CV-5	ZW1-5 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW1.CV-6	ZW1-6 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW1.CV-7	ZW1-7 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW1.CV-8	ZW1-8 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW1.CV-9	ZW1-9 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW1.E-325-1	E-325-1 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-325-10	E-325-10 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-325-2	E-325-2 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-325-3	E-325-3 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-325-4	E-325-4 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-325-5	E-325-5 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-325-6	E-325-6 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-325-7	E-325-7 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-325-8	E-325-8 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-325-9	E-325-9 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-326-1	E-326-1 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-326-10	E-326-10 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-326-2	E-326-2 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-326-3	E-326-3 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-326-4	E-326-4 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-326-5	E-326-5 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-326-6	E-326-6 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-326-7	E-326-7 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E-326-8	E-326-8 Post MIT Priming Eductor	EDUCTOR	1/1/2016

DCMWTP Active Assets

WTP.ZW1.E-326-9	E-326-9 Post MIT Priming Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E350-1	E-350-1 Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E350-10	E-350-10 Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E350-2	E-350-2 Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E350-3	E-350-3 Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E350-4	E-350-4 Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E350-5	E-350-5 Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E350-6	E-350-6 Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E350-7	E-350-7 Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E350-8	E-350-8 Eductor	EDUCTOR	1/1/2016
WTP.ZW1.E350-9	E-350-9 Eductor	EDUCTOR	1/1/2016
WTP.ZW1.FCV-320-1	FCV-320-1 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW1.FCV-320-10	FCV-320-10 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW1.FCV-320-2	FCV-320-2 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW1.FCV-320-3	FCV-320-3 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW1.FCV-320-4	FCV-320-4 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW1.FCV-320-5	FCV-320-5 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW1.FCV-320-6	FCV-320-6 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW1.FCV-320-7	FCV-320-7 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW1.FCV-320-8	FCV-320-8 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW1.FCV-320-9	FCV-320-9 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW1.FIT-3520-1	FIT-3520-1 Permeate Flow Meter ZW1-1	METERPW	3/25/2016
WTP.ZW1.FIT-3520-10	FIT-3520-10 Permeate flow Meter	METER	1/1/2016
WTP.ZW1.FIT-3520-2	FIT-3520-2 Permeate flow Meter	METER	1/1/2016
WTP.ZW1.FIT-3520-3	FIT-3520-3 Permeate Flow Meter ZW1-3	METERPW	3/25/2016
WTP.ZW1.FIT-3520-4	FIT-3520-4 Permeate flow Meter	METER	1/1/2016
WTP.ZW1.FIT-3520-5	FIT-3520-5 Permeate flow Meter	VALVE	1/1/2016
WTP.ZW1.FIT-3520-6	FIT-3520-6 Permeate flow Meter	METER	1/1/2016
WTP.ZW1.FIT-3520-7	FIT-3520-7 Permeate flow Meter	METER	1/1/2016
WTP.ZW1.FIT-3520-8	FIT-3520-8 Permeate flow Meter	METER	1/1/2016
WTP.ZW1.FIT-3520-9	FIT-3520-9 Permeate flow Meter	METER	1/1/2016
WTP.ZW1.FV-320-A1	FV-320-A1 CEB Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-A10	FV-320-A10 CEB Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-A2	FV-320-A2 CEB Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-A3	FV-320-A3 CEB Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-A4	FV-320-A4 CEB Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-A5	FV-320-A5 CEB Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-A6	FV-320-A6 CEB Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-A7	FV-320-A7 CEB Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-A8	FV-320-A8 CEB Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-A9	FV-320-A9 CEB Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-B10	FV-320-B10 Back Pulse Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-B9	FV-320-B9 Back Pulse Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-C10	FV-320-C10 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-320-C9	FV-320-C9 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-A1	FV-321-A1 Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-A10	FV-321-A10 Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-A2	FV-321-A2 Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-A3	FV-321-A3 Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-A4	FV-321-A4 Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-A5	FV-321-A5 Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-A6	FV-321-A6 Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-A7	FV-321-A7 Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-A8	FV-321-A8 Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-A9	FV-321-A9 Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-B1	FV-321-B1 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-B10	FV-321-B10 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-B2	FV-321-B2 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-B3	FV-321-B3 Basin Drain Valve	VALVE	1/1/2016

DCMWTP Active Assets

WTP.ZW1.FV-321-B4	FV-321-B4 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-B5	FV-321-B5 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-B6	FV-321-B6 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-B7	FV-321-B7 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-B8	FV-321-B8 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-B9	FV-321-B9 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-C1	FV-321-C1 Basin Fill Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-C10	FV-321-C10 Basin Fill Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-C2	FV-321-C2 Basin Fill Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-C3	FV-321-C3 Basin Fill Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-C4	FV-321-C4 Basin Fill Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-C5	FV-321-C5 Basin Fill Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-C6	FV-321-C6 Basin Fill Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-C7	FV-321-C7 Basin Fill Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-C8	FV-321-C8 Basin Fill Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-321-C9	FV-321-C9 Basin Fill Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-A1	FV-322-A1 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-A10	FV-322-A10 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-A2	FV-322-A2 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-A3	FV-322-A3 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-A4	FV-322-A4 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-A5	FV-322-A5 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-A6	FV-322-A6 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-A7	FV-322-A7 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-A8	FV-322-A8 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-A9	FV-322-A9 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-B1	FV-322-B1 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-B10	FV-322-B10 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-B2	FV-322-B2 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-B3	FV-322-B3 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-B4	FV-322-B4 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-B5	FV-322-B5 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-B6	FV-322-B6 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-B7	FV-322-B7 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-B8	FV-322-B8 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-B9	FV-322-B9 Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-C1	FV-322-C1 Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-C10	FV-322-C10 Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-C2	FV-322-C2 Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-C3	FV-322-C3 Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-C4	FV-322-C4 Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-C5	FV-322-C5 Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-C6	FV-322-C6 Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-C7	FV-322-C7 Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-C8	FV-322-C8 Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-322-C9	FV-322-C9 Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-A1	FV-323-A1 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-A10	FV-323-A10 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-A2	FV-323-A2 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-A3	FV-323-A3 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-A4	FV-323-A4 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-A5	FV-323-A5 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-A6	FV-323-A6 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-A7	FV-323-A7 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-A8	FV-323-A8 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-A9	FV-323-A9 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-B1	FV-323-B1 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-B10	FV-323-B10 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-B2	FV-323-B2 CIP Basin Drain Valve	VALVE	1/1/2016

DCMWTP Active Assets

WTP.ZW1.FV-323-B3	FV-323-B3 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-B4	FV-323-B4 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-B5	FV-323-B5 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-B6	FV-323-B6 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-B7	FV-323-B7 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-B8	FV-323-B8 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-B9	FV-323-B9 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-C1	FV-323-C1 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-C10	FV-323-C10 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-C2	FV-323-C2 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-C3	FV-323-C3 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-C4	FV-323-C4 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-C5	FV-323-C5 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-C6	FV-323-C6 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-C7	FV-323-C7 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-C8	FV-323-C8 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-323-C9	FV-323-C9 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-A1	FV-324-A1 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-A10	FV-324-A10 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-A2	FV-324-A2 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-A3	FV-324-A3 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-A4	FV-324-A4 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-A5	FV-324-A5 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-A6	FV-324-A6 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-A7	FV-324-A7 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-A8	FV-324-A8 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-A9	FV-324-A9 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-B1	FV-324-B1 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-B10	FV-324-B10 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-B2	FV-324-B2 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-B3	FV-324-B3 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-B4	FV-324-B4 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-B5	FV-324-B5 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-B6	FV-324-B6 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-B7	FV-324-B7 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-B8	FV-324-B8 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-B9	FV-324-B9 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-C1	FV-324-C1 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-C10	FV-324-C10 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-C2	FV-324-C2 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-C3	FV-324-C3 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-C4	FV-324-C4 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-C5	FV-324-C5 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-C6	FV-324-C6 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-C7	FV-324-C7 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-C8	FV-324-C8 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-324-C9	FV-324-C9 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-325-1	FV-325-1 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-325-10	FV-325-10 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-325-2	FV-325-2 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-325-3	FV-325-3 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-325-4	FV-325-4 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-325-5	FV-325-5 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-325-6	FV-325-6 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-325-7	FV-325-7 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-325-8	FV-325-8 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-325-9	FV-325-9 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-326-1	FV-326-1 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-326-10	FV-326-10 Post MIT Priming Flow Valve	VALVE	1/1/2016

DCMWTP Active Assets

WTP.ZW1.FV-326-2	FV-326-2 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-326-3	FV-326-3 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-326-4	FV-326-4 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-326-5	FV-326-5 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-326-6	FV-326-6 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-326-7	FV-326-7 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-326-8	FV-326-8 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-326-9	FV-326-9 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-A10	FV-327-A10 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-A9	FV-327-A9 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-B10	FV-327-B10 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-B9	FV-327-B9 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-C10	FV-327-C10 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-C9	FV-327-C9 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-D10	FV-327-D10 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-D9	FV-327-D9 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-E10	FV-327-E10 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-E9	FV-327-E9 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-F10	FV-327-F10 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-F9	FV-327-F9 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-G10	FV-327-G10 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-327-G9	FV-327-G9 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-329-1	FV-329-1 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-329-10	FV-329-10 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-329-2	FV-329-2 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-329-3	FV-329-3 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-329-4	FV-329-4 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-329-5	FV-329-5 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-329-6	FV-329-6 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-329-7	FV-329-7 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-329-8	FV-329-8 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-329-9	FV-329-9 Post MIT Priming Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-A1	FV-3466-A1 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-A2	FV-3466-A2 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-A3	FV-3466-A3 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-A4	FV-3466-A4 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-A5	FV-3466-A5 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-A6	FV-3466-A6 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-A7	FV-3466-A7 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-A8	FV-3466-A8 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-B1	FV-3466-B1 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-B2	FV-3466-B2 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-B3	FV-3466-B3 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-B4	FV-3466-B4 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-B5	FV-3466-B5 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-B6	FV-3466-B6 Permeate Valve ZW1-6	VALVE	1/1/2016
WTP.ZW1.FV-3466-B7	FV-3466-B7 Permeate Valve	VALVE	1/1/2008
WTP.ZW1.FV-3466-B8	FV-3466-B8 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-C1	FV-3466-C1 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-C2	FV-3466-C2 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-C3	FV-3466-C3 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-C4	FV-3466-C4 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-C5	FV-3466-C5 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-C6	FV-3466-C6 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-C7	FV-3466-C7 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-C8	FV-3466-C8 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-D1	FV-3466-D1 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-D2	FV-3466-D2 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-D3	FV-3466-D3 Permeate Valve	VALVE	1/1/2016

DCMWTP Active Assets

WTP.ZW1.FV-3466-D4	FV-3466-D4 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-D5	FV-3466-D5 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-D6	FV-3466-D6 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-D7	FV-3466-D7 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3466-D8	FV-3466-D8 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-A10	FV-FV-3467-A10 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-A9	FV-FV-3467-A9 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-B10	FV-FV-3467-B10 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-B9	FV-FV-3467-B9 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-C10	FV-FV-3467-C10 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-C9	FV-FV-3467-C9 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-D10	FV-FV-3467-D10 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-D9	FV-FV-3467-D9 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-E10	FV-FV-3467-E10 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-E9	FV-FV-3467-E9 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-F10	FV-FV-3467-F10 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-F9	FV-FV-3467-F9 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-G10	FV-FV-3467-G10 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3467-G9	FV-FV-3467-G9 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-A1	FV-3468-A1 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-A2	FV-3468-A2 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-A3	FV-3468-A3 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-A4	FV-3468-A4 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-A5	FV-3468-A5 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-A6	FV-3468-A6 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-A7	FV-3468-A7 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-A8	FV-3468-A8 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-B1	FV-3468-B1 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-B2	FV-3468-B2 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-B3	FV-3468-B3 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-B4	FV-3468-B4 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-B5	FV-3468-B5 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-B6	FV-3468-B6 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-B7	FV-3468-B7 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-B8	FV-3468-B8 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-C1	FV-3468-C1 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-C2	FV-3468-C2 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-C3	FV-3468-C3 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-C4	FV-3468-C4 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-C5	FV-3468-C5 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-C6	FV-3468-C6 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-C7	FV-3468-C7 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-C8	FV-3468-C8 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-D1	FV-3468-D1 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-D2	FV-3468-D2 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-D3	FV-3468-D3 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-D4	FV-3468-D4 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-D5	FV-3468-D5 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-D6	FV-3468-D6 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-D7	FV-3468-D7 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3468-D8	FV-3468-D8 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3470-1	FV-3470-1 Back Pulse Valve	VALVE	1/1/2016
WTP.ZW1.FV-3470-2	FV-3470-2 Back Pulse Valve	VALVE	1/1/2016
WTP.ZW1.FV-3470-3	FV-3470-3 Back Pulse Valve	VALVE	1/1/2016
WTP.ZW1.FV-3470-4	FV-3470-4 Back Pulse Valve	VALVE	1/1/2016
WTP.ZW1.FV-3470-5	FV-3470-5 Back Pulse Valve	VALVE	1/1/2016
WTP.ZW1.FV-3470-6	FV-3470-6 Back Pulse Valve	VALVE	1/1/2016
WTP.ZW1.FV-3470-7	FV-3470-7 Back Pulse Valve	VALVE	1/1/2016
WTP.ZW1.FV-3470-8	FV-3470-8 Back Pulse Valve	VALVE	1/1/2016

DCMWTP Active Assets

WTP.ZW1.FV-3475-1	FV-3475-1 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-3475-10	FV-3475-10 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-3475-2	FV-3475-2 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-3475-3	FV-3475-3 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-3475-4	FV-3475-4 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-3475-5	FV-3475-5 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-3475-6	FV-3475-6 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-3475-7	FV-3475-7 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-3475-8	FV-3475-8 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW1.FV-3496-1	FV-3496-1 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3496-2	FV-3496-2 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3496-3	FV-3496-3 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3496-4	FV-3496-4 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3496-5	FV-3496-5 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3496-6	FV-3496-6 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3496-7	FV-3496-7 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3496-8	FV-3496-8 MIT Feed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-A1	FV-3560-A1 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-A10	FV-3560-A10 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-A2	FV-3560-A2 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-A3	FV-3560-A3 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-A4	FV-3560-A4 Permeate Valve	VALVE	3/4/2015
WTP.ZW1.FV-3560-A5	FV-3560-A5 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-A6	FV-3560-A6 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-A7	FV-3560-A7 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-A8	FV-3560-A8 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-A9	FV-3560-A9 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-B1	FV-3560-B1 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-B10	FV-3560-B10 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-B2	FV-3560-B2 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-B3	FV-3560-B3 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-B4	FV-3560-B4 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-B5	FV-3560-B5 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-B6	FV-3560-B6 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-B7	FV-3560-B7 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-B8	FV-3560-B8 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-B9	FV-3560-B9 Permeate Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-C1	FV-3560-C1 Permeate Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-C10	FV-3560-C10 Permeate Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-C2	FV-3560-C2 Permeate Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-C3	FV-3560-C3 Permeate Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-C4	FV-3560-C4 Permeate Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-C5	FV-3560-C5 Permeate Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-C6	FV-3560-C6 Permeate Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-C7	FV-3560-C7 Permeate Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-C8	FV-3560-C8 Permeate Bleed Valve	VALVE	1/1/2016
WTP.ZW1.FV-3560-C9	FV-3560-C9 Permeate Bleed Valve	VALVE	1/1/2016
WTP.ZW1.M35-1	ZW1-1 Permeate Motor	MOTOR	1/1/2016
WTP.ZW1.M35-10	ZW1-10 Permeate motor	MOTOR	1/1/2004
WTP.ZW1.M35-2	ZW1-2 Permeate motor	MOTOR	1/1/2016
WTP.ZW1.M35-3	ZW1-3 Permeate motor	MOTOR	1/1/2016
WTP.ZW1.M35-4	ZW1-4 Permeate motor	MOTOR	1/1/2001
WTP.ZW1.M35-5	ZW1-5 Permeate motor	MOTOR	1/1/2016
WTP.ZW1.M35-6	ZW1-6 Permeate motor	MOTOR	1/1/2016
WTP.ZW1.M35-7	ZW1-7 Permeate motor	MOTOR	1/1/2016
WTP.ZW1.M35-8	ZW1-8 Permeate motor	MOTOR	1/1/2016
WTP.ZW1.M35-9	ZW1-9 Permeate motor	MOTOR	1/1/2016
WTP.ZW1.P-35-1.VFD	WTP.ZW1.P35-1.VFD	VFD	1/1/2016
WTP.ZW1.P35-10	P-35-10 ZW1-10 Permeate Pump	PUMP	1/1/2016

DCMWTP Active Assets

WTP.ZW1.P35-2	P-35-2 ZW1-2 Permeate Pump	PUMP	1/1/2016
WTP.ZW1.P35-2/1	P-35-2 ZW1-2 Permeate Pump Motor	MOTOR	1/1/2016
WTP.ZW1.P35-3	P-35-3 ZW1-3 Permeate Pump	PUMP	1/1/2002
WTP.ZW1.P35-4	P-35-4 ZW1-4 Permeate Pump	PUMP	1/1/2016
WTP.ZW1.P35-5	P-35-5 ZW1-5 Permeate Pump	PUMP	1/1/2016
WTP.ZW1.P35-6	P-35-6 ZW1-6 Permeate pump	PUMP	3/9/2016
WTP.ZW1.P35-7	P-35-7 ZW1-7 Permeate Pump	PUMP	1/1/2016
WTP.ZW1.P35-8	P-35-8 ZW1-8 Permeate Pump	PUMP	1/1/2016
WTP.ZW1.P35-9	P-35-9 ZW1-9 Permeate Pump	PUMP	1/1/2016
WTP.ZW1.P35.1	P-35-1 ZW1-1 Permeate Pump	PUMP	1/1/2016
WTP.ZW1.SV-313-A1	SV-313-1 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW1.SV-313-A10	SV-313-10 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW1.SV-313-A2	SV-313-2 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW1.SV-313-A3	SV-313-3 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW1.SV-313-A4	SV-313-4 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW1.SV-313-A5	SV-313-5 Turbidimeter flow solenoid valve	METER	1/1/2016
WTP.ZW1.SV-313-A6	SV-313-6 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW1.SV-313-A7	SV-313-7 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW1.SV-313-A8	SV-313-8 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW1.SV-313-A9	SV-313-9 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW1.SV-325-1	SV-325-1 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-325-10	SV-325-10 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-325-2	SV-325-2 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-325-3	SV-325-3 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-325-4	SV-325-4 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-325-5	SV-325-5 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-325-6	SV-325-6 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-325-7	SV-325-7 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-325-8	SV-325-8 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-325-9	SV-325-9 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-326-1	SV-326-1 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-326-10	SV-326-10 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-326-2	SV-326-2 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-326-3	SV-326-3 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-326-4	SV-326-4 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-326-5	SV-326-5 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-326-6	SV-326-6 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-326-7	SV-326-7 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-326-8	SV-326-8 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-326-9	SV-326-9 Post MIT Priming Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-350-1	SV-350-1 eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-350-10	SV-350-10 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-350-2	SV-350-2 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-350-3	SV-350-3 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-350-4	SV-350-4 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-350-5	SV-350-5 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-350-6	SV-350-6 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-350-7	SV-350-7 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-350-8	SV-350-8 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW1.SV-350-9	SV-350-9 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW2.2ND-STG.PIPING	Second Stage Piping	PIPING	1/26/2022
WTP.ZW2.ACT-340-A3	ACT-340-A3 CIP Basin Fill Valve Actuator	*	12/1/2012
WTP.ZW2.AIT-210	AIT-210 Turbidimeter	METER	1/29/2019
WTP.ZW2.AIT-3737-1	AIT-3737-1 Turbidimeter	METER	1/1/2016
WTP.ZW2.AIT-3737-1C	AIT-3737-1 Turbidimeter Controller	CONTRLLR	1/1/2012
WTP.ZW2.AIT-3737-2	AIT-3737-2 Turbidimeter	METER	1/1/2016
WTP.ZW2.AIT-3737-2C	AIT-3737-2 Turbidimeter Controller	CONTRLLR	1/1/2012
WTP.ZW2.AIT-3737-3	AIT-3737-3 Turbidimeter	METER	1/1/2016
WTP.ZW2.AIT-3737-3C	AIT-3737-3 Turbidimeter Controller	CONTRLLR	1/1/2012

DCMWTP Active Assets

WTP.ZW2.CV-1	ZW2-1 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW2.CV-2	ZW2-2 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW2.CV-3	ZW2-3 Permeate Check Valve	VALVE	1/1/2016
WTP.ZW2.E-370-1	E-370-1 Eductor	EDUCTOR	1/1/2016
WTP.ZW2.E-370-2	E-370-2 Eductor	EDUCTOR	1/1/2016
WTP.ZW2.E-370-3	E-370-3 Eductor	EDUCTOR	1/1/2016
WTP.ZW2.FCV-340-1	FCV-340-1 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW2.FCV-340-2	FCV-340-2 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW2.FCV-340-3	FCV-340-3 Basin Fill Flow Valve	VALVE	1/1/2016
WTP.ZW2.FIT-3720-1	FIT-3720-1 Permeate Flow Meter	METER	1/1/2016
WTP.ZW2.FIT-3720-2	FIT-3720-2 Permeate Flow Meter	METER	1/1/2016
WTP.ZW2.FIT-3720-3	FIT-3720-3 Permeate Flow Meter	METER	1/1/2016
WTP.ZW2.FIT3620-1	FIT-3620-1 Reject Flow Meter	METER	1/1/2016
WTP.ZW2.FIT3620-2	FIT-3620-2 Reject Flow Meter	METER	1/1/2016
WTP.ZW2.FIT3620-3	FIT-3620-3 Reject Flow Meter	METER	1/1/2016
WTP.ZW2.FV-340-A1	FV-340-A1 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW2.FV-340-A2	FV-340-A2 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW2.FV-340-A3	FV-340-A3 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW2.FV-340-B1	FV-340-B1 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW2.FV-340-B2	FV-340-B2 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW2.FV-340-B3	FV-340-B3 CIP Basin Fill Valve	VALVE	1/1/2016
WTP.ZW2.FV-340-C1	FV-340-C1 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW2.FV-340-C2	FV-340-C2 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW2.FV-340-C3	FV-340-C3 CIP Bleed Valve	VALVE	1/1/2016
WTP.ZW2.FV-341-A1	FV-341-A1 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW2.FV-341-A2	FV-341-A2 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW2.FV-341-A3	FV-341-A3 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW2.FV-341-B1	FV-341-B1 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW2.FV-341-B2	FV-341-B2 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW2.FV-341-B3	FV-341-B3 CIP Basin Drain Valve	VALVE	1/1/2016
WTP.ZW2.FV-341-C1	FV-341-C1 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW2.FV-341-C2	FV-341-C2 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW2.FV-341-C3	FV-341-C3 CIP Basin Drain Bleed Valve	VALVE	1/1/2016
WTP.ZW2.FV-3661-1	FV-3661-1 Reject Flow Valve	VALVE	12/1/2012
WTP.ZW2.FV-3661-2	FV-3661-2 Reject Flow Valve	VALVE	1/1/2016
WTP.ZW2.FV-3661-3	FV-3661-3 Reject Flow Valve	*	12/1/2012
WTP.ZW2.FV-3670-1	FV-3670-1 Back Pulse Valve	VALVE	1/1/2016
WTP.ZW2.FV-3670-2	FV-3670-2 Back Pusle Valve	VALVE	1/1/2008
WTP.ZW2.FV-3670-3	FV-3670-3 Back Pusle Valve	VALVE	2/11/2015
WTP.ZW2.FV-3675-A1	FV-3675-A1 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW2.FV-3675-A2	FV-3675-A2 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW2.FV-3675-A3	FV-3675-A3 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW2.FV-3675-B1	FV-3675-B1 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW2.FV-3675-B2	FV-3675-B2 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW2.FV-3675-B3	FV-3675-B3 Aeration Flow Valve	VALVE	1/1/2016
WTP.ZW2.FV-3760-1	FV-3760-1 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.FV-3760-2	FV-3760-2 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.FV-3760-3	FV-3760-3 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.HV-3466-A1	HV-3466-A1 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.HV-3466-A2	HV-3466-A2 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.HV-3466-A3	HV-3466-A3 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.HV-3466-B1	HV-3466-B1 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.HV-3466-B2	HV-3466-B2 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.HV-3466-B3	HV-3466-B3 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.HV-3466-C1	HV-3466-C1 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.HV-3466-C2	HV-3466-C2 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.HV-3466-C3	HV-3466-C3 Permeate Valve	VALVE	1/1/2016
WTP.ZW2.M36-1	M36-1 Reject Pump Motor	MOTOR	1/1/2016
WTP.ZW2.M36-2	M36-2 Reject Pump Motor	MOTOR	1/1/2001

DCMWTP Active Assets

WTP.ZW2.M36-3	M36-3 Reject Pump Motor	MOTOR	1/1/2013
WTP.ZW2.M370-1	ZW2-1 Permeate Motor	MOTOR	1/1/2013
WTP.ZW2.M370-2	ZW2-2 Permeate motor	MOTOR	1/1/2016
WTP.ZW2.M370-3	ZW2-3 Permeate motor	MOTOR	1/1/2016
WTP.ZW2.P35-2VFD	WTP.ZW2.P35-2.VFD	VFD	1/1/2002
WTP.ZW2.P36-1	ZW2 -P36-1 REJECT PUMP	PUMP	12/1/2013
WTP.ZW2.P36-2	ZW2 -P36-2 REJECT PUMP	PUMP	2/6/2015
WTP.ZW2.P36-3	ZW2 -P36-3 REJECT PUMP	PUMP	2/6/2015
WTP.ZW2.P370-1	P-370-1 ZW2-1 Permeate Pump	PUMP	1/1/2016
WTP.ZW2.P370-1.VFD	WTP.ZW2.P370-1.VFD	VFD	1/1/2016
WTP.ZW2.P370-2	P-370-2 ZW2-2 Permeate Pump	PUMP	1/1/2016
WTP.ZW2.P370-2.VFD	WTP.ZW2.P370-2.VFD	VFD	1/1/2016
WTP.ZW2.P370-3	P-370-3 ZW2-3 Permeate Pump	PUMP	1/1/2016
WTP.ZW2.P370-3.VFD	WTP.ZW2.P370-3.VFD	VFD	1/1/2016
WTP.ZW2.SV-313-A1	SV-313-A1 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW2.SV-313-A2	SV-313-A2 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW2.SV-313-A3	SV-313-A3 Turbidimeter flow solenoid valve	VALVE	1/1/2016
WTP.ZW2.SV-370-1	SV-370-1 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW2.SV-370-2	SV-370-2 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW2.SV-370-3	SV-370-3 Eductor Solenoid Valve	VALVE	1/1/2016
WTP.ZW2.ZW2-1	Membrane Train ZW2-1	FILTER	10/20/2001
WTP.ZW2.ZW2-2	Membrane Train ZW2-2	FILTER	8/14/2002
WTP.ZW2.ZW2-3	Membrane Train ZW2-3	FILTER	10/20/2001
WTP.ZW3.P35-3.VFD	WTP.ZW3.P35-3.VFD	VFD	1/1/2016
WTP.ZW4.P35-4VFD	WTP.ZW4.P35-4.VFD	VFD	1/1/2002
WTP.ZW8.P35-8VFD	WTP.ZW8.P35-8.VFD	VFD	1/1/2002
WTP10001	1ST STAGE PERMEATE PUMP 1 VFD P-35-1	VFD	7/21/2008
WTP10001-1	1st STAGE PERMEATE PUMP 1 VFD P-35-1	VFD	5/4/2015
WTP10002	1ST STAGE PERMEATE PUMP 2 VFD P-35-2	VFD	7/21/2008
WTP10002-1	1ST STAGE PERMEATE PUMP 2 VFD P-35-2	VFD	3/24/2009
WTP10003	1ST STAGE PERMEATE PUMP 3 VFD P-35-3	VFD	7/21/2008
WTP10003-1	1ST STAGE PERMEATE PUMP 3 VFD P-35-3	VFD	9/9/2011
WTP10004	1ST STAGE PERMEATE PUMP 4 VFD P-35-4	VFD	7/21/2008
WTP10004-1	1st STAGE PERMEATE PUMP 4 VFD P-35-4	VFD	8/3/2015
WTP10005-1	1ST STAGE PERMEATE PUMP 5 VFD P-35-5	VFD	3/24/2009
WTP10006	1ST STAGE PERMEATE PUMP 6 VFD P-35-6	VFD	7/21/2008
WTP10007	1ST STAGE PERMEATE PUMP 7 VFD P-35-7	VFD	7/21/2008
WTP10008	1ST STAGE PERMEATE PUMP 8 VFD P-35-8	VFD	7/21/2008
WTP10009	2ND STAGE PERMEATE PUMP 1 VFD P-37-1	VFD	7/21/2008
WTP10012	1ST STAGE PERMEATE PUMP 9 VFD P-35-9	VFD	7/21/2008
WTP10013	1ST STAGE PERMEATE PUMP 10 VFD P-35-10	VFD	7/21/2008
WTP10020	2ND STAGE REJECT PUMP 2 VFD P-36-2	VFD	12/7/2009
WTP10021	2ND STAGE REJECT PUMP 3 VFD P-36-3	VFD	12/7/2009
WTP11101	MOV PANEL M1	CONTROL	7/21/2008
WTP11102	MOV PANEL M2	CONTROL	7/21/2008
WTP11103	MOV PANEL M3	CONTROL	7/21/2008
WTP11104	MOV PANEL M4	CONTROL	7/21/2008
WTP11105	MOV PANEL M5	CONTROL	7/21/2008
WTP11106	MOV PANEL M6	CONTROL	7/21/2008
WTP11107	MOV PANEL M7	CONTROL	7/21/2008
WTP11108	MOV PANEL M8	CONTROL	7/21/2008
WTP11109	MOV PANEL M21	CONTROL	7/21/2008
WTP11110	MOV PANEL M22	CONTROL	7/21/2008
WTP11111	MOV PANEL M23	CONTROL	7/21/2008
WTP11121	CONTROL CABINET ICP-1	CONTROL	7/21/2008
WTP11122	CONTROL CABINET ICP-2	CONTROL	7/21/2008
WTP11123	CONTROL CABINET ICP-3	CONTROL	7/21/2008
WTP16001	WTP MCC	PS	7/21/2008
WTP17001	MSB 1	ELEC	7/21/2008

DCMWTP Active Assets

WTP17002	DSB 1	ELEC	7/21/2008
WTP17003	DSB 2	ELEC	7/21/2008
WTP17004	MCC 1	ELEC	7/21/2008
WTP17005	MCC 2	ELEC	7/21/2008
WTP17007	MAIN BREAKER	ELEC	7/21/2008
WTP17008	PANEL LA	ELEC	7/21/2008
WTP17009	PANEL LC	ELEC	7/21/2008
WTP17010	PANEL EB	ELEC	7/21/2008
WTP17011	PANEL LEB	ELEC	7/21/2008
WTP17012	PANEL EA	ELEC	7/21/2008
WTP17013	PANEL LEA	ELEC	7/21/2008
WTP17014	PANEL LD	ELEC	7/21/2008
WTP17015	TUSS PUMP BREAKER PANEL	ELEC	7/21/2008
WTP17016	PANEL LCP-5501 - Caustic Pumps	ELEC	10/5/2009
WTP17027	LIGHTING PANEL FOR POLE AND WALL LIGHTS	ELEC	7/21/2008
WTP18101	T 1 TRANSFORMER	ELEC	7/21/2008
WTP1STSTAGEAIRVALVE	WTP 1st Stage Airation Valve FCV-8566	CTLVALPW	12/22/2009
WTP20000	2ND STAGE PERMEATE PUMP 3 P-37-3	PUMP	7/21/2008
WTP20000-1	2ND STAGE PERMEATE PUMP MOTOR P-37-3	MOTOR	5/17/2018
WTP20001	2ND STAGE PERMEATE PUMP P-37-1	PUMP	7/21/2008
WTP20001-1	2ND STAGE PERMEATE PUMP MOTOR P-37-1	MOTOR	5/17/2018
WTP20002	2ND STAGE PERMEATE PUMP 2 P-37-2	PUMP	7/21/2008
WTP20002-1	2ND STAGE PERMEATE PUMP MOTOR P-37-2	MOTOR	5/17/2018
WTP20003	1ST STAGE PERMEATE PUMP 1 P-35-1	PUMP	7/21/2008
WTP20004	1ST STAGE PERMEATE PUMP 2 P-35-2	PUMP	7/21/2008
WTP20005	1ST STAGE PERMEATE PUMP 3 P-35-3	PUMP	7/21/2008
WTP20006	1ST STAGE PERMEATE PUMP 4 P-35-4	PUMP	7/21/2008
WTP20007	1ST STAGE PERMEATE PUMP 5 P-35-5	PUMP	7/21/2008
WTP20008	1ST STAGE PERMEATE PUMP 6 P-35-6	PUMP	7/21/2008
WTP20009	1ST STAGE PERMEATE PUMP 7 P-35-7	PUMP	7/21/2008
WTP20010	1ST STAGE PERMEATE PUMP 8 P-35-8	PUMP	7/21/2008
WTP20011	FYBROC, BASIN DRAIN PUMP 2010	PUMP	7/21/2008
WTP20012	1ST STAGE PERMEATE PUMP 9 P-35-9	PUMP	7/21/2008
WTP20013	1ST STAGE PERMEATE PUMP 10 P-35-10	PUMP	7/21/2008
WTP20015	BRINE TRANSFER PUMP	PUMP	7/21/2008
WTP20016	FYBROC, CITRIC ACID PUMP P-6021	PUMP	7/21/2008
WTP21101	2ND STAGE REJECT PUMP P-36-1	PUMP	7/21/2008
WTP21101-1	2ND STAGE REJECT PUMP MOTOR P-36-1	MOTOR	5/17/2018
WTP21102	2ND STAGE REJECT PUMP P-36-2	PUMP	7/21/2008
WTP21102-1	2ND STAGE REJECT PUMP MOTOR P-36-2	MOTOR	5/17/2018
WTP21103	2ND STAGE REJECT PUMP P-36-3	PUMP	7/21/2008
WTP21103-1	2ND STAGE REJECT PUMP MOTOR P-36-3	MOTOR	5/17/2018
WTP21104	CHEMICAL UNLOAD PUMP 1	PUMP	7/21/2008
WTP21105	CHEMICAL UNLOAD PUMP 2	PUMP	7/21/2008
WTP23101	RAW WATER SAMPLE PUMP	PUMP	7/21/2008
WTP23102	HYPO TRANSFER PUMP 5421	PUMP	7/21/2008
WTP23103	FYBROC, HYPO CIP PUMP P-5424	PUMP	7/21/2008
WTP23104	CAUSTIC TRANSFER PUMP 5521	PUMP	7/21/2008
WTP23106	AMMONIA FINISH TRANSFER PUMP 6122	PUMP	7/21/2008
WTP23107	AMMONIA RAW TRANSFER PUMP 6121	PUMP	7/21/2008
WTP23110-FIN	FINISHED ANALYZER PANEL RECYCLE PUMP	PUMP	12/8/2009
WTP23110-RAW	RAW ANALYZER PANEL RECYCLE PUMP	PUMP	12/8/2009
WTP23110-ZW2	2ND STAGE ANALYZER PANEL RECYCLE PUMP	PUMP	12/8/2009
WTP27001	MIT AIR COMPRESSORS 1 (A)	COMPRESS	7/21/2008
WTP27002-2	MIT AIR COMPRESSORS 2 (B)	COMPRESS	4/3/2012
WTP27005	SURGE TANK COMPRESSOR	COMPRESS	7/21/2008
WTP28001	HYPO BLOWER 1	BLOWER	7/21/2008
WTP28002	HYPO BLOWER 2	BLOWER	7/21/2008
WTP28003	BULK SALT STORAGE TANK BLOWER	BLOWER	7/21/2008

DCMWTP Active Assets

WTP28105	TURBINE E	TURBINE	7/21/2008
WTP29001	PAC METERING PUMP 7141	PUMP	7/21/2008
WTP29002	PAC METERING PUMP 7142	PUMP	7/21/2008
WTP29003	LAMELLA SETTLER POLYMER SYSTEM 7241	PUMP	7/21/2008
WTP29004	CENTRIFUGE POLYMER SYSTEM 7242	PUMP	7/21/2008
WTP29005	BISULFITE METERING PUMP 5341	PUMP	7/21/2008
WTP29006	BISULFITE METERING PUMP 5342	PUMP	7/21/2008
WTP29007	HYPO FINISHED METERING PUMP 5445	PUMP	7/21/2008
WTP29008	HYPO FINISHED METERING PUMP 5446	PUMP	7/21/2008
WTP29009	CAUSTIC METER PUMP 5541	PUMP	7/21/2008
WTP29010	CAUSTIC METER PUMP 5542	PUMP	7/21/2008
WTP29011	AMMONIA FINISH METERING PUMP 6143	PUMP	7/21/2008
WTP29012	AMMONIA FINISH METERING PUMP 6144	PUMP	7/21/2008
WTP29013	HYPO METERING PUMP 5447	PUMP	7/21/2008
WTP29014	HYPO METERING PUMP 5448	PUMP	7/21/2008
WTP29015	HYPO RAW METERING PUMP 5441	PUMP	7/21/2008
WTP29016	HYPO RAW METERING PUMP 5442	PUMP	7/21/2008
WTP29017	HYPO BACK PULSE METERING PUMP 5443	PUMP	7/21/2008
WTP29018	HYPO BACK PULSE METERING PUMP 5444	PUMP	7/21/2008
WTP29019	AMMONIA RAW METERING PUMP 6141	PUMP	7/21/2008
WTP29020	AMMONIA RAW METERING PUMP 6142	PUMP	7/21/2008
WTP29021	HYDRACELL CHEM. METERING PUMP SER. 241792	PUMP	8/24/2011
WTP29022	HYDRACELL CHEM. METERING PUMP SER. 242118	PUMP	8/24/2011
WTP2NDSTAGEAIRVALVE	WTP 2nd Stage Airation Valve FCV-8568	CTLVALPW	12/22/2009
WTP3100	Lab 2100N turbidimeter	XDUCER	7/21/2008
WTP31005	2ND STAGE PERMEATE PUMP 1 MOTOR P-37-1	MOTOR	7/21/2008
WTP31006	2ND STAGE PERMEATE PUMP 2 MOTOR P-37-2	MOTOR	7/21/2008
WTP31007	2ND STAGE PERMEATE PUMP 3 MOTOR P-37-3	MOTOR	7/21/2008
WTP31008	BASIN DRAIN PUMP MOTOR P-2010	MOTOR	7/21/2008
WTP31009	1ST STAGE PERMEATE PUMP 1 MOTOR P-35-1	MOTOR	7/21/2008
WTP31010	1ST STAGE PERMEATE PUMP 2 MOTOR P-35-2	MOTOR	7/21/2008
WTP31011	1ST STAGE PERMEATE PUMP 3 MOTOR P-35-3	MOTOR	7/21/2008
WTP31012	1ST STAGE PERMEATE PUMP 4 MOTOR P-35-4	MOTOR	7/21/2008
WTP31013	1ST STAGE PERMEATE PUMP 5 MOTOR P-35-5	MOTOR	7/21/2008
WTP31014	1ST STAGE PERMEATE PUMP 6 MOTOR P-35-6	MOTOR	7/21/2008
WTP31015	1ST STAGE PERMEATE PUMP 7 MOTOR P-35-7	MOTOR	7/21/2008
WTP31016	1ST STAGE PERMEATE PUMP 8 MOTOR P-35-8	MOTOR	7/21/2008
WTP31017	VACUUM PUMP A MOTOR M-92-A	MOTOR	7/21/2008
WTP31018	VACUUM PUMP B MOTOR M-92-B	MOTOR	7/21/2008
WTP31019	VACUUM PUMP C MOTOR M-92-C	MOTOR	7/21/2008
WTP31020	1ST STAGE PERMEATE PUMP 9 MOTOR P-35-9	MOTOR	7/21/2008
WTP31021	1ST STAGE PERMEATE PUMP 10 MOTOR P-35-10	MOTOR	7/21/2008
WTP3469-10-ASV	ZW1_10 FV-3469-10 Angle Seat Valve	VALVE	9/30/2010
WTP3469-10-EDUC	ZW1_10 FV-3469-10 EDUCTOR	VALVE	9/30/2010
WTP3469-9-ASV	ZW1_9 FV-3469-9 Angle Seat Valve	VALVE	9/30/2010
WTP3469-9-EDUC	ZW1_9 FV-3469-9 EDUCTOR	VALVE	9/30/2010
WTP45101	ALUM FEED SYSTEM	CHEM	7/21/2008
WTP45102	POLYMER FEED SYSTEM	CHEM	7/21/2008
WTP45103	BISULFITE FEED SYSTEM	CHEM	7/21/2008
WTP45104	HYPO STORAGE SYSTEM	CHEM	7/21/2008
WTP45105	CITRIC ACID FEED SYSTEM	CHEM	7/21/2008
WTP45107	ION EXCHANGE SYSTEM	CHEM	7/21/2008
WTP45108	RECTIFIER / CLORTEC GENERATION UNIT	CHEM	7/21/2008
WTP45109	CLORTEC SODIUM HYPOCHLORITE GENERATION SYSTEM	CHEM	7/21/2008
WTP45110	HYPO FINISHED WATER FEED SYSTEM	CHEM	7/21/2008
WTP45111	CAUSTIC FEED SYSTEM	CHEM	7/21/2008
WTP45112	AMMONIA FINISH FEED SYSTEM	CHEM	7/21/2008
WTP45113	HYPO REMOTE FEED SYSTEM	CHEM	7/21/2008

DCMWTP Active Assets

WTP45114	HYPO RAW WATER FEED SYSTEM	CHEM	7/21/2008
WTP45115	HYPO BACK PULSE WATER FEED SYSTEM	CHEM	7/21/2008
WTP45116	AMMONIA RAW FEED SYSTEM	CHEM	7/21/2008
WTP52001	3RD STAGE FLOCCULATOR M-7003	MIXER	7/21/2008
WTP52002	3RD STAGE FLOCCULATOR M-7023	MIXER	7/21/2008
WTP52003	3RD STAGE FLOCCULATOR M-7043	MIXER	7/21/2008
WTP52301	3RD STAGE FLASH MIXER M-7002	MIXER	7/21/2008
WTP52302	3RD STAGE FLASH MIXER M-7022	MIXER	7/21/2008
WTP52303	3RD STAGE FLASH MIXER M-7042	MIXER	7/21/2008
WTP52801	FILTRATE STATIC MIXER	MIXER	7/21/2008
WTP65501	CENTRIFUGE	CNTIFUGE	7/21/2008
WTP65601	CENTRATE PUMP P-7302	PUMP	1/14/2009
WTP70201	STRAINER 1 7611	STRAINER	7/21/2008
WTP70202	STRAINER 2 7621	STRAINER	7/21/2008
WTP70203	STRAINER 1 7611 - Motor	MOTOR	6/24/2009
WTP70204	STRAINER 2 7621 - Motor	MOTOR	6/24/2009
WTP7021-BFV	SETTLER 7020 INLET VALVE FV-7021	VALVE	8/31/2010
WTP70303	STRAINER 3 7631	STRAINER	7/21/2008
WTP70304	STRAINER 3 7631 - Motor	MOTOR	6/24/2009
WTP70901	OIL SEPARATOR	FACILITY	7/21/2008
WTP71001	1ST STAGE FEED CHANNEL	FACILITY	7/21/2008
WTP71002	1ST STAGE MEMBRANE BASIN TRAIN 1	FACILITY	7/21/2008
WTP71003	1ST STAGE MEMBRANE BASIN TRAIN 2	FACILITY	7/21/2008
WTP71004	1ST STAGE MEMBRANE BASIN TRAIN 3	FACILITY	7/21/2008
WTP71005	1ST STAGE MEMBRANE BASIN TRAIN 4	FACILITY	7/21/2008
WTP71006	1ST STAGE MEMBRANE BASIN TRAIN 5	FACILITY	7/21/2008
WTP71007	1ST STAGE MEMBRANE BASIN TRAIN 6	FACILITY	7/21/2008
WTP71008	1ST STAGE MEMBRANE BASIN TRAIN 7	FACILITY	7/21/2008
WTP71009	1ST STAGE MEMBRANE BASIN TRAIN 8	FACILITY	7/21/2008
WTP71010	1ST STAGE REJECT CHANNEL	FACILITY	7/21/2008
WTP71011	1ST STAGE MEMBRANE BASIN TRAIN 9	FACILITY	9/2/2009
WTP71012	1ST STAGE MEMBRANE BASIN TRAIN 10	FACILITY	9/2/2009
WTP71013	2ND STAGE MEMBRANE BASIN TRAIN 1	FACILITY	9/2/2009
WTP71014	2ND STAGE MEMBRANE BASIN TRAIN 2	FACILITY	9/2/2009
WTP71015	2ND STAGE MEMBRANE BASIN TRAIN 3	FACILITY	9/2/2009
WTP71800	3RD STAGE COAGULANT STORAGE	TANK	7/21/2008
WTP71801	BISULFITE DAY TANK	TANK	7/21/2008
WTP71802	HYPO STORAGE TANK 1	TANK	7/21/2008
WTP71803	HYPO STORAGE TANK 2	TANK	7/21/2008
WTP71804	CAUSTIC TANK	TANK	7/21/2008
WTP71805	CITRIC ACID TANK	TANK	7/21/2008
WTP71808	BULK SALT STORAGE TANK	TANK	7/21/2008
WTP71809	BRINE DAY TANK	TANK	7/21/2008
WTP71810	HYPO DAY TANK FILTER WATER	TANK	7/21/2008
WTP71811	CAUSTIC DAY TANK	TANK	7/21/2008
WTP71813	HYPO DAY TANK REMOTE FEED	TANK	7/21/2008
WTP71814	HYPO DAY TANK RAW WATER	TANK	7/21/2008
WTP71816-1	SLUDGE TANK-1	TANK	8/23/2010
WTP71816-1-FSL	SLUDGE TANK-1 Low-Flow Switch	ELEC	8/23/2010
WTP73001	3RD STAGE SETTLER SYSTEM #1 M-7000	SETTLER	7/1/2002
WTP73002	3RD STAGE SETTLER SYSTEM #2 M-7020	SETTLER	7/1/2002
WTP73003	3RD STAGE SETTLER SYSTEM #3 M-7040	SETTLER	1/2/2004
WTP73101	3RD STAGE THICKENER RAKE M-7004 (#1)	THICKNER	7/21/2008
WTP73102	3RD STAGE THICKENER RAKE M-7024 (#2)	THICKNER	7/1/2002
WTP73103	3RD STAGE THICKENER RAKE M-7044 (#3)	THICKNER	7/21/2008
WTP73301	3RD STAGE SETTLING PLATES 7000	SETTLER	7/21/2008
WTP73302	3RD STAGE SETTLING PLATES 7020	SETTLER	7/21/2008
WTP73303	3RD STAGE SETTLING PLATES 7040	SETTLER	1/11/2010
WTP77701	WATER TREATMENT BUILDING	FACILITY	7/21/2008

DCMWTP Active Assets

WTP79101	2ND STAGE TRAIN 1 REJECT CONTROL VALVE	VALVE	7/21/2008
WTP79102	2ND STAGE TRAIN 2 REJECT CONTROL VALVE	VALVE	7/21/2008
WTP79201	2ND STAGE TRAIN 3 REJECT CONTROL VALVE	VALVE	7/21/2008
WTP79202	1ST STAGE TRAIN 1 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79203	1ST STAGE TRAIN 2 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79204	1ST STAGE TRAIN 3 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79205	1ST STAGE TRAIN 4 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79206	1ST STAGE TRAIN 5 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79207	1ST STAGE TRAIN 6 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79208	1ST STAGE TRAIN 7 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79209	1ST STAGE TRAIN 8 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79210	1ST STAGE TRAIN 1 MIT AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79211	1ST STAGE TRAIN 2 MIT AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79212	1ST STAGE TRAIN 3 MIT AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79213	1ST STAGE TRAIN 4 MIT AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79214	1ST STAGE TRAIN 5 MIT AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79215	1ST STAGE TRAIN 6 MIT AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79216	1ST STAGE TRAIN 7 MIT AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79217	1ST STAGE TRAIN 8 MITAIR VALVE SYSTEM	VALVE	7/21/2008
WTP79218	2ND STAGE TRAIN 1 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79219	2ND STAGE TRAIN 2 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79220	2ND STAGE TRAIN 3 AIR VALVE SYSTEM	VALVE	7/21/2008
WTP79221	1ST STAGE TRAIN 9 AIR VALVE SYSTEM	VALVE	6/16/2009
WTP79222	1ST STAGE TRAIN 10 AIR VALVE SYSTEM	VALVE	6/16/2009
WTP79301	BACKPULSE TANK A INF ISOLATION VALVE	VALVE	7/21/2008
WTP79302	BACKPULSE TANK B INF ISOLATION VALVE	VALVE	7/21/2008
WTP79303	BACKPULSE TANK A EFF ISOLATION VALVE	VALVE	7/21/2008
WTP79303-1	1st Stage BackPulse BFV-8874	VALVE	9/16/2009
WTP79304	BACKPULSE TANK B EFF ISOLATION VALVE	VALVE	7/21/2008
WTP79304-1	2nd Stage BackPulse BFV-8974	VALVE	9/16/2009
WTP79313	TURBINE E CONTROL VALVE	VALVE	1/15/2009
WTP81001	BACKPULSE TANK A	TANK	7/21/2008
WTP81002	BACKPULSE TANK B	TANK	7/21/2008
WTP81003	BACKPULSE TANK SYSTEM PIPING	PIPING	9/30/2009
WTP86201	AIR SEPARATOR VESSEL	TANK	7/21/2008
WTP86202	AIR VACUUM SEPARATOR	TANK	7/21/2008
WTP91101	UNIT HEATER 1A	HVAC	7/21/2008
WTP91102	UNIT HEATER 1B	HVAC	7/21/2008
WTP91103	UNIT HEATER 1C	HVAC	7/21/2008
WTP91104	UNIT HEATER 1D	HVAC	7/21/2008
WTP91301	AIR HANDLING UNIT 1A	HVAC	7/21/2008
WTP91302	AIR HANDLING UNIT 1B	HVAC	7/21/2008
WTP91303	AIR HANDLING UNIT 2A	HVAC	7/21/2008
WTP91304	AIR HANDLING UNIT 2B	HVAC	7/21/2008
WTP91305	AIR FILTER UNIT A	HVAC	7/21/2008
WTP91307	EXHAUST FAN 1B	HVAC	7/21/2008
WTP91312	EXHAUST FAN EF-8B (FLOURIDE TANK AREA)	HVAC	7/21/2008
WTP91313	EXHAUST FAN EF-7 (HYPO TANK AREA)	HVAC	7/21/2008
WTP91314	EXHAUST FAN EF-8A (FLUORIDE PUMP ROOM)	HVAC	7/21/2008
WTP91315	EXHAUST FAN EF-9 (ALUMINUM CHLOROHYDRATE TANK AREA))	HVAC	7/21/2008
WTP91316	POWERED EXHAUST AC 1	HVAC	7/21/2008
WTP91317	POWERED EXHAUST AC 2	HVAC	7/21/2008
WTP91318	POWERED EXHAUST HP 1	HVAC	7/21/2008
WTP91319	POWERED EXHAUST HP 2	HVAC	7/21/2008
WTP91320	POWERED EXHAUST HP 3	HVAC	7/21/2008
WTP91321	CL2 GEN VENTILATION	HVAC	7/21/2008
WTP91501	AIR CONDITIONER 1 MCC Room adjust econmiser	HVAC	7/21/2008
WTP91502	AIR CONDITIONER 2	HVAC	7/21/2008

DCMWTP Active Assets

WTP91503	AIR CONDITIONER 3	HVAC	7/21/2008
WTP91601	HEAT PUMP 1	HVAC	7/21/2008
WTP91602	HEAT PUMP 2	HVAC	7/21/2008
WTP91603	HEAT PUMP 3	HVAC	7/21/2008
WTP95101	FIRE EXSTINGUISHERS PLANT WIDE	SAFETY	7/21/2008
WTP95301	EYE WASH SHOWER HYPO BULK STORAGE #5	SAFETY	7/21/2008
WTP95302	EYE WASH SHOWER CITRIC BULK STORAGE	SAFETY	7/21/2008
WTP95303	EYE WASH SHOWER AMMONIA BULK STORAGE	SAFETY	7/21/2008
WTP95304	EYE WASH SHOWER CHEM DELIVERY AREA	SAFETY	7/21/2008
WTP95305	EYE WASH SHOWER SOUTH WALL TRAIN 1	SAFETY	7/21/2008
WTP95306	EYE WASH SHOWER SOUTH WALL TRAIN 6	SAFETY	7/21/2008
WTP95307	EYE WASH SHOWER SOUTH WALL TRAIN10	SAFETY	7/21/2008
WTP95308	EYE WASH SHOWER ERT ROOM	SAFETY	7/21/2008
WTP95309	Eyewash Shower Ammonia Delivery Area	SAFETY	12/3/2008
WTP96002	FINISH WATER PANEL PH METER	XDUCER	7/21/2008
WTP96003	RAW WATER PANEL PH METER	XDUCER	7/21/2008
WTP96101	ORP ANAYLZER CIP	XDUCER	7/21/2008
WTP96102	2100N lab turbidimeter	XDUCER	7/21/2008
WTP96301	1ST STAGE TRAIN 1 TURBIDITY METER	XDUCER	7/21/2008
WTP96302	1ST STAGE TRAIN 2 TURBIDITY METER	XDUCER	7/21/2008
WTP96303	1ST STAGE TRAIN 3 TURBIDITY METER	XDUCER	7/21/2008
WTP96304	1ST STAGE TRAIN 4 TURBIDITY METER	XDUCER	7/21/2008
WTP96305	1ST STAGE TRAIN 5 TURBIDITY METER	XDUCER	7/21/2008
WTP96306	1ST STAGE TRAIN 6 TURBIDITY METER	XDUCER	7/21/2008
WTP96307	1ST STAGE TRAIN 7 TURBIDITY METER	XDUCER	7/21/2008
WTP96308	1ST STAGE TRAIN 8 TURBIDITY METER	XDUCER	7/21/2008
WTP96309	2ND STAGE TRAIN 1 TURBIDITY METER	XDUCER	7/21/2008
WTP96310	2ND STAGE TRAIN 2 TURBIDITY METER	XDUCER	7/21/2008
WTP96311	2ND STAGE TRAIN 3 TURBIDITY METER	XDUCER	7/21/2008
WTP96312	FINISH WATER PANEL TURBIDITY METER	XDUCER	7/21/2008
WTP96313	RAW WATER PANEL TURBIDITY METER	XDUCER	7/21/2008
WTP96314	1ST STAGE TRAIN 9 TURBIDITY METER	XDUCER	7/21/2008
WTP96315	1ST STAGE TRAIN 10 TURBIDITY METER	XDUCER	7/21/2008
WTP96401	1ST STAGE TRAIN 1 PARTICLE COUNTER	XDUCER	7/21/2008
WTP96402	1ST STAGE TRAIN 2 PARTICLE COUNTER	XDUCER	7/21/2008
WTP96403	1ST STAGE TRAIN 3 PARTICLE COUNTER	XDUCER	7/21/2008
WTP96404	1ST STAGE TRAIN 4 PARTICLE COUNTER	XDUCER	7/21/2008
WTP96405	1ST STAGE TRAIN 5 PARTICLE COUNTER	XDUCER	7/21/2008
WTP96406	1ST STAGE TRAIN 6 PARTICLE COUNTER	XDUCER	7/21/2008
WTP96407	1ST STAGE TRAIN 7 PARTICLE COUNTER	XDUCER	7/21/2008
WTP96408	1ST STAGE TRAIN 8 PARTICLE COUNTER	XDUCER	7/21/2008
WTP96409	1ST STAGE TRAIN 9 PARTICLE COUNTER	XDUCER	7/21/2008
WTP96410	1ST STAGE TRAIN 10 PARTICLE COUNTER	XDUCER	7/21/2008
WTP96501	1ST STAGE TRAIN 1 FLOW METER	XDUCER	7/21/2008
WTP96502	1ST STAGE TRAIN 2 FLOW METER	XDUCER	7/21/2008
WTP96503	1ST STAGE TRAIN 3 FLOW METER	XDUCER	7/21/2008
WTP96504	1ST STAGE TRAIN 4 FLOW METER	XDUCER	7/21/2008
WTP96505	1ST STAGE TRAIN 5 FLOW METER	XDUCER	7/21/2008
WTP96506	1ST STAGE TRAIN 6 FLOW METER	XDUCER	7/21/2008
WTP96507	1ST STAGE TRAIN 7 FLOW METER	XDUCER	7/21/2008
WTP96508	1ST STAGE TRAIN 8 FLOW METER	XDUCER	7/21/2008
WTP96509	2ND STAGE TRAIN 1 FLOW METER	XDUCER	7/21/2008
WTP96510	2ND STAGE TRAIN 2 FLOW METER	XDUCER	7/21/2008
WTP96511	2ND STAGE TRAIN 3 FLOW METER	XDUCER	7/21/2008
WTP96512	FLOW METER INFLUENT	XDUCER	7/21/2008
WTP96513	1ST STAGE BACK PULSE FLOW METER	XDUCER	7/21/2008
WTP96514	2ND STAGE BACK PULSE FLOW METER	XDUCER	7/21/2008
WTP98001	PLC 1	OIT	7/21/2008
WTP98002	OIT 2	OIT	7/21/2008

DCMWTP Active Assets

WTP98003	PLC 2	OIT	7/21/2008
WTP98004	PLC 3	OIT	7/21/2008
WTP98005	OIT 1	OIT	7/21/2008
WTP98301	Crispin Air relief Valve	VALVE	7/21/2008
WTP98302	FV-9284 BRAY BFV priming vacuum isolation	VALVE	7/21/2008
WTP98303	FV-9286 BRAY BFV feed siphon vacuum isolation	VALVE	7/21/2008
WTP98304	MIT VALVE	VALVE	7/21/2008
WTP98305	1ST STAGE TRAIN 3 - MIT SOLENOID	SOLVALVE	7/21/2008
WTP98306	ZW2 2 BLOWER VALVE	VALVE	7/21/2008
WTP98307	BACKPULSE VALVE ZW2 2	VALVE	7/21/2008
WTP98308-1	SETTLER 7000 DUMP VALVE FV-7005	VALVE	1/11/2010
WTP98312	FV-9284 air sep vessel priming vacuum isolation valve	VALVE	7/21/2008
WTP98312B	FV-9286 air sep vessel feed siphon vacuum isolation valve	VALVE	12/8/2011
WTP98434	NaOCI Storage Tank MOV FV-5464		8/28/2009
WTP98510	ZW1_1 FV-3470-1 BFV	VALVE	7/28/2009
WTP98520	ZW1_2 FV-3470-2 BFV	VALVE	7/28/2009
WTP98530	ZW1_3 FV-3470-3 BFV	VALVE	7/28/2009
WTP98540	ZW1_4 FV-3470-4 BFV	VALVE	7/28/2009
WTP98550	ZW1_5 FV-3470-5 BFV	VALVE	7/28/2009
WTP98560	ZW1_6 FV-3470-6 BFV	VALVE	7/28/2009
WTP98570	ZW1_7 FV-3470-7 BFV	VALVE	7/28/2009
WTP98580	ZW1_8 FV-3470-8 BFV	VALVE	7/28/2009
WTP98600	ZW1_9 FV-3466-A-9 BFV	VALVE	7/28/2009
WTP98601	ZW1_9 FV-3466-B-9 BFV	VALVE	7/28/2009
WTP98602	ZW1_9 FV-3466-C-9 BFV	VALVE	7/28/2009
WTP98603	ZW1_9 FV-3466-D-9 BFV	VALVE	7/28/2009
WTP98604	ZW1_9 FV-3466-E-9 BFV	VALVE	7/28/2009
WTP98605	ZW1_9 FV-3466-F-9 BFV	VALVE	7/28/2009
WTP98606	ZW1_9 FV-3466-G-9 BFV	VALVE	7/28/2009
WTP98607	ZW1_9 FV-3467-A-9 BFV	VALVE	7/28/2009
WTP98608	ZW1_9 FV-3467-B-9 BFV	VALVE	7/28/2009
WTP98609	ZW1_9 FV-3467-C-9 BFV	VALVE	7/28/2009
WTP98610	ZW1_9 FV-3467-D-9 BFV	VALVE	7/28/2009
WTP98611	ZW1_9 FV-3467-E-9 BFV	VALVE	7/28/2009
WTP98612	ZW1_9 FV-3467-F-9 BFV	VALVE	7/28/2009
WTP98613	ZW1_9 FV-3467-G-9 BFV	VALVE	7/28/2009
WTP98614	ZW1_10 FV-3466-A-10 BFV	VALVE	7/28/2009
WTP98615	ZW1_10 FV-3466-B-10 BFV	VALVE	7/28/2009
WTP98616	ZW1_10 FV-3466-C-10 BFV	VALVE	7/28/2009
WTP98617	ZW1_10 FV-3466-D-10 BFV	VALVE	7/28/2009
WTP98618	ZW1_10 FV-3466-E-10 BFV	VALVE	7/28/2009
WTP98619	ZW1_10 FV-3466-F-10 BFV	VALVE	7/28/2009
WTP98620	ZW1_10 FV-3466-G-10 BFV	VALVE	7/28/2009
WTP98621	ZW1_10 FV-3467-A-10 BFV	VALVE	7/28/2009
WTP98622	ZW1_10 FV-3467-B-10 BFV	VALVE	7/28/2009
WTP98623	ZW1_10 FV-3467-C-10 BFV	VALVE	7/28/2009
WTP98624	ZW1_10 FV-3467-D-10 BFV	VALVE	7/28/2009
WTP98625	ZW1_10 FV-3467-E-10 BFV	VALVE	7/28/2009
WTP98626	ZW1_10 FV-3467-F-10 BFV	VALVE	7/28/2009
WTP98627	ZW1_10 FV-3467-G-10 BFV	VALVE	7/28/2009
WTP98628	ZW_1 FV-3475-10	SOLVALVE	7/14/2011
WTP98630	ZW2_1 FV-3670-1 BFV	VALVE	7/28/2009
WTP98631	ZW2_2 FV-3670-2 BFV	VALVE	7/28/2009
WTP98632	ZW2_3 FV-3670-3 BFV	VALVE	7/28/2009
WTP98640	ZW2_1 FV-3760-1 BFV	VALVE	9/10/2009
WTP98641	ZW2_2 FV-3760-2 BFV	VALVE	9/10/2009
WTP98642	ZW2_3 FV-3760-3 BFV	VALVE	9/10/2009

DCMWTP Active Assets

WTP99301	ROLL UP DOOR 1	FACILITY	7/21/2008
WTP99302	ROLL UP DOOR 2	FACILITY	7/21/2008
WTP99303	First Stage Train 1 Float Switches	DI	4/19/2002
WTP99304	First Stage Train 2 Float Switches	DI	4/19/2002
WTP99305	First Stage Train 3 Float Switches	DI	4/19/2002
WTP99306	First Stage Train 4 Float Switches	DI	4/19/2002
WTP99307	First Stage Train 5 Float Switches	DI	4/19/2002
WTP99308	First Stage Train 6 Float Switches	DI	4/19/2002
WTP99309	First Stage Train 7 Float Switches	DI	4/19/2002
WTP99310	First Stage Train 8 Float Switches	DI	4/19/2002
WTP99311	First Stage Train 9 Float Switches	DI	4/19/2002
WTP99312	First Stage Train 10 Float Switches	DI	4/19/2002
WTP99313	Second Stage Train 1 Float Switches	DI	4/19/2002
WTP99314	Second Stage Train 2 Float Switches	DI	4/19/2002
WTP99315	Second Stage Train 3 Float Switches	DI	4/19/2002
WTP99316	VACUUM PUMP D MOTOR M-92-D	MOTOR	12/5/2008
WTP99317	Centrate Tank Level Floats	DI	1/12/2009
WTPBUILDING/GROUNDS	WATER TREATMENT PLANT BUILDING/GROUNDS		12/5/2008
WTPGATE1	WTP Horse Wall Automated Gate	SECURITY	8/5/2008
WTPGREENGATE	WTP Green Gate PBX Communications Interface	SECURITY	8/27/2020
WTPHEATER-1	WTP CIP HEATER A	ELEC	10/1/2008
WTPHEATER-2	WTP CIP HEATER B	ELEC	10/1/2008
WTPHEATER-CONTROL	WTP CIP HEATER CONTROL PANEL	CONTROL	10/1/2008
WTPHEATER-SYSTEM	WTP CIP HEATER SYSTEM	ELEC	10/1/2008
WTPLAN126	WTP 126 SWITCH	NETWORK	8/2/2008
WTPNET26	WTP 26 SWITCH	NETWORK	8/2/2008
WTPROUTER	WTP ROUTER	NETWORK	12/12/2011
WTPTELEMROUTER	WTP Cisco ASA5515 ROUTER	NETWORK	12/20/2017
WTPTELESWITCH	WTP Cisco 3650 Layer 3 switch	NETWORK	2/14/2019
WTPVIDEO	WTP Conference RM Video System	INFOTECH	4/17/2014
WTPWASTEHOLDINGPIT	WTP WASTE HOLDING PIT	WETWELL	6/3/2002



Hazen and Sawyer
11260 El Camino Real, Suite 102
San Diego, CA 92130
858.764.5520



David C. McCollom Water Treatment Plant Capacity Reliability Study

Final Report – Revision 1
January 24, 2018

Table of Contents

Table of Contents.....	i
Executive Summary.....	1
1. Recovery of Strainers Backwash Water.....	10
1.1 Background	10
1.2 Proposed Improvements	11
1.3 Solids Removal	12
1.4 Strainer Backwash Recovery Equalization	15
1.5 Proposed Location.....	16
1.6 Electrical Considerations	16
1.7 Impacts to the Existing Backwash Waste Storage Tank and Existing Stage 2 Ultrafiltration.....	17
1.8 Existing Backwash Waste Equalization Tank	18
1.9 Estimation of Probable Cost	20
2. Stage 2 UF Membranes Expansion.....	21
2.1 Proposed Expansion.....	21
2.2 Impacts to Existing Piping and other Stages	28
2.3 Blowers	29
2.4 Traveling Bridge Crane.....	30
2.5 Electrical Improvements.....	30
2.6 Maintenance of Plant Operations	31
2.7 Recommendations	31
2.8 Estimation of Probable Cost	32
3. DAF Addition to Stage 3	33
3.1 Background	33
3.2 Stage 2 Reject Solids Characterization	34
3.3 Strainer Backwash Solids Projection	35
3.4 Proposed DAF System	37
3.5 Summary of Major Equipment.....	38
3.6 Coagulant Feed System and Storage.....	40
3.7 DAF Solids (Float) Management	40
3.8 Accommodations for Water Treatment Residuals System Expansion.....	41
3.9 Electrical and Instrumentation requirements.....	41

3.10 Hydraulic Requirements.....	41
3.11 Operational Considerations	41
3.12 Recommendations	42
3.13 Estimation of Probable Cost.....	43
4. Stage 4 Centrifuge Addition.....	45
4.1 Background.....	45
4.2 Water Quality Characteristics and Solids Generation Estimates.....	46
4.3 Existing Water Treatment Residuals System	48
4.4 Accommodations for Water Treatment Residuals System Expansion	49
4.5 Proposed Conceptual Water Treatment Residuals System Improvements	50
4.6 Electrical Considerations.....	52
4.7 Operational Considerations.....	52
4.8 Recommendations.....	53
4.9 Estimation of Probable Cost.....	54
Table 4-5 – Estimation of Probable Cost for Centrifuge Addition.....	54
5. Potential Alternatives for DBPs Reduction	55
5.1 Background.....	55
5.2 Water Quality and Disinfection Byproduct Characteristics	56
5.3 Existing Disinfection Practices at the WTP	66
5.4 Options for DBP Reduction.....	66
5.5 Screening-Level Evaluation	70
5.6 Potential Alternatives for DCMWTP.....	74
5.7 Recommendations.....	80
Appendix A – Vendor Submittals	82

List of Tables

Table ES - 1. Solids Removal Equipment Ranking.....	2
Table ES - 2. Summary of Proposed Modifications to Stage 2	3
Table ES - 3. Summary of the Proposed DAF System to Stage 3.....	5
Table ES - 4. Summary of Proposed Modifications to Stage 4	6
Table ES - 5. Prioritized Alternatives for DBPs Reduction.....	7
Table ES - 6. Summary of the Estimated Costs for Each Proposed Improvements.....	8
Table ES - 7. Project Prioritization for Different Phases of Improvements.....	9
Table 1-1. Design Conditions – Normal Mode	12
Table 1-2. Design Conditions – Impaired Mode.....	13
Table 1-3. Solids Removal Equipment Summary	14
Table 1-4. Solids Removal Equipment Ranking.....	15
Table 1-5. Strainer Backwash Recovery System Equipment Summary*	15
Table 1-6. Stage 1 Ultrafiltration Operating Parameters.....	17
Table 1-7. Stage 2 Ultrafiltration System Operating Parameters.....	18
Table 1-8. Scenario 1: Normal Strainer BW Mode, Three Stage 2 UF Trains, Plate Settlers.	19
Table 1-9. Scenario 2: Normal Strainer BW Mode, Three Stage 2 UF Trains, Plate Settlers & DAF	19
Table 1-10. Scenario 3, Impaired Strainer BW Mode, Three Stage 2 UF Trains, Plate Settlers & DAF.....	19
Table 1-11. Scenario 4, Impaired Strainer BW Mode, Four Stage 2 UF Trains, Plate Settlers & DAF	19
Table 1-12. Estimate of Probable Cost for Strainers Backwash Water Recovery.....	20
Table 2-1. Summary of Design and Operating Parameters for Stage 2 UF System	21
Table 2-2. Zenon UF Scope of Supply	22
Table 2-3. Stage 2 Header Conditions with Three Trains Operating.....	29
Table 2-4. Stage 2 Header Conditions with Four Trains Operating	29
Table 2-5. Velocity in Upsized Feed and Permeate Headers.....	29
Table 2-6. Stage Scour Air System Operating Summary	30
Table 2-7. Summary of Proposed Modifications.....	31
Table 2-8. Estimation of Probable Cost for UF Train Addition.....	32
Table 3-1. Design Conditions – DAF System.....	38
Table 3-2. Major Mechanical Equipment.....	38
Table 3-3 – Summary of Proposed Modifications	42
Table 3-4 Estimation of Probable Cost for DAF Addition.....	43
Table 4-1. Estimated raw water solids generation, MWD Lake Skinner (CDM, 20102).	46
Table 4-2. Centrifuge influent estimates for the DCMWTP from a "Solid-Liquid Mass Balance" model (CDM, 2010)	48
Table 4-3. Simple comparison of single to dual centrifuge operation at the DCMWTP assuming 73.5 hours equipment operation time required per week.....	52

Table 4-4 – Summary of Proposed Modifications	53
Table 4-5 – Estimation of Probable Cost for Centrifuge Addition.....	54
Table 5-1. DBP Reduction Alternatives	67
Table 5-2. Options for DBP Reduction at the DCMWTP.....	68
Table 5-3. Criterion Weighting	71
Table 5-4. Screening Level Decision Matrix.....	72
Table 5-5. Decision Matrix Results.....	74
Table 5-6. Level Two Evaluation of Potential Options	75
Table 5-7. Prioritized Alternatives.....	80

List of Figures

Figure ES - 1. Strainer Backwash Recovery System Schematic.....	2
Figure 1-1. Bollfilter type 6.18/500 DN 500 Automatic Backwash Strainer.....	10
Figure 1-2. Strainer Backwash Recovery System Schematic	12
Figure 1-3. Hydro International, Grit King.....	13
Figure 1-4. Smith-Loveless, PISTA V10	14
Figure 1-5. Ovivo, Jeta	14
Figure 1-6. Proposed Strainer Backwash Recovery System Location.....	16
Figure 2-1. Existing Stage 2 Trains, Upper Plan View.....	24
Figure 2-2. Existing Stage 2 Trains, Upper Plan View.....	25
Figure 2-3. Proposed Stage 2 Expansion (Fourth Train), Lower Plan View	26
Figure 2-4. Proposed Stage 2 Expansion (Fourth Train), Upper Plan View.....	27
Figure 2-5. Proposed Stage 2 Expansion (Fourth Train), Section View.....	28
Figure 2-6. Traveling Bridge Crane.....	30
Figure 3-1. Turbidity Data from Stage 2 Reject.....	35
Figure 3-2. Stage 3 Process Flow Diagram with Proposed Modifications	37
Figure 3-3. Component layout of proposed DAF System.....	39
Figure 3-4 – Proposed Strainer Backwash Recovery System Location	43
Figure 4-1. Process Flow Diagram with proposed modifications	46
Figure 4-2. Layout of the new centrifuge and centrifuge feed pump.....	50
Figure 4-3. Existing and new centrifuge feed pumps.....	51
Figure 4-4. Picture and general dimensions for Alfa Laval ALDEC 45	51
Figure 5-1. TOC Concentrations in Raw and Finished Water at the DCMWTP	59
Figure 5-2. TTHM Concentrations at Sampling Sites in the Distribution System	60
Figure 5-3. TTHM LRAA Trends in the Distribution System.....	61
Figure 5-4. TTHM OEL Trends in the Distribution System.....	62
Figure 5-5. HAA5 Concentrations at Sampling Sites in the Distribution System	63
Figure 5-6. TOC vs. TTHM Concentrations in Finished Water.....	64
Figure 5-7. Lack of Simple Correlation between FW TOC and FW TTHM	65
Figure 5-8. Option for GAC Siting.....	77
Figure 5-9. Alternative for GAC Siting.....	78
Figure 5-10. Option for UV Siting.....	79

Executive Summary

The David C. McCollom Water Treatment Plant (DCMWTP), owned and operated by the Olivenhain Municipal Water District (OMWD), is a 34 MGD ultrafiltration membrane treatment plant utilizing surface water from either the Colorado River or the State Water Project via the Metropolitan Water District of Southern California (MWD) and the San Diego County Water Authority (SDCWA). Hazen and Sawyer (Hazen) is assisting OMWD with the evaluation of potential improvements to various processes at the DCMWTP as part of a Capacity Reliability Study. A series of Technical Memoranda (TM) were prepared as part of this study, and each TM addressed a different process improvement being considered as part of this study. Sections 2 through 5 of this report correspond to TM 1 through 5, respectively. The processes evaluated included:

- Recovery of the Backwash Waste Water from the Strainers (TM 1)
- Addition of One UF Membrane Treatment Train to Stage 2 (TM 2)
- Addition of a Dissolved Air Flotation (DAF) System to Stage 3 (TM 3)
- Addition of a Centrifuge to Stage 4 (TM 4)
- Evaluation of Disinfection Alternatives and DBPs Control (TM 5)

Strainers Backwash Waste Water Recovery

The investigation of the proposed strainer backwash recovery (SBWR) system led to evaluation of two modes of operation: normal mode and impaired mode. The normal mode of operation would be carried out for approximately ten (10) months of the year, when the raw water quality is relatively good and the strainers backwash according to the scheduled timer. When the raw water quality is diminished, the elevated suspended solids concentration and presence of filamentous algae will cause the SBWR system to operate in impaired mode. The impaired raw water will require a greater degree of solids and algae removal.

The SBWR system will include solids removal, flow equalization, and a pump station to send the flow either to the existing BWWEQ tank (normal mode) or to the new DAF (impaired mode). This is shown in the schematic presented in **Figure ES - 1**. This system can be further optimized in the preliminary design to potentially eliminate the need for the transfer pumps from the Recovery EQ tank to the BWWEQ and the DAF system in Stage 3.

Three types of equipment that remove solids were investigated and ranked (**Table ES - 1**) based on cost, power consumption, and footprint. The systems from Hydro International and from Smith & Loveless Inc. were ranked similarly. However, for conservative reasons, Smith & Loveless was considered in the cost estimate for this study (the higher cost of the two).

The solids removal equipment is proposed to be located in the same building with the new DAF system for Stage 3, which is west of the existing Stage 3 building. Alternatively, the system can be placed outside under a canopy. The cost estimate considered the solids removal system in a building.




Figure ES - 1. Strainer Backwash Recovery System Schematic

Table ES - 1. Solids Removal Equipment Ranking

Manufacturer	Model	Cost	Power Consumption	Footprint	Overall Rank
Hydro International	Grit King	3	3	3	9
Smith & Loveless Inc.	PISTA V10	2	2	3	7
Ovivo	Jeta	1	1	1	3

The recovered water will impact other stages of the treatment, including Stages 2 and 3. Stage 2 feeds from the existing backwash waste EQ tank (BWWEQ), which has sufficient buffer capacity to hold the strainers backwash water in the normal operating mode. When the strainers would operate in impaired mode, which generates significantly more waste water volume, the BWWEQ tank will likely overflow. The overflow condition can be addressed by operating with all four UF trains in Stage 2, or by increasing the current capacity of Stage 2 from 850 gpm/train to 1,000 gpm/train (design capacity). Another option for preventing BWWEQ tank overflow is sending some of the strainers backwash waste water to the storm drain.

UF Train Addition to Stage 2

The DCMWTP utilizes two separate UF systems referred to as Stage 1 and Stage 2. The Stage 1 UF system is the primary water treatment for the plant. Stage 2 treats Stage 1 reject as well as supernatant from Stage 3 plate settlers that recover backwash from Stage 2. With the current configuration, the Stage 2 UF system is a choke point in the overall plant production. Stage 2 is comprised of three UF trains. When one train is taken offline for cleaning or service, the overall plant capacity is reduced by approximately 33%. This study evaluated the feasibility of expanding the Stage 2 UF system by 33% with the addition of one more train.

The proposed location for the new UF train is directly adjacent to the existing train, where the CIP pumps are currently located, at the western end of the membrane trains. The addition of a new train next to train 13 will require relocation of the CIP pumps, CIP piping, chemical feed piping, and the elevated walkway. The compressed air equipment, currently located in the area north of the Stage 2 membrane trains, would require relocation outside the membrane building (north side). The CIP pumps would be relocated to the area previously occupied by the compressed air system.

The addition of the fourth train will require saw-cutting, demolition, forming a new foundation, doweling into the existing floor slab, and providing watertight joints all around. Based on review of the record drawings and photos of the interior of the water treatment building, it appears feasible to add a new fourth basin of similar dimensions adjacent to the existing Stage 2 basins without compromising the building foundation or outer metal building structure.

The elevated walkway that currently surrounds train 13 will need to be reconfigured. If the existing walkway structure is reused, the spacing between the support columns and the basin wall will likely encroach on much of the available space that traverses between the north and south roll-up doors. If a new walkway is installed, it can be designed such that the support columns and the stairs are positioned to maximize the clearance to move equipment through this area. The cost estimate presented in this document considers that a new walkway would be required.

The chemical feed lines that are routed from the chemical rooms along the south wall and underneath the elevated walkway will need to be moved underneath the relocated elevated walkway, similar to the existing chemical piping arrangement. Final location of the stairs will be determined during preliminary design. **Table ES - 2** summarizes the proposed modifications.

Table ES - 2. Summary of Proposed Modifications to Stage 2

Item	Comment
Add Concrete Basin	Will require significant modifications to the existing plant infrastructure, including concrete work inside the membrane building.
Add Membrane System	Will require SCADA integration, additional piping, valves, and associated hardware.
Modify and Relocate the Walkway	Will encroach into the remaining space between Stage 2 and the west masonry wall.
CIP System Relocation	Potential challenges locating the pumps and associated piping in the area north of the Stage 2 membranes.
Air System Relocation	Relocate the existing equipment outside to the north side of the membrane treatment building, or to another location to be more optimal.
CIP Drain	Relocate the drain north of Stage 2, closer to the relocated CIP pumps.
Electrical and I/O Upgrades	Upgrade the feeder circuit and the upstream breaker for MCC-2. Evaluate Panel CC-3 for capacity to handle additional I/O.
Relocated Elevated Walkway	Reuse the existing structure or redesign with new material.

Dissolved Air Flotation (DAF) Addition to Stage 3

The plant currently utilizes three (3) lamella plate settlers for solids removal and thickening of water treatment residuals. During peak flows, all three lamella plate settlers are required to operate in duty mode to meet the treatment capacity, with no redundancy. Additionally, the DCMWTP must reduce treatment capacity by 33% when any one settler unit is taken down for maintenance. A DAF system is proposed to provide enhanced capacity and redundancy for the existing plate settlers. The DAF system is proposed to also treat strainer backwash water during periods when raw water quality diminishes due to the presence of filamentous algae.

Based on the 600 gpm (0.86 mgd) flowrate of strainer backwash water to the DAF system, it is anticipated that a packaged DAF system would be a more cost-effective option than a component engineered system. A packaged DAF system would also allow for a faster design and construction schedule compared to a traditional DAF design for this size.

The strainer backwash water solids characteristics are not known at this time; it is recommended that bench-scale and/or pilot testing be performed to determine the required dose for treating strainer backwash water. The anticipated coagulant to be used for the DAF system would be Nalco 4954, which was tested during DAF pilot testing and is currently utilized for the Stage 3 plate settlers. For a dedicated coagulant system, a bulk storage tank, day tank, transfer pumps, and metering pumps would be provided. For preliminary sizing purposes, it was assumed that the DAF coagulant dose would be similar to the doses tested during pilot testing (60 mg/L). At this dose, a 3,000-gal bulk storage tank would be provided for 30 days of storage.

The possibility of pumping the DAF float directly to the exiting sludge tanks should be explored in the preliminary design phase, after an analysis of the characterization of suspended solid in the strainer backwash water and hydraulic analysis have been completed. For the purposes of this preliminary sizing, it was assumed that the float will be collected in a holding tank, and two solids transfer pumps (one duty, one standby) will convey solids to the Stage 4 solids holding tanks, prior to being dewatered using the centrifuge(s). For preliminary sizing purposes, it was assumed that the solids content would be similar to Stage 2 reject (76 NTU avg.) and the DAF coagulant dose would be similar to the doses tested during pilot testing (60 mg/L). Based on these assumptions, a floated solids holding tank was sized to be 10,000 gal to provide between 1-2 days of storage.

It may be possible for the DAF clarified water to flow by gravity to the BWWEQ tank; however, this must be confirmed during preliminary design. For the purposes of this planning level study, it is conservatively assumed that the DAF clarifiers water will require pumping. A hydraulic analysis is recommended during preliminary design to adequately size these pumps. For preliminary sizing purposes, it is assumed that two (1 duty, 1 standby) 600 gpm pumps will be provided; however, a larger number of smaller pumps may be preferable for operational flexibility.

The DAF system is proposed to be located west of the residuals treatment building. The new building will be sized to also allow placement of the grit removal from the strainer backwash water. For preliminary sizing purposes, it is assumed that a 155 ft x 55 ft building will be provided for the DAF system and SBWR system.

Table ES - 3. Summary of the Proposed DAF System to Stage 3

Item	Comment
New DAF Building	Building to include new DAF system and the grit removal for the strainer backwash recovery system.
Packaged DAF System (600 gpm)	New DAF system to be provided with recycle pumps, air compressors, saturators, etc. Ladders, stairs and platforms not included in DAF package and provided separately.
Floated Solids Holding Tank and Pumps	Tank sizes to be confirmed during preliminary design based on verified solids loading. Pumps to be sized appropriately to pump back to existing solids holding tanks.
Clarified Water pumps	Pumps to be sized based on system hydraulic analysis to pump to the backwash water equalization tank.
Coagulant System	Tank and pump sizes to be confirmed during preliminary design based on verified coagulant doses.
Piping	Modifications to allow Stage 2 reject and/or centrate to be directed to the DAF system. New piping to allow recovered strainer backwash water to be directed to the DAF system.
Electrical	The DAF system can be supplied from MCC-5. The existing circuits, main circuit breaker, and upstream breaker supplying MCC-5 would have to be upgraded to 600A to support the new load.

Centrifuge Addition to Stage 4

The reject from Stage 2 is currently treated by the three Stage 3 lamella plate settlers, which serve as thickeners upstream of the Stage 4 dewatering centrifuge. While the existing centrifuge can adequately handle the range of water treatment residuals historically generated at the DCMWTP, a second unit is proposed to enhance reliability and redundancy of Stage 4.

The existing centrifuge (Centrifuge 1) was upgraded by the manufacturer in 2010. While the model of Centrifuge 1 (Aldec 406) is no longer manufactured, Alfa Laval currently manufactures a version (Aldec 45) with many of the same features and would provide the same capacity as the existing unit. The variable frequency drives that were provided in the 2010 upgrade are no longer available from Alfa Laval, but similar drives can be used that essentially provide the same or greater functionality. The controls systems for the new centrifuge can be integrated into the existing control panel.

The new centrifuge is proposed to be located in the area on the elevated platform as planned in the LT2 Improvements project. The new Centrifuge Feed Pump 3 and Centrifuge Feed Line 2 are recommended to match the existing assets. A new electrical circuit breaker and variable frequency drive will be necessary for the proposed new progressive cavity pump. The proposed pump has an updated design which allows for fully servicing the pump in-place. The proposed piping configuration will allow any of the three pumps to convey flow to either centrifuge if only one centrifuge is in operation. This configuration will also allow flow to be conveyed to both centrifuges simultaneously with Centrifuge Feed Pump 2 serving as a swing spare.

It may also be necessary to install a dedicated polymer feed pump for Centrifuge 2. While polymer could be fed to Centrifuge 2 through the same system that feeds Centrifuge 1, a second pump would provide redundancy, simplify the operation of the centrifuge polymer feed system, and would allow simultaneous operation of both centrifuges. Adding a second polymer feed pump and new lines is recommended.

Depending on the operation, the DAF unit considered to be added to Stage 3 could be expected to routinely produce a higher concentration of solids in the thickened sludge when compared to the lamella plate settlers. However, since the thickened sludge from both types of thickening processes will be collected and stored in the thickened sludge storage tanks, the thickened sludge will be blended and equalized, and a relatively uniform stream can be expected to be conveyed to the centrifuges. In discussing the potential for variability in thickened sludge characteristics, Alfa Laval indicated little concern for the operation of the centrifuges, except a potential reduction in hydraulic capacity due to a slight reduction in the efficiency of the centrifuge due to the thicker solids concentration.

An additional improvement to be considered is related to the capture of the strainer backwash waste stream. One component of the solids in this stream is likely grit, including Asiatic clam shells. This material can be expected to have a detrimental impact on the lifetime of certain wear items in the centrifuges. The service or replacement of some of these wear items can be significant as it involves servicing the centrifuge at the manufacturer's facilities. Alfa Laval indicated that it is possible to provide a tungsten-carbide material upgrade for the feed zone of the centrifuge that would mitigate some of the wear caused by abrasive solids. However, it is recommended to capture the abrasive solids ahead of the treatment system to avoid introduction to the centrifuges.

Table ES - 4. Summary of Proposed Modifications to Stage 4

Item	Comment
Centrifuge 2	Proposed model will operate similarly to the existing centrifuge, and can be fully integrated with the existing control system.
Centrifuge Feed Pump 3	Addition of the third centrifuge feed pump, with associated mechanical and piping improvements, will accommodate simultaneous operation of both centrifuges with redundancy.
Dewatering Polymer Feed Pump 2	The second polymer feed pump, feed line and associated mechanical improvements will be dedicated to Centrifuge 2.

Evaluation of Disinfection Alternatives and DBPs control

The water quality of the two water sources (Colorado River and State Water Project) feeding DCMWTP can differ considerably. The State Water Project (SWP) water typically contains more DBPs precursors relative to the Colorado River water (CRW). As such, when MWD increases the ratio of SWP water in the blend, OMWD experiences higher formation of DBPs at the treatment plant and in the distribution system. OMWD has little control over the blend ratios and must be prepared to treat a source water with higher percentages of SWP water while maintaining plant capacity and regulatory compliance.

Utilizing a stepwise process, a total of 24 alternatives for DBPs reduction were screened. The top alternatives were prioritized based on a cost-benefit analysis in terms of expected DBP reduction and estimated capital costs. The recommended alternatives and are presented in **Table ES - 5**.

Table ES - 5. Prioritized Alternatives for DBPs Reduction

Alternative	Overall Expected Impact on DBP Reduction	Taste &Odor Reduction	Planning-level Capital Cost Estimates
Install UV Disinfection for Giardia Credit	High	No	\$2M-\$3M
Install UV Disinfection for Giardia and Virus Credit	High	No	\$5M-\$7M (est.)
Install GAC Contactors	High	Yes	\$13M-\$15M
Install GAC Contactors and Pre-Ozone	High	Yes	\$22M-\$25M (est.)
Add Aeration/Mixing to One or More Storage Reservoirs in Distribution System	Medium	No	\$400k-\$700k per Reservoir (Assume 7 Reservoirs, or Approx. \$5M)
Add/change Pre-oxidant to Ozone or Chlorine Dioxide	Low	Yes	\$8M-10M

Most of these DBP reduction processes require some form of bench or pilot scale testing to confirm expected reduction in the DBP formation potential and the capital and operating costs. GAC should be piloted to determine overall effectiveness, which can be measured by break-through curves generated for TOC and pre-formed DBPs. The breakthrough curves help establish design conditions (e.g., required empty bed contact time) and operating costs (i.e., GAC replacement frequency). Pilot testing can also evaluate different types of carbon to identify the most cost-effective option. The cost of piloting is a function of the number of carbons tested and the length of the tests. Previous pilots tests have been completed in the \$50,000 - \$100,000 range per season of testing. The blend of source water would need to be determined.

Ozone as a pre-oxidant to GAC can also be tested as part of the pilot experiments. Ozone fed water prior to GAC frequently changes the process into a biologically-active carbon (BAC). As this testing involves the development of a biomass within the column, it often requires a longer trial period, which will increase the piloting costs. Ozone alone (i.e., without GAC) can be evaluated on the bench-scale with jar testing. The costs are a function of the ozone doses and source water quality changes to be tested. Often these jar tests can be performed in as little time as one week and cost approximately \$20k-\$40k per season.

Aeration effectiveness on TTHM stripping can be modeled and/or tested. The vendors have desktop models that are used to predict TTHM removal. UV systems do not typically need piloting if designed for disinfection only. However, UV transmittance (UVT) measurements will be needed to establish design and operating doses. In addition, water quality characteristics need to be examined to determine the potential for fouling of the quartz sleeves. Fouling potential can be experimentally tested if water quality review identifies potentially problematic characteristics.

There are several general good practices that OMWD should continue that help with DBP reduction. With the free chlorine CT currently being achieved in the finished water piping, the downstream injection of ammonia should be evaluated for mixing and its effectiveness in maintaining a 5:1 chlorine to ammonia ratio. In addition, hydraulic modeling of the distribution system should be conducted and/or the SCADA-data reviewed to determine optimum operations to minimize water age in the system.

In summary, it is recommended that OMWD:

1. Begin collecting UV transmittance data (at 254 nm) of the source water, post Stage 1, and finished water. The data should be collected at various times for a period of at least six months.
2. Plan and budget for a UV disinfection basis of design report.
3. Plan and budget for pilot testing of GAC with or without ozone.
4. Collect data specific to each of the storage reservoirs within the distribution system and submit to aeration/mixer vendors to better refine costs and performance of TTHM reduction systems.

Estimate of Probable Cost

Table ES - 6 presents a summary of the engineer's estimate of the probable construction costs for each proposed implementation. With the exception of the DBPs alternative, the costs represent the total cost of the project, including engineering, contractor overhead and profit, contingency etc. Details of each assumptions are presented in the individual sections of this report. It should be noted that the contingency assumed is dependent on project definition at this level of the study. For example, a 25% contingency was assumed for the strainers backwash water recovery and DAF addition, whereas a 20% contingency was assumed for the UF train addition to Stage 2 and the centrifuge addition to Stage 4.

The cost estimate presented for the DBP's alternatives does not represent the total cost of the project. It reflects the range of costs for the installed equipment for an array of six options, and should be used for ranking the alternatives, as presented in Section 5.

Table ES - 6. Summary of the Estimated Costs for Each Proposed Improvements

Stage Number	Description	Estimated Cost
-	Strainers Backwash Waste Recovery	\$1,370,000
2	UF Train Addition	\$4,403,000
3	DAF Addition	\$5,005,000
4	Centrifuge Addition	\$844,000
-	DBPs Alternatives	\$2,000,000-\$25,000,000 ¹⁾

¹⁾ This represents an estimation of the installed equipment and shall be used only for alternatives ranking. It does not reflect the overall cost of implementing DBPs treatment.

Recommendations for Project Phasing

OMWD may decide not to install all the proposed improvements at once, but rather phase the improvements over a number of years. A summary of the recommended priorities for the improvements is presented in **Table ES-7** and discussed below.

- The recovery of the backwash water from the strainers would result in more water processed by the UF trains in Stage 2. This can lead to occasional overflow of the BWWEQ tank. The

overflow can be prevented by either operating the existing UF closer to the design flow (1,000 gpm permeate) or directing some of the backwash waste water to the storm drain, per current operation. There are some concerns with the filamentous algae resulting in the BWWEQ tanks and from there, into the Stage 2 UF membrane feed water, which will be detrimental to the membrane operation. The proposed DAF system in Stage 3 will remove most of the floating solids from the strainers BWW water. The removed solids from the DAF system will require processing by the centrifuge, and as such, it is recommended that this phase is implemented after the DAF is added to Stage 3 and a second centrifuge is added to Stage 4.

- The addition of a fourth train to Stage 2 is an important element of the reliability improvements, as the plant production capacity is reduced by 33% when one train is in CIP or down for maintenance. This phase should be prioritized and implemented early.
- The DAF system will provide redundancy to Stage 3. Similar to Stage 2, Stage 3 capacity is reduced by 33% when one of the plate settlers is down for maintenance. The addition of the DAF system is recommended to follow the addition of the fourth UF train to Stage 2.
- The centrifuge in Stage 4 has no redundancy. The addition of the second centrifuge will provide 100% redundancy and will allow for both the DAF system and plate settlers to operate at the same time. Based on the criticality of this stage, this phase of the project is recommended to be implemented after or simultaneous to the DAF addition.
- DBPs treatment should be considered high priority. The variability in the source water quality poses a risk to exceed the DBPs MCL. The capability to reduce or to prevent formation of the DBPs at the treatment plant or in the distribution system will result in flexibility in operation while maintaining the plant capacity and meeting all drinking water quality standards.

Table ES - 7. Project Prioritization for Different Phases of Improvements

Proposed Improvement Phase	Recommended Priority	Recommended Order of Implementation
Strainers BWW Recovery	Low	5
UF 4 th train to Stage 2	High	2
DAF System to Stage 3	Average	3
Centrifuge to Stage 4	Average	4
DBPs Reduction/Treatment	High	1

1. Recovery of Strainers Backwash Water

1.1 Background

The David C. McCollum Water Treatment Plant (DCMWTP) is a direct filtration facility that utilizes three 500-micron Bollfilter Type 6.18/500 DN 24" automatic backwashing strainers (**Figure 1-1**) to pretreat the flow into the facility and reduce the solids loading onto the Stage 1 membranes. A blend of Colorado River Water (CRW) and State Project Water (SPW) enters the DCMWTP via the San Diego County Water Authority (SDCWA) pipeline. Under normal operating conditions, each strainer backwashes primarily on a timer set point (every 3 hours, but can vary based on operator input) and secondarily on a differential pressure (4 psi). Regardless of the trigger, the strainers backwash sequentially, with only one strainer backwashing at a time. The backwash duration is 1 to 2 minutes per strainer, at an average flow rate of 600 gpm. This results in approximately 14,400 to 28,800 gallons per day (5 to 10 million gallons per year) of backwash water that is currently directed to the storm drain.

Historically, during April and July, the raw water quality diminishes significantly, most notably due to the presence of filamentous algae. Filamentous algae is also associated with the transition between the San Diego canal and Lake Skinner sources. The algae have an adverse impact on the strainers, forcing the strainers to operate in a constant backwashing mode until the strainers are cleared of debris, or they are taken out of service and cleaned manually. During this period of diminished raw water quality, backwash waste water generated per day increases significantly. The following evaluation analyzes the feasibility of recovering the strainer backwash waste water.



Figure 1-1. Bollfilter type 6.18/500 DN 500 Automatic Backwash Strainer

1.2 Proposed Improvements

The preliminary investigation of the proposed strainer backwash recovery (SBWR) system led to evaluation of two modes of operation: normal mode and impaired mode. The normal mode of operation would be carried out for approximately ten (10) months of the year, when the raw water quality is relatively good and the strainers backwash according to the scheduled timer. When the raw water quality is diminished, the suspended solids concentration is elevated and filamentous algae will cause the SBWR system to operate in impaired mode. The impaired raw water will require a greater degree of solids removal, including algae removal.

Mechanical separators typically used for grit and suspended solids removal are not very effective for removing algae. If algae are not removed before entering the backwash waste equalization (BWWEQ) tank, they will be sent to the Stage 2 membranes. Algae are a concern with respect to hollow fiber membrane systems and should be prevented from entering the Stage 2 membrane basins. Experience has shown that fibrous material such as algae can be difficult to backwash off membranes. Polysaccharides from the algae can coat the membrane surface with a hard thin film restricting flow across the membrane surface. Once this occurs, the removal of the film is difficult. For this reason, it is proposed that when operating in impaired mode, the strainer backwash waste water would be sent to the new DAF system that will be added to Stage 3. A DAF system can remove algae and also the carried-over solids that are not removed by the proposed grit removal system. When operating in impaired mode, the SBWR flow will utilize 100% of the DAF treatment capacity. It is assumed that in the impaired mode, the existing Stage 3 clarifiers will treat Stages 2 and 4 as they currently do through the existing plate settlers. Once the analysis of the solids constituents is performed for the BW waste water, an investigation should be carried out whether the BWW can be sent to the existing plate settlers. It is possible that the broken shells and snails, as well as other abrasive solids could impact negatively the performance of the settlers, as well as potentially damage the equipment.

The SBWR system will include solids removal, flow equalization, and a pump station to send the flow either to the existing BWWEQ tank (normal mode) or to the new DAF (impaired mode). This is shown in the flow schematic presented in **Figure 1-2**.




Figure 1-2. Strainer Backwash Recovery System Schematic

1.3 Solids Removal

Regardless of the mode of operation, the solids will need to be removed before the strainer backwash water can be recovered. Several technologies were evaluated for this study. The proposed equipment will require that the dewatered solids are trucked to a landfill. Because the strainers backwash periodically, the solids removal equipment will be required to treat intermittent flow. The normal mode operating conditions are presented in **Table 1-1** and the impaired mode operating conditions are presented in **Table 2**. The strainer backwash water solid concentrations and particle distribution are unknown. However, the equipment vendors indicated that the capacity for solids removal is independent of the amount of solids and it is controlled by the flow rate to the unit. Nevertheless, it is recommended that a full characterization of the backwash water quality be performed during preliminary design, in order to refine the solids load rates.

Table 1-1. Design Conditions – Normal Mode

Parameter	Unit	Value
Strainer Backwash Flow	gpm	600
Strainer Backwash Frequency	hour	3
Strainer Backwash Duration / Strainer	min	2
Solids Makeup	-	Sand, Grit, Asiatic Clam & Snail Remnants (Larger than 500 μ m) Filamentous Algae

The impaired mode design conditions are presented in **Table 1-2** below.

Table 1-2. Design Conditions – Impaired Mode

Parameter	Unit	Value
Strainer Backwash Flow	gpm	600
Strainer Backwash Frequency	-	Continuous
Strainer Backwash Duration	min	Continuous
Solids Makeup	-	Sand, Grit, Asiatic Clam & Snail Remnants, (Larger than 500 µm) Filamentous Algae

Solids removal equipment from three vendors was investigated: Grit King by Hydro International, PISTA V10 by Smith-Loveless, and Jeta by Ovivo (**Figure 1-3**, **Figure 1-4**, and **Figure 1-5**). Industry experience has shown these to be proven technologies for solids and grit removal.



Figure 1-3. Hydro International, Grit King




Figure 1-4. Smith-Loveless, PISTA V10



Figure 1-5. Ovivo, Jeta

The solids removal equipment is summarized in **Table 1-3** below.

Table 1-3. Solids Removal Equipment Summary

Manufacturer	Model	Flow Capacity (gpm)	Power Consumption (HP)	Footprint (ft x ft)	Equipment Cost
Hydro International	Grit King	650	2	20 x 9	\$153,000
Smith & Loveless Inc.	PISTA V10	650	6	22 x 8	\$246,905
Ovivo	Jeta	694	18	30 x 30	\$325,210

The solids removal equipment systems are ranked in **Table 1-4** based on cost, power consumption, and footprint. For each criterion, the systems are ranked from one to three, with three being the most advantageous and one being least advantageous. The overall ranking is the sum of the ranking for each criterion. The systems from Hydro International and from Smith & Loveless Inc. are ranked similarly, however, Smith & Loveless was considered in the cost estimate for this study (the higher cost of the two).

Table 1-4. Solids Removal Equipment Ranking

Manufacturer	Model	Cost	Power Consumption	Size	Overall Rank
Hydro International	Grit King	3	3	3	9
Smith & Loveless Inc.	PISTA V10	2	2	3	7
Ovivo	Jeta	1	1	1	3

1.4 Strainer Backwash Recovery Equalization

An equalization (EQ) tank and a pump station will be required downstream of the solids removal system since it operates at atmospheric pressure. The SBWR EQ tank will serve two purposes. When operating in normal mode, the periodic flow from the strainers can be equalized prior to discharge into the existing BWWEQ tank which helps maintain a constant flow to the Stage 2 membranes. When operating in impaired mode, the strainer backwash flow can be equalized prior to entering the stage 3 DAF.

Preliminary tank sizing is constrained by the two operating modes. When operating in normal mode, the periodic backwash volumes will be between 2,000 to 4,000 gallons delivered at about 600 gpm over approximately 6 minutes, every 3 to 4 hours. When operating in impaired mode, the assumption is a continuous 600 gpm flow through the solids removal equipment into the EQ tank.

Based on the anticipated flows for both modes of operation, the upper volumetric boundary is 4,000 gallons. Therefore, allowing for 2 complete strainer backwash cycles, the proposed conceptual equalization volume is 10,000 gallons. The proposed transfer pump station will consist of two 600 gpm, 10 HP pumps, 1 duty and 1 standby.

Strainer Backwash Recovery System Equipment Summary

Table 1-5 below summarizes the major equipment required for the proposed strainer backwash recovery system.

Table 1-5. Strainer Backwash Recovery System Equipment Summary*

Description	Quantity	Size
Solids Removal System	1	650 gpm
SBWR EQ Tank	1	10,000 gal
SBWR Transfer Pumps	2 (1 duty, 1 standby)	650 gpm, 10HP

* plus the necessary piping, appurtenances, instrumentation, etc.

1.5 Proposed Location

The proposed location for the strainer backwash recovery system is inside the new DAF building. The new building is proposed to be located on the western part of the site, between the existing Backwash Waste EQ tank and the existing residuals handling building (**Figure 1-6**). If desired, the SBWR system could be located outside to the west of the proposed DAF building, underneath a canopy structure. The cost estimate for this system assumes that the SBWR system is located inside the DAF building.




Figure 1-6. Proposed Strainer Backwash Recovery System Location

1.6 Electrical Considerations

The SBWR system can be connected to the MCC-5, along with the DAF system (Section 3) and the centrifuge (Section 4). MCC-5 was one of three MCCs included in the LT2 Improvements project conducted in 2011. This motor control center currently has a connected load of approximately 180 A. The three new systems (SBWR, DAF, and centrifuge) proposed to be connected to this MCC will have a new load of 194 A, bringing the total connected load to 374 A on a bus rated for 600A. The existing circuits, main circuit breaker, and upstream breaker supplying MCC-5 would have to be upgraded to 600A to

support the new load. The cost estimate associated with the upgrades to MCC-5 is included in the DAF system presented in Section 3.

1.7 Impacts to the Existing Backwash Waste Storage Tank and Existing Stage 2 Ultrafiltration

The proposed SBWR system will need to be integrated into the existing Stage 2 ultrafiltration system through the existing 260,000-gallon BWWEQ tank. The following summarizes the evaluation of impacts of the proposed changes.

Currently, Stage 2 is supplied from the Stage 1 backwash and the recovered Stage 3 water. Flow through the plant can vary based on factors such as demand, time of year, and equipment / resource availability. This evaluation is a high-level analysis that assumes the plant is operating near full capacity and simplifies operations into basic conditions to establish the average flows. It should be noted the intent of this analysis is to examine the feasibility of integrating the proposed SBWR system into the existing facility and identify any major flaws. The DCMWTP is a very complex facility and a more extensive analysis would be required in the detail design.

Factors examined for this analysis were the maximum daily Stage 1 backwash volume, the maximum Stage 3 return flow, the maximum Stage 2 capacity, and the expected strainer backwash flows.

Stage 1 Backwash

Stage 1 is comprised of 10 Zenon UF trains; however, not all of the trains are outfitted the same, and consequently do not operate under the same parameters. Trains 1 through 8 have the same membrane surface area, while Trains 9 and 10 are configured differently and include a larger membrane surface area. Trains 1-8 and Trains 9-10 backwash at different time intervals and discharge different volumes. The differences are summarized in **Table 1-6** and are based on plant operating data from August 2017 when the plant operated at about 95% capacity. For this analysis, a conservative assumption was used and only the standard backwash waste was considered. Periodic maintenance cleans are also discharged into the BWWEQ tank, however they do not occur every day and result in an overall reduced volume. Therefore, the total Stage 1 UF daily standard backwash volume from all trains is approximately 2,220,036 gallons per day (2.22 MGD). This volume is sent to the Stage 2 membrane system.

Table 1-6. Stage 1 Ultrafiltration Operating Parameters

Parameter	Unit	Trains 1 -8	Trains 9 & 10
Backwash Volume / Train	gal	30,135	29,582
Number of Trains Operating	-	7 (N-1)	2
Backwash / Train / Day	-	8	9
Backwash Volume	Gal/day	1,687,560	532,476

Stage 3 Clarified Water

In addition to the Stage 1 UF backwash, the Stage 3 clarified water is also sent to the Stage 2 membrane system via the BWWEQ tank. This flow ranges from 350 to 520 gpm (0.65 – 0.75 MGD). A conservative

estimate of 0.75 MGD was assumed. Combined with the Stage 1 backwash, the assumed existing maximum flow to the Stage 2 membrane system is 3.21 MGD.

Stage 2 Ultrafiltration System

The existing Stage 2 system consists of 3 trains, each configured identically with 7 cassettes housing 20 membrane modules and 1 cassette containing 64 membrane modules. The Stage 2 UF system operates in a “Feed and Bleed” arrangement at 85% recovery. The maximum net permeate flow is 1000 gpm and the system is offline 6.25% of the time for periodic backwashes. This translates to a 93.75% online time, or 1,350 minutes per day. Under these conditions, Stage 2 is assumed to have a maximum production capacity of 4.32 MGD. At 85% recovery, this equates to 5.08 MGD feed flow. The Stage 2 operating parameters are summarized in **Table 1-7**.

Table 1-7. Stage 2 Ultrafiltration System Operating Parameters

Parameter	Unit	Value
Number of Stage 2 UF Trains	#	3
Stage 2 UF Max Net Permeate/Train	gpm (MGD)	1000*(1.44)
Stage 2 Recovery	%	85
Online Time	min/day	1350
Max Stage 2 Permeate Capacity	MGD	4.32
Max Stage 2 Feed	MGD	5.08

*Current Stage 2 production is limited to a max instantaneous flow of 850 gpm due to limitations of the Stage 2 reject pumps.

Based on the operating assumptions stated for Stages 1, 2, and 3, Stage 2 has an approximate maximum of 2.11 MGD (1,470 gpm) extra capacity to treat the proposed SBWR flow.

When the SBWR system is operating in normal mode, the Stage 2 UF system should have extra capacity to process the additional flow. However, when the SBWR system is operating in impaired mode, the Stage 2 UF system will likely be at or near its theoretical capacity. This evaluation has assumed that during the SBWR system impaired mode of operation, the strainers will be in continuous or near continuous backwash. This is a very conservative assumption and it is likely that the strainers will not be backwashed continuously. If the strainers backwash continually, the existing BWWEQ and Stage 2 UF systems could be overwhelmed. It is recommended that the existing strainer backwash connection to the storm drain is kept in place as a contingency should the strainer backwash begins to outpace Stage 2.

1.8 Existing Backwash Waste Equalization Tank

The usable capacity for the BWWEQ tank is 140,400 gallons. Evaluation of the impacts of the proposed SBWR system on the existing BWWEQ tank will be difficult as there are many dynamic factors that affect the BWWEQ tank such as the Stage 2 UF membrane condition. Most flow feeding the BWWEQ tank is from the Stage 1 backwash waste water. Based on the operating conditions stated above, the maximum hourly volume into the tank from Stage 1 is 92,500 gallons. Four operating scenarios are presented in **Table 1-8** through **Table 1-11**. Each scenario assumes a maximum hourly flow into the BWWEQ tank from the Strainers, Stage 1, and Stage 3. Each scenario also assumes two cases for Stage 2: the maximum design flow and the current maximum operating flow. A positive flow balance

represents extra capacity in the BWWEQ tank while a negative balance represents a tank overflow condition.

As presented in **Tables 9 and 10**, when the DAF system would operate in parallel with the plate settlers, the buffer capacity in the BWWEQ tank becomes very limited during normal operation mode (5,450 gal excess capacity) or is exceed in the impaired operation mode (27,550 overflow). Increasing the current operating feed water flow to the Stage 2 to the design flow would result in increased capacity in the tank and would avoid water overflow. Alternatively, the BWWEQ tanks overflow can be prevented by running the Stage 2 with all four trains at the same time (**Table 11**).

The flow assumptions made for normal mode operation coincide with approximately 80% of operating data from 2016 and 2017 showing normal months. To verify this conclusion, a detailed flow analysis is recommended as part of design.

Table 1-8. Scenario 1: Normal Strainer BW Mode, Three Stage 2 UF Trains, Plate Settlers

Source	Flow IN (gal/h)	Total Flow IN (gal/h)	Total Flow OUT (gal/h)		Flow Balance (gal/h)
From Strainers	3,600	127,300	Max Design	211,765	84,465
From Stage 1	92,500				
From Stage 3	31,200		Max Current	168,750	41,450

Table 1-9. Scenario 2: Normal Strainer BW Mode, Three Stage 2 UF Trains, Plate Settlers & DAF

Source	Flow IN (gal/h)	Total Flow IN (gal/h)	Total Flow OUT (gal/h)		Flow Balance (gal/h)
From Strainers	3,600	163,300	Max Design	211,765	48,465
From Stage 1	92,500				
From Stage 3	67,200		Max Current	168,750	5,450

Table 1-10. Scenario 3, Impaired Strainer BW Mode, Three Stage 2 UF Trains, Plate Settlers & DAF

Source	Flow IN (gal/h)	Total Flow IN (gal/h)	Total Flow OUT (gal/h)		Flow Balance (gal/h)
From Strainers	36,600	196,300	Max Design	211,765	15,465
From Stage 1	92,500				
From Stage 3	67,200		Max Current	168,750	(-27,550)

Table 1-11. Scenario 4, Impaired Strainer BW Mode, Four Stage 2 UF Trains, Plate Settlers & DAF

Source	Flow IN (gal/h)	Total Flow IN (gal/h)	Total Flow OUT (gal/h)		Flow Balance (gal/h)
From Strainers	36,600	196,300	Max Design	211,765	86,050
From Stage 1	92,500				
From Stage 3	67,200		Max Current	225,000	28,700

1.9 Estimation of Probable Cost

Table 1-12. Estimate of Probable Cost for Strainers Backwash Water Recovery

Item Description	Total Costs
Sitework	\$96,000
Concrete	\$19,700
Equipment	\$344,200
Mechanical	\$23,100
Electrical	\$72,500
Instrumentation and Control	\$38,900
Total Installed Equipment	\$594,400

Item	Description		Total Cost
1	Total Installed Equipment		\$594,400
2	General Conditions (allowed factor at this time)	10.0%	\$59,440
		Subtotal:	\$ 653,840
3	Contractor Overhead	10.0%	\$65,384
		Subtotal:	\$719,224
4	Contractor Profit	10.0%	\$71,922
		Subtotal:	\$791,146
5	Sales Tax (on materials only)	8.5%	\$31,165
		Subtotal:	\$822,311
6	Escalation at 3% annually*	6.9%	\$56,549
		Subtotal:	\$878,860
7	Bond and Insurance	3.0%	\$26,366
		Subtotal:	\$905,226
8	Contingency	25.0%	\$226,307
	Probable Bid Cost		\$1,132,000
9	Engineering	8.0%	\$90,560
10	CM	10.0%	\$113,200
11	Legal/Admin/Permitting	3.0%	\$33,960
	Probable Project Cost		\$1,369,720
12	Additional Cost for Canopy		\$223,669
	Probable Project Cost (with Canopy)		\$1,593,000

*Assumes construction starts in January 2020.

2. Stage 2 UF Membranes Expansion

The David C. McCollum Water Treatment Plant (DCMWTP) utilizes two separate Ultrafiltration (UF) systems referred to as Stage 1 and Stage 2. The Stage 1 UF system is the primary water treatment for the plant. Stage 2 treats Stage 1 reject as well as supernatant from the third stage (Stage 3) (plate settlers) that recover backwash from Stage 2. With the current configuration, the Stage 2 UF system is a choke point in the overall plant production. Stage 2 is comprised of three UF trains. When one train is taken offline for cleaning or service, the overall plant capacity is reduced by approximately 33%. This technical memorandum evaluates the feasibility of expanding the Stage 2 UF system by 33% with the addition of one more train. The expansion will increase capacity reliability by providing operational redundancy, allowing Stage 2 to operate in an N+1 configuration and the plant production to not be affected by one offline train.

2.1 Proposed Expansion

Stage 2 currently consists of three trains outfitted with Zenon ZeeWeed 500D UF cassettes and modules. Each basin is configured identically, with 7 cassettes housing 20 membrane modules and 1 cassette containing 64 membrane modules. Each UF train is housed in an open concrete basin. The Stage 2 UF system operates in “Feed and Bleed” mode at 85% recovery. The Stage 2 UF system has a net design permeate flow of 1000 gpm. However due to hydraulic limitations with the Stage 2 reject pumps, Stage 2 currently has a maximum net production of 850 gpm. Adjusting for production time lost to periodic backwashing this equates to 4.32 MGD, assuming all three trains are operating at maximum flow. The Stage 2 UF configuration is summarized in **Table 2-1**.

Table 2-1. Summary of Design and Operating Parameters for Stage 2 UF System

Parameter	Unit	Value
Number of Stage 2 UF Trains	#	3
Membrane Make and Model	-	Zenon ZeeWeed 500D
20 Module Cassettes	#	7
64 Module Cassettes	#	1
Total modules per Train	#	204
Online Factor	min/day	1,350 (93.8%)
Net Permeate Flow /Train (Design)	gpm	1000*
Design Capacity (all trains)	MGD	4.32
Stage 2 Recovery	%	85

*Current Stage 2 production is limited to a max instantaneous flow of 850 gpm due to limitations of the Stage 2 reject pumps.

The proposed expansion will add 33% to the existing Stage 2 capacity by adding one UF train identical to the existing trains. The additional Stage 2 capacity provided by a new train will provide sufficient redundancy to allow for one Stage 2 train to be offline for cleaning or service without the need to reduce Stage 1 production capacity.

The proposed location for the new UF train is directly adjacent to the existing train 13 (or adjacent to train 3 of the Stage 2) where the CIP pumps are currently located, at the western end of the membrane trains. A careful review of the as-built drawings in conjunction with the field investigation concluded this will be the ideal location for a new train with respect to constructability and integration into the existing facility.

Table 2-2 summarizes the equipment to be supplied by Zenon for the proposed new Stage 2 train. **Figure 2-1** and **Figure 2-2** show the existing conditions in and around the proposed area and **Figure 2-3**, **Figure 2-4**, and **Figure 2-5** show the proposed changes.

Table 2-2. Zenon UF Scope of Supply

Item	Quantity	Description
Membrane Modules	204	ZeeWeed 500D, 340 ft ²
20 Module Membrane Cassettes	7	ZW500D 20M
64 Module Membrane Cassettes	1	ZW500D 64M
Permeate Pump	1	To match existing
Reject Pump	1	To match existing
Permeate & Reject Flow Meters	1 (each)	To match existing
Permeate & Reject Inlet and Discharge Valves	4	To match existing
In Basin Piping	-	1 x 10" Permeate 1 x 10" Basin Fill 1X 4" Aeration Header Permeate Spool Connection Air Spool Connection Cyclic Aeration Valves
Cassette Support System	-	Beams Brackets Hanger Arms Leveling Pins
Remote I/O Panel *	1	To match existing
Instruments (Turbidity Meter & Particle Counter)	1 (each)	To match existing

*Verification of spare capacity in CC-3 for new I/O to occur during preliminary design.

The existing Stage 2 reject pumps currently are not meeting their design flow requirements. Operations have reported occurrences when the reject pumps are called to produce 175 gpm at 100% speed with the actual flow being about 165 gpm. Other times the reject demand is only 100 gpm and the pumps cannot meet this flow consistently. Operating data from March and August 2017 indicates Stage 2 operates at an average 81% recovery. During preliminary design, an evaluation of the existing pumps along with detailed hydraulic analysis of the reject pipe network is recommended to identify the cause of the UF reject flow restrictions.

The addition of a new train next to train 13 will require relocation of the CIP pumps, CIP piping, chemical feed piping, and the elevated walkway. The compressed air equipment is currently located in the area north of the Stage 2 membrane trains. The proposed expansion would require the compressed air equipment be relocated outside the membrane building on the north side. The final location to be determined during preliminary design. The CIP pumps would be relocated to the area previously occupied by the compressed air system. This will require careful planning during design of the rerouted CIP piping to ensure adequate accesses to the existing Stage 2 reject pumps, piping, and instruments as well as the CIP pumps. This will likely require some of the CIP pipe run overhead. The existing CIP pumps are assumed to be reused, however modification of the CIP piping could have an adverse impact to the new pump hydraulics, i.e. insufficient NPSHA or increase discharge head resulting in a flow reduction. The operating point of the relocated pumps and revised piping will be required during the detailed design.

The CIP system drains into a buried pipe located just south of the current CIP pump location. This is highlighted in blue in **Figure 2-1**. This drain pipe will need to be relocated because the proposed new train will be situated directly over this location (**Figure 2-3**).

Figure 2-3 shows a proposal for relocation of the drain. The new buried drain pipe can be aligned on the west side of Stage 2 and the drain be located north of Stage 2, near the CIP pumps. Reuse of all existing equipment, instruments, and valves is assumed. All relocated CIP pipes are assumed new.

The 2010 LT2 plant upgrades changed the Stage 1 mode of operation from feed and bleed to deposition. Because of this change, flow from Stage 1 to Stage 2 is no longer by gravity. As part of a detailed design, the plant hydraulics could be analyzed to evaluate the feasibility of constructing the new basin at the existing floor elevation. This will require detailed analysis of the basin fill hydraulics, the basin fill controls, as well as an evaluation of the relationship between the new Stage 2 train and the existing Stage 2 trains. This study assumes that the basin for the forth train will be identical to the existing three trains.

The concrete basins for the existing trains are recessed down below the building floor slab. The addition of the forth train will require saw-cutting, demolition, forming a new foundation, doweling into the existing floor slab, and providing watertight joints all around. Based on review of the record drawings and photos of the interior of the water treatment building, it appears feasible to add a new fourth basin of similar dimensions adjacent to the existing Stage 2 basins without compromising the building foundation or outer metal building structure.

The elevated walkway that currently surrounds train 13 will need to be reconfigured. **Figure 2-2** shows the existing walkway and **Figure 2-4** shows a possible reconfigured walkway. It is believed that much of the existing structure could be reused. Once the new basin is in place, there should be approximately 14 ft between the west wall of train 14 and the existing masonry wall. If the existing walkway structure is reused, the spacing between the support columns and the basin wall will likely encroach on much of the available space that traverses between the north and south roll-up doors. If a new walkway is installed, it can be designed such that the support columns and the stairs are positioned to maximize the clearance to move equipment through this area (**Figure 2-6**). The cost estimate presented in this document considers that a new walkway would be required.

The chemical feed lines that are routed from the chemical rooms along the south wall and underneath the elevated walkway (highlighted purple in **Figure 2-1** through **Figure 2-4**) will need to be moved underneath the relocated elevated walkway, similar to the existing chemical piping arrangement. Final location of the stairs to be determined during preliminary design. New piping is assumed for the relocated chemical piping.




Figure 2-1. Existing Stage 2 Trains, Upper Plan View




Figure 2-2. Existing Stage 2 Trains, Upper Plan View




Figure 2-3. Proposed Stage 2 Expansion (Fourth Train), Lower Plan View




Figure 2-4. Proposed Stage 2 Expansion (Fourth Train), Upper Plan View




Figure 2-5. Proposed Stage 2 Expansion (Fourth Train), Section View

2.2 Impacts to Existing Piping and other Stages

Operating with all four trains in the Stage 2 would impact the water recovered and fed to Stage 1. California Department of Drinking Water (DDW) limits the total amount of backwash recovered water to equal or less than 10% of the total plant influent flow. At the maximum total influent flow of 34 MGD, the maximum flow from the Stage 2 allowed for recovery would be 3.4 MGD. This is approximately 99% of the maximum flow that all four trains would produce in Stage 2.

Operating with all four Stage 2 trains would also produce 33% more reject, which will be sent to Stage 3. The impacts to Stage 4 of running with 4 trains in Stage 2 is incorporated into the discussion of DAF addition in Section 3.

The proposed Stage 2 UF expansion assumes the new UF train will be a redundant unit and Stage 2 will operate in an N+1 configuration, with one train in standby. **Table 2-3** presents a summary of the pipe velocities of the feed, permeate, and reject pipes with three Stage 2 UF trains operating at 1000 gpm. Hypothetically all four trains could be operated during times when lowering the flux is beneficial, i.e. when the Stage 2 membrane performance has degraded, or when the BWWEQ tank is critically high. **Table 2-4** present a summary of the hydraulic conditions assuming four train are operating at 1000 gpm. The pipe velocities of the feed and permeate headers are high for both cases, well above the industry standard of 7.0 ft/s. The velocity in the reject header with three or four trains operating is 5.5 ft/s and 7.4 ft/s, which are deemed acceptable. If the option to operate all for trains simultaneously is desired, it is recommended that the feed and permeate headers be replaced with 16" and 14" piping, respectively

(Table 2-5). Such replacement will require approximately 300 ft of new buried pipeline for the feed header, from the backwash waste EQ pump station to the Stage 2 membrane system. Two valves and a flowmeter on the feed header will also require replacement. The permeate header is approximately 200 ft long. The decision of upgrading the headers would need to consider the capital costs versus the benefit of operating with all four trains in Stage 2, which will only be on temporary basis, when the raw water quality is impaired or Stage 1 UF membranes require extensive backwash.

Table 2-3. Stage 2 Header Conditions with Three Trains Operating

Service	Size (in)	Material	Flow (GPM)	Pipe Velocity (ft/sec)
Feed Header	12	CPVC	3,530	11.30
Permeate Header	10	SS	3,000	11.29
Reject Header	6	PVC	450	5.64

Table 2-4. Stage 2 Header Conditions with Four Trains Operating

Service	Size (in)	Material	Flow (GPM)	Pipe Velocity (ft/sec)
Feed Header	12	CPVC	3,530	11.30
Permeate Header	10	SS	4,000	15.05
Reject Header	6	PVC	5,10	7.52

Table 2-5. Velocity in Upsized Feed and Permeate Headers

Service	Proposed Size (in)	Flow (GPM)		Pipe Velocity (ft/sec)	
		Three Trains	Four Trains	Three Trains	Four Trains
Feed Header (CPVC)	16	3530	4,700	7.14	9.52
Permeate Header (SS)	14	3,000	4,000	6.60	8.80

2.3 Blowers

Low pressure scour air is currently supplied to the stage 2 UF system by 2 blowers that operate in a duty standby configuration. The Zenon UF system operates in one of two aeration modes, *cyclic* or *constant* aeration control. When operating in cyclic control, air is supplied to half of the cassettes in a basin for a period of time, i.e. 30 seconds, then the flow is cycled to the other half of the basin. In constant control scour, air is supplies to the entire basin. The current volumetric air flow set point is 675 SCFM. Therefore, when operating in cyclic mode, 675 SCFM is directed to half of the train's cassettes at any given time, hence the total flow rate is 675 SCFM. When operating in constant mode, 675 SCFM is directed to all the cassettes in the train, hence the flow total rate is 1,350 SCFM. This is summarized in **Table 2-6**. Currently, when opening all 3 Stage 2 UF trains in cyclic mode the existing blowers can maintain the air requirements. When operating all three trains in constant mode the blowers operate near

the limits of its capacity. If four Stage 2 UF are to be operated at the same time, with the low pressure air system operating in constant mode, the existing blowers will likely need to be upgraded.

Table 2-6. Stage Scour Air System Operating Summary

Train	Aeration Control Mode	Volumetric Air Flow
ZW2-1	Cyclic	675 (SCFM)
ZW2-2	Cyclic	675 (SCFM)
ZW2-3	Constant	1,350 (SCFM)

2.4 Traveling Bridge Crane

The limits of the traveling bridge crane were evaluated with respect to the location of the new proposed Stage 2 UF train to verify the new proposed location will be accessible by the crane. **Figure 6** is section AS-3 from volume 2 of the Boyle Engineering March, 2000 structural drawing set with the new train super imposed and indicates the new proposed equipment will be assessable with the crane.




Figure 2-6. Traveling Bridge Crane

2.5 Electrical Improvements

The new UF train would likely be fed by MCC-2, which has a calculated load of 397Amps (A) based on the provided single line diagrams. The proposed new load (excluding improvements or additions to the existing air blowers) would be 40A. MCC-2 has a bus rating of 600A and thus has enough capacity to

accommodate the new train. However, the feeder circuit as well as the upstream breaker to this MCC would have to be upgraded to 600A.

The existing air blowers are fed from MCC-4, which has a total connected load of 692A on a bus rated for 800A. Upgrading the blowers from 100 HP to 150 HP will bring the total connected load to 804A.

Further understanding of plant operations may be required to draw a conclusion on the operating load on this MCC and its capacity to feed the proposed blower improvements. The cost estimate for this study did not consider upgrades to MCC-4.

2.6 Maintenance of Plant Operations

The addition of a new Stage 2 UF membrane train will require significant construction which will require interruption to the overall facility. During the detailed design a Maintenance of Plant Operation (MOPO) plan will need to be developed to outline and minimize plant shutdowns.

2.7 Recommendations

The new proposed Stage 2 UF train is recommended to be located adjacent to the existing Stage 2 train 13. This will require relocation of the existing CIP system to the area north of the existing Stage 2 UF trains, which will in turn require the relocation of the compressed air system currently located in the area proposed for the CIP system. The fabricated elevated walkway that surround the upper level of the UF basins will also need to be reconfigured to accommodate the new UF basin. **Table 2-7** summarizes the discussion above with regards to proposed modifications to accommodate the addition of the fourth train in Stage 2.

Table 2-7. Summary of Proposed Modifications

Item	Comment
Add Concrete Basin	Will require significant modifications to the existing plant infrastructure, including concrete work inside the membrane building.
Add Membrane System	Will require SCADA integration, additional piping, valves, and associated hardware.
Modify and Relocate the Walkway	Will encroach into the remaining space between Stage 2 and the west masonry wall.
CIP System Relocation	Potential challenges locating the pumps and associated piping in the area north of the Stage 2 membranes.
Air System Relocation	Relocate the existing equipment outside to the north side of the membrane treatment building, or to another location to be more optimal.
CIP Drain	Relocate the drain north of Stage 2, closer to the relocated CIP pumps.
Electrical and I/O Upgrades	Upgrade the feeder circuit and the upstream breaker for MCC-2. Evaluate Panel CC-3 for capacity to handle additional I/O.
Relocated Elevated Walkway	Reuse the existing structure or redesign with new material.

2.8 Estimation of Probable Cost

Table 2-8. Estimation of Probable Cost for UF Train Addition

Item Description		Total Costs
Sitework		\$164,200
Concrete		\$55,100
Miscellaneous Metals		\$123,200
Equipment		\$1,149,600
Mechanical		\$75,800
Electrical		\$187,000
Instrumentation and Control		\$35,700
Total Installed Equipment		\$1,790,600

Item	Description	Total Cost
1	Total Installed Equipment	\$1,790,600
2	General Conditions (allowed factor at this time) 10.0%	\$179,060
	Subtotal:	\$1,969,660
3	Contractor Overhead 10.0%	\$196,966
	Subtotal:	\$2,166,626
4	Contractor Profit 10.0%	\$216,663
	Subtotal:	\$2,383,289
5	Sales Tax (on materials only) 8.5%	\$98,195
	Subtotal:	\$2,481,484
6	Escalation at 3% annually* 4.8%	\$118,898
	Subtotal:	\$2,600,382
7	Bond and Insurance 3.0%	\$78,011
	Subtotal:	\$2,678,393
8	Contingency 20.0%	\$535,679
	Probable Bid Cost	\$3,214,000
9	Engineering 8.0%	\$257,120
10	CM 10.0%	\$321,400
11	Legal/Admin/Permitting 3.0%	\$96,420
	Probable Project Cost	\$3,888,940
12	Additional Cost for Stage 2 Feeder and Permeate Header	\$514,406
	Probable Project Cost (with Stage 2 Feeder and Permeate Header)	\$4,403,000

*Assumes construction starts January 2019.

3. DAF Addition to Stage 3

This section presents the conceptual design of a dissolved air flotation (DAF) system addition to Stage 3 at the DCMWTP. The plant currently utilizes three (3) lamella plate settlers for solids removal and thickening of water treatment residuals. Each of the existing plate settler systems was designed for 150 gpm capacity. During peak flows, all three lamella plate settlers are required in duty mode to meet the treatment capacity (lack of N+1 redundancy). In addition, the DCMWTP must reduce treatment capacity by 33% when any one settler unit is taken down for maintenance. DCMWTP staff are interested in adding a DAF system to provide enhanced capacity and redundancy for the existing plate settlers. In addition, the DAF system is proposed to treat strainer backwash water during periods when raw water quality diminishes due to the presence of filamentous algae.

The objectives of the sections are:

- Characterize the conditions related to current solids removal and thickening operations at the DCMWTP based on information provided by OMWD;
- Provide a conceptual design of a DAF system and other associated improvements, including location of major components;
- Present considerations related to the operation of Stage 3 along with other improvements in consideration at the DCMWTP; and
- Present the opinion of probable cost for the conceptual improvements.

3.1 Background

Raw water treated at the DCMWTP is obtained from relatively high-quality surface sources; however, water quality (turbidity and algae) can change depending on source water blending. A new DAF system is being considered for solids thickening in addition to the plate settlers. The DAF system will serve as a full redundant unit to the plate settlers and will augment the treatment of the strainers backwash waste during periods of declined water quality. Currently, Stage 2 UF reject and centrate from the Stage 4 centrifuge dewatering process are sent to the Stage 3 plate settlers for clarification and thickening. A project is planned to replace the internal components of the plate settlers due to ageing and corrosion. The updated components have potential to increase capacity; however, performance will need to be verified upon completion of the project.

Additionally, the flow of strainer backwash water is also being considered for treatment by the proposed DAF process during challenging water quality periods when strainer backwash can be nearly continuous for periods of time. Section 1 describes the proposed strainer backwash treatment. Under current operations that flow is discharged to on-site storm water drainage. The new DAF system can provide flexibility to treat and recover a large portion of the strainer backwash flow.

The purpose of the DAF process is to separate most of the solids present in Stage 2 reject, centrate or strainer backwash water by floating them to the tank surface for removal. Flotation is achieved by injecting a pressurized air-saturated recycle stream into the process flow. After flocculation, the water is exposed to micro-bubbles that are created by saturating 8 to 20 percent of the filtered water stream (DAF

recycle) with air in a packed tower pressure vessel (saturator) at 65 to 95 psig. The DAF recycle is added in the DAF contact zone and the pressure is suddenly reduced to atmospheric levels by the use of specially designed nozzles. As a result of the drop in pressure, air is released in the form of micro-bubbles that attach to the flocculated particles and float the particles to the surface of the tank. This process forms a dense foam (float) at the water surface. Periodically, the float is removed by a mechanical skimmer. The DAF float is then collected in a DAF holding tank and pumped to the centrifuges (Stage 4) for mechanical dewatering.

3.2 Stage 2 Reject Solids Characterization

The solids entering the Stage 3 process includes solids from Stage 2 and centrate from Stage 4 (centrifuge). The turbidity of the Stage 2 reject is monitored by an online turbidimeter (AIT-710-1). The daily averages of the collected turbidity data from January 2016 to December 2017 are provided in **Figure 3-1**. The turbidity data shows that the Stage 2 reject is highly variable depending on solids in the source water and the amount of treatment chemicals used at the DCMWTP. The turbidity during challenging source water conditions regularly peaks above 100 NTU, but on average is approximately 76 NTU. These turbidity levels are toward the high-end of solids treated by DAF systems; however, a pilot study was performed to confirm DAF performance capabilities at the DCMWTP (discussed below).

DAF Pilot Testing

In September 2010, a five-week pilot study was performed by Leopold (now Xylem) to evaluate DAF to treat solids entering Stage 3 of the DCMWTP. The pilot study tested various DAF operating strategies and several coagulants. The water quality (turbidity) during this time was consistent with the data presented in **Figure 3-1**, as turbidity in the water feeding Stage 3 was ranging between 60 and 80 NTU. The study evaluated loading rates between 4 to 8 gpm/ft² and DAF recycle rates between 7.3 to 19%. While there was some variability in the DAF pilot performance, mostly due to DAF pilot operational challenges, the DAF system did perform successfully to remove solids (as indicated by reducing turbidity). According to the study, the most effective operating strategy was a loading rate of 4 gpm/ft², with a recycle rate of 10%, and a flocculation time of 13 minutes. This operating strategy produced an average turbidity of 0.3 NTU. The most successful coagulant tested during the study was Nalco 4954, which is the current coagulant used in Stage 3 treatment.




Figure 3-1. Turbidity Data from Stage 2 Reject

3.3 Strainer Backwash Solids Projection

The strainer backwash water solids concentrations and particle distribution are currently unknown as they have been discharged to storm water drainage without monitoring. The characterization of suspended solids in the strainer backwash water will directly correlate to the floated solids removed in the DAF system; therefore, the characterization of suspended solids is important to properly sizing the equipment. It is recommended that a full characterization of the backwash water quality (after straining) be performed during preliminary design to refine the solids loading rates and appropriately size the DAF system and floated solids holding tank.

The pilot plant testing described above was performed on Stage 2 reject water only; therefore, the DAF system performance may differ significantly when treating strainer backwash water. At this time, the successful parameters from DAF testing (flocculation time, loading rate, and recycle rate) are assumed to be sufficient for treating strainer backwash water. It is recommended that bench-scale and/or pilot testing be performed on the strainer backwash water to confirm that the proposed DAF design parameters are adequate for treatment.

Projected Future Operations

Under normal operations, the Stage 2 reject and Stage 4 centrate is conveyed to the Stage 3 plate settlers. The Stage 4 centrate is collected in a tank and intermittently recycled/blended with Stage 2 reject water

prior to Stage 3. Depending on the optimization of centrifuge operation, some residual polymer may recycle and affect the performance of the plate settlers. Additionally, centrate must be pumped back to the main treatment building to be blended with the Stage 2 reject. As an option, the DAF system can operate in parallel with the plate settlers, and the centrate can be directed to the new DAF system (shorter pipe run) during normal operations.

As described in Section 1 - Strainer Backwash Water Recovery (SBWR) system, two operating scenarios are anticipated: normal mode and impaired mode. The normal mode of operation would be carried out for approximately ten (10) months of the year, when the raw water quality is relatively good and the strainers intermittently backwash based on time (about once every 3 hours), or when differential pressure on the strainers exceeds 4 psi. When the raw water quality is diminished, the strainer backwash quality may require an alternate treatment to adequately assure solids and algae removal. It is anticipated that treating the strainer backwash water with the DAF system would be more advantageous than the lamella plate settlers as there may be elevated levels of algae that are typically more likely to float than settle. The DAF system configuration will allow for parallel operation with the plate settlers during periods of increased flows and/or solids loading.

Below are the projected Stage 3 solids clarification and thickening future operations during normal and impaired mode. The proposed DAF operations at the DCMWTP are presented schematically in **Figure 3-2**.

Normal Mode

- Plate settlers provide routine solids removal and thickening operations of Stage 2 reject and Stage 4 centrate
- DAF system provides redundancy to plate settlers (and vice versa)
- DAF system treats centrate flow (optional)

Impaired Mode

- Plate settlers provide routine solids removal and thickening operations of Stage 2 reject and Stage 4 centrate
- DAF system treats higher flows from strainer backwash
- DAF system treats centrate flow (optional)




Figure 3-2. Stage 3 Process Flow Diagram with Proposed Modifications

3.4 Proposed DAF System

Based on the 600 gpm (0.86 mgd) flowrate of strainer backwash water to the DAF system, it is anticipated that a packaged DAF system would be a more cost-effective option than a component engineered system. A packaged DAF system may also allow for a faster design and construction schedule compared to a traditional DAF design for this size. Several vendors provide packaged DAF systems for drinking water treatment including Xylem (formally Leopold), Suez (formally IDI), and Roberts. Other manufacturers produce DAF systems for industrial or wastewater purposes; however, because they do not have confirmed NSF 61 materials they were not considered. The Suez system is a high rate DAF system that operates between 10-20 gpm/ft². Although the footprint would be reduced at the higher loading rates, performance of this system could not be confirmed; therefore, a system with a conventional loading rate was considered.

For the purpose of this preliminary conceptual layout, Xylem systems are used because the system utilizes a conventional loading rate system that has proven results for the DCMWTP. The proposed design utilizes one DAF train sized to treat 600 gpm; however, if desired, two (2) 300gpm trains may be installed as an alternative. Two (2) smaller trains would allow for operation at lower flows and provide more flexibility, but it anticipated that the design would be approximately 40-50% more expensive based on discussions with Xylem representatives. The design parameters and major equipment anticipated for the DAF system are provided in **Table 3-1** and **Table 3-2** respectively.

Table 3-1. Design Conditions – DAF System

Parameter	Unit	Value
Maximum Flow	gpm	600
Number of Trains	-	1
Number of Basins per Train	-	1
Number of Flocculation Stages per Basin	-	2
Flocculation Time at Design Flow	min	12
Basin Loading Rate at Design Flow	gpm/ft ²	4
Recycle Percentage	%	8-20, 10% average
Recycle Flow Per Train	gpm	70 gpm

Table 3-2. Major Mechanical Equipment

Parameter	Qty	Sizing
Static Mixers	1	-
Flocculation Mixers	2	1 HP ea. (2 HP total)
Air compressors	2	1.4 scfm , 5 HP ea.
Mechanical Skimmer	1	1 HP
Saturators	1	-
Recycle Pumps	2	70 gpm, 210 ft, 10 HP ea (1 duty, 1 standby)
Clarified Water Transfer Pumps	2	600 gpm, 10 HP ea. (1 duty, 1 standby)
Number of Solids Pumps	2	20 gpm, 5 HP ea. (1 duty, 1 standby)
Coagulant System	2	10 gpm, 1 HP ea. (1 duty, 1 standby)

The DAF system will require platforms, ladders, railings, and walkways for operator access to the top of the DAF unit. Conceptual layout of the equipment is provided in **Figure 3-3**. The approximate planning level cost for the DAF equipment shown in **Figure 3-3** is \$670,000.

3.5 Summary of Major Equipment

Mixing and Flocculator Equipment:

- Static Mixer - An in-line static mixer shall be provided on the influent line
- Flocculators - Each of the two flocculation stages will have an axial impeller type vertical mixer.

Recycle System Equipment:

- Recycle Pumps - Two (2) recycle pumps, (1) duty and (1) standby under normal conditions shall be provided. Both pumps may be required for higher recycle flows when solids loading from Stage 2 warrants a higher bubble concentration. The pumps shall be vertical multi-stage type each shall be controlled by a variable frequency drive to allow the recycle flow to be adjusted to provide the desired performance




Figure 3-3. Component layout of proposed DAF System

- Air Compressors – Two (2) air-cooled, oil-less rotary scroll air compressor package shall be provided to saturate air. Each package shall be mounted on an air receiver tank. The compressor package shall come complete with compressor, receiver, interconnecting piping, all accessories and appurtenances specified or otherwise required for proper operation.
- Saturation Tank - A packed tower air saturation tank with polypropylene packing shall be provided for saturating water. An injector style air saturator is not recommended.
- Dispersion Manifolds - Dissolved air dispersion manifolds shall be in the contact zone at the entrance to the DAF tank. Each manifold will be supplied with fixed orifice dispersion nozzles to uniformly disperse the saturated water. Two or three manifolds will be provided to help assure the appropriate bubble concentration over the anticipated range of recycle flows.

DAF System Tank Accessories:

- Process Tank - The dissolved air flotation process tank shall be constructed of painted carbon steel plates, suitable for potable water treatment. Tanks shall be supplied with FRP flow control weir plate, including two stage flocculation area, one flotation area, one solids area and one effluent area. The process tank will be provided with an appropriate coating for corrosion resistance of the water to be treated.
- Mechanical Skimmers – A chain and flight mechanical skimmer system with a non-metallic chain shall be provided. The motor shall be provided with a VFD motor and controller to allow the skimming rate to be adjusted as needed to remove float at the desired rate and frequency.
- Launder pipes – The clarified water shall be collected through perforated launder pipes fixed to the bottom of the process tank. The pipes shall be constructed of Schedule 80 PVC.

3.6 Coagulant Feed System and Storage

The strainer backwash water solids characteristics are not known at this time; therefore, the required coagulant dose and storage requirements cannot be estimated. It is recommended that bench-scale and/or pilot testing be performed to determine the required dose for treating strainer backwash water. The anticipated coagulant to be used for the DAF system would be Nalco 4954, which was tested during DAF pilot testing and is currently utilized for the Stage 3 plate settlers. Additional metering pumps could be added to the existing coagulant system in the solids treatment building and pumped into the process piping prior to the DAF system; however, it is likely that a dedicated coagulant system for the DAF system may be more desirable based on the relative distances of the various treatment processes. For a dedicated coagulant system, a bulk storage tank, day tank, transfer pumps, and metering pumps would be provided. For preliminary sizing purposes, it was assumed that the DAF coagulant dose would be similar to the doses tested during pilot testing (60 mg/L). At this dose, a 3,000-gal bulk storage tank would be provided for 30 days of storage.

3.7 DAF Solids (Float) Management

The possibility of pumping the DAF float directly to the exiting sludge tanks should be explored in the preliminary design phase, after an analysis of the characterization of suspended solid in the strainer backwash water and hydraulic analysis have been completed. For the purposes of this preliminary sizing, it was assumed that the (float will be collected in a holding tank, and two solids transfer pumps (one duty, one standby) will convey solids to the Stage 4 solids holding tanks, prior to being dewatered using the

centrifuge(s). The actual solids concentration of the strainer backwash water is unknown at this time. The solid transfer pumps will be piped and valved to provide dual purpose by permitting recirculation of solids in the float holding tank to help dissipate residual air and help normalize the concentration of solids delivered to the Stage 4 solids holding tanks. Currently it is assumed that float solids will be dewatered in Stage 4 using the same anionic polymer at a similar dose. For preliminary sizing purposes, it was assumed that the solids content would be similar to Stage 2 reject (76 NTU avg) and the DAF coagulant dose would be similar to the doses tested during pilot testing (60 mg/L). Based on these assumptions, a floated solids holding tank was sized to be 10,000 gal to provide between 1-2 days of storage.

3.8 Accommodations for Water Treatment Residuals System Expansion

The new DAF system will be provided to augment rather than replace the existing Stage 3 plate settlers; therefore, existing space within the residuals treatment building is not available. The DAF system is proposed to be located west of the residuals treatment building as show in Figure 3-4. The new building will be sized to also allow placement of the grit removal from the strainer water. The proposed layout is preliminary, as the sizing conditions for several pieces of equipment (coagulant storage and floated solids holding tank) are currently unknown. For preliminary sizing purposes, it is assumed that a 155 ft x 55 ft building will be provided for the DAF system and SBWR system.

3.9 Electrical and Instrumentation requirements

The DAF system will require 460 volts, 3 phase, 60 hertz service for the equipment. The system is proposed to be connected to MCC-5, as discussed in Section 1. It is recommended that the findings are confirmed during preliminary design to determine what electrical improvements are required to support the new DAF system. The DAF system will be provided with a Main Control Panel complete with a PLC and a visual HMI display. The PLC will be tied into the overall plant SCADA system. A turbidity meter would be required to analyze the clarified water from the DAF system and help monitor the performance.

3.10 Hydraulic Requirements

It may be possible for the DAF clarified water to flow by gravity to the backwash water equalization storage tank; however, this must be confirmed during preliminary design. For the purposes of this planning level study, it is conservatively assumed that the DAF clarifies water will require pumping to the existing backwash water equalization storage tank prior to the Stage 2 Membrane process. A hydraulic analysis is recommended during preliminary design to adequately size these pumps. For preliminary sizing purposes, it is assumed that two (1 duty, 1 standby) 600 gpm pumps will be provided; however, a larger number of smaller pumps may be desired for operational flexibility.

3.11 Operational Considerations

The strainer backwash water will contribute more solids to Stage 3, and could potentially increase the load to the centrifuge(s). Section 4 further details the addition of a second centrifuge, and it is anticipated that this will be sufficient to treat the additional thickened solids. The DAF unit is expected to routinely produce a higher concentration of solids when compared to the lamella plate settlers. Since the thickened

solids from both processes will be collected and stored in the thickened solids storage tanks, blended and equalized, a relatively uniform solids concentration will be conveyed to the centrifuge(s).

The performance of the thickening process may be impacted by optimization of coagulant dose. The streaming current monitor (SCM) is used to control coagulant for Stage 2 effluent. It is possible that the length of the sample line from the point of withdrawal to the instrument is excessive, and creates longer than desired detention times to appropriately control ACH coagulant dose. Solids can settle in the sample line, which further impact the representativeness of the sample and impact the desired ACH coagulant dose control. Further, the current location of SCM sample withdrawal should be evaluated with respect to the point of ACH coagulant and polymer dose locations to assure that chemical reactions are complete and all chemicals have been completely dispersed, without excessive time delays. Correlating the turbidity data to optimize coagulant dose is also recommended to aid in thickening operations. Because the solids content of the strainer backwash water has not been characterized, it is recommended that an additional turbidity analyzer be placed on the strainer backwash water line to assist operations in optimizing treatment of that future flow to the DAF system.

3.12 Recommendations

Table 3-3 summarizes our findings and proposed improvements for the addition of a new DAF System.

Table 3-3 – Summary of Proposed Modifications

Item	Comment
New DAF Building	Building to include new DAF system and the grit removal for the strainer backwash recovery system.
Packaged DAF System (600 gpm)	New DAF system to be provided with recycle pumps, air compressors, saturators, etc. Ladders, stairs and platforms not included in DAF package and provided separately.
Floated Solids Holding Tank and Pumps	Tank to be sized to be confirmed during preliminary design based on verified solids loading. Pumps to be sized appropriately to pump back to existing solids holding tanks.
Clarified Water pumps	Pumps to be sized appropriately based on system hydraulic analysis to pump to the backwash water equalization tank.
Coagulant System	Tank and pump sizes to be confirmed during preliminary design based on verified coagulant doses.
Piping	Modifications to allow Stage 2 reject and/or centrate to be directed to the DAF system. New piping to allow recovered strainer backwash water to be directed to the DAF system.
Electrical	Can be supplied from MCC-5. The existing circuits, main circuit breaker, and upstream breaker supplying MCC-5 would have to be upgraded to 600A to support the new load.




Figure 3-4 – Proposed Strainer Backwash Recovery System Location

3.13 Estimation of Probable Cost

Table 3-4 Estimation of Probable Cost for DAF Addition

Item Description	Total Costs
Sitework	\$68,500
Concrete	\$178,600
Miscellaneous Metals	\$492,900
Equipment	\$974,300
Mechanical	\$73,400
Electrical	\$289,500
Instrumentation and Control	\$103,900
Total Installed Equipment	\$2,182,000

Item	Description	Total Cost
1	Total Installed Equipment	\$2,182,000
2	General Conditions (allowed factor at this time) 10.0%	\$218,200
	Subtotal:	\$2,400,200
3	Contractor Overhead 10.0%	\$240,020
	Subtotal:	\$2,640,220
4	Contractor Profit 10.0%	\$264,022
	Subtotal:	\$2,904,242
5	Sales Tax (on materials only) 8.5%	\$123,780
	Subtotal:	\$3,028,022
6	Escalation at 3% annually* 6.1%	\$184,407
	Subtotal:	\$3,212,429
7	Bond and Insurance 3.0%	\$96,373
	Subtotal:	\$3,212,429
8	Contingency 25.0%	\$827,200
	Probable Bid Cost	\$4,136,000
9	Engineering 8.0%	\$330,880
10	CM 10.0%	\$413,600
11	Legal/Admin/Permitting 3.0%	\$124,080
	Probable Project Cost	\$5,004,560

*Assumes construction starts July 2019

4. Stage 4 Centrifuge Addition

This section presents the findings from the evaluation of the addition of a centrifuge in Stage 4 at the DCMWTP. The plant currently utilizes one centrifuge for the dewatering of water treatment residuals. While the existing centrifuge can adequately handle the range of water treatment residuals historically generated at the DCMWTP, OMWD is interested in adding a second unit to enhance reliability and redundancy. The objectives of this section are:

- Characterize the conditions related to dewatering operations at the DCMWTP based on information provided by OMWD;
- Provide a conceptual layout of the proposed centrifuge and other associated improvements;
- Present considerations related to the operation of the proposed improved Stage 4 water treatment residuals dewatering system in light of other improvements in consideration at the DCMWTP; and
- Present the opinion of cost for the conceptual improvements.

4.1 Background

The DCMWTP utilizes a series of treatment processes in the production of high quality potable water. Figure 4-1Figure 3-2 schematically represents these processes. Mechanical screening of raw water is followed by two stages of membrane filtration (Stages 1 and 2). Both stages provide ultrafiltration membrane treatment. The reject from the Stage 1 is filtered by the Stage 2 membranes, and the filtrate from Stage 2 is blended with raw water upstream of the Stage 1 membranes.

Stage 2 reject is directed to a series of residuals handling processes to maximize water recovery and minimize the disposal of residuals off-site. The reject from Stage 2 is currently treated by the three Stage 3 lamella plate settlers, which serve as thickeners upstream of the Stage 4 dewatering centrifuge. Sludge thickened in Stage 3 is stored in the two thickened sludge storage tanks before it is pumped to the centrifuge. The overflow from the plate settlers is recycled and blended with the Stage 2 influent, while the Stage 4 centrate flow is blended with the Stage 3 influent. Other than backwash flow from the raw water mechanical strainers, the plant currently has no liquid discharges. Dewatered residuals are collected in roll-off containers and trucked off-site.




Figure 4-1. Process Flow Diagram with proposed modifications

4.2 Water Quality Characteristics and Solids Generation Estimates

Raw water treated at the DCMWTP is obtained from relatively high quality surface sources. Characterization of solids generated at the DCMWTP was estimated by others based on raw water quality as sampled and is summarized in **Table 4-1**. These estimated values were developed from 95th percentile raw water quality data collected at the MWD Lake Skinner outlet (between 8/22/02 and 8/19/08), industry references¹, stoichiometric calculations and certain assumptions for projecting the generation of solids based on water quality factors².

Table 4-1. Estimated raw water solids generation, MWD Lake Skinner (CDM, 2010²).

Solids Constituent	Estimated Solids Generation (dry lb/MG treated water)
Turbidity	17.35
Color	11.68
Total Organic Carbon	25.35
Iron	0.64
Manganese	0.12
Total Estimated Raw Water Solids	55.14

Since these values are representative of the 95th percentile of raw water quality parameters, solids quantities under more typical conditions can be expected to be significantly less. For instance, the 95th percentile value for turbidity was 1.6 ntu, but plant staff have reported a recent average raw water

¹ *Integrated Design and Operation of Water Treatment Facilities* (Kawamura, 2000).

² *Supplemental Preliminary Design Report, David C. McCollom Water Treatment Plant LT2 Improvements Project* (CDM, February 2010).

turbidity of 1.2 ntu from 2015 through November 2017. The difference between the 95th percentile and the recent average turbidity level corresponds to 11.9 dry lb/MG of treated water, a 25% reduction for turbidity and a 7.9% reduction overall. Additional average or typical data was not available for detailed analysis, however the estimates in Table 1 are useful in understanding the higher-end of the range of solids generated at the plant based on raw water quality.

In addition to raw water quality, the various chemicals added for the treatment of process streams at the DCMWTP also contribute to solids generation. The chemicals and their application points are as follows:

- aluminum chlorohydrate (ACH)
 - coagulant (Stage 1)
- sodium hypochlorite
 - pre-oxidant and disinfectant (Stage 1 and finished water)
- Catfloc 4954
 - coagulant (Stage 3)
- polymer
 - thickening aid (Stage 4)

Among these chemicals, the only non-trivial impact on the generation of solids is due to the addition of ACH upstream of the Stage 1 filters, and Catfloc 4954 upstream of the Stage 3 lamella plate settlers. In order to estimate the impact, the LT2 PDR assumed the amount of solids generated by the addition of ACH ($\text{Al}_2\text{Cl}(\text{OH})_5$) would be equivalent to the addition of aluminum sulfate ($\text{Al}_2(\text{SO}_4)_3 \cdot 18\text{H}_2\text{O}$) which, at a dose of 3 mg/L, should correspond to 6.7 pounds of dry solids for every MG of water treated at the plant (per LT2 PDR). Since the ratios of aluminum to the molecular weights of ACH (30.9%) and aluminum sulfate (8.1%) are very different, this assumption may not be appropriate.

The exact chemical composition of Catfloc 4954 is proprietary, but it is also composed of aluminum compounds. The estimated solids generated from the use of Catfloc 4954 (as extrapolated from the LT2 PDR) was apparently approximately 0.78 times the mass of the assumed 90 mg/L dose to the influent of the Stage 3 thickening units, ranging between approximately 7.3 to 7.8 pounds of dry solids for every MG of water treated at the plant (under the three flow conditions modeled). The basis for this estimate is not clear based on the LT2 PDR.

Additional information related to the ACH and Catfloc 4954 solutions used at the DCMWTP is necessary in order to further evaluate the validity of the assumptions in the model. Hazen also recommends that the chemical characteristics of water treatment residuals be analyzed by a qualified laboratory as a means of confirming the aluminum solids component of the water treatment residuals. Understanding the total mass of aluminum in a sludge sample, relative to the total mass of the sample and the mass of the other constituents in the sample, could provide evidence related to the effect of ACH and Catfloc 4954 doses on the generation of water treatment residuals at the DCMWTP.

A “Solid-Liquid Mass Balance” model was developed by CDM to estimate the conveyance of the water treatment residuals between processes at the DCMWTP. This model utilized the solids generation estimates as described above and assumed certain performance criteria for the different processes in order to estimate the flow rates and solids concentrations in different process and waste streams. **Table 4-2** presents the model estimates for the daily centrifuge influent flow rates and solids load at both average

plant production and the design capacity of the plant. These values are useful for the selection of centrifuges and in predicting operating requirements—particularly the time necessary to dewater the water treatment residuals generated by the plant. These values suggest a thickened sludge concentration of approximately 1% at both average and design plant production, which is relatively consistent with the range of thickened sludge concentrations reported by the plant staff (1 – 1.5%), and is consistent with what is typically seen with lamella plate settler units operated at loading rates in accordance with manufacturer recommendations.

Table 4-2. Centrifuge influent estimates for the DCMWTP from a "Solid-Liquid Mass Balance" model (CDM, 2010)

	Centrifuge Influent	
	Flow (MGD)	Solids Loading (ppd)
Average Plant Production (20 MGD)	0.025	2,128
Design Capacity (34 MGD)	0.03	2,518

The approximate rate of water treatment residuals generation at the DCMWTP is discussed in the following section, and is useful in the consideration of the accuracy of this model.

4.3 Existing Water Treatment Residuals System

Water treatment residuals are currently collected and thickened in the Stage 3 lamella plate settler units (TK-710, TK-711 and TK-712). The thickened sludge from these units is collected and stored in two sludge storage tanks. Sludge from these tanks is conveyed by one of two progressive cavity centrifuge feed pumps (P-726-1 and P-726-2, both powered by variable frequency drives) to Centrifuge 1 (CEN-731) for dewatering. Centrifuge 1 is located in the Residuals Handling Building on an elevated platform. The dewatered residuals are discharged via a chute into a roll off container. This container is moved by operations staff using a forklift in the interest of evenly filling it with water treatment residuals, which are ultimately disposed of off-site. Centrate from the centrifuge is collected in a centrate tank and is recycled to the Stage 3 influent by two centrate return pumps (P-740-1 and P-740-2).

Centrifuge 1 (Model Aldec 406) was manufactured in 2002 by Alfa Laval. The centrifuge was manufactured based on the following design criteria.³

- Sludge flowrate: 42 gpm
- Feed solids: 2%
- Cake solids: 23%
- Polymer dose: 16 lb/dry ton
- Recovery: 95%

The centrifuge was upgraded by the manufacturer in 2010 and was relocated to its current location in the Residuals Handling Building. The following is a list of the upgrades to the centrifuge and associated controls:

³ Personal communication with Alfa Laval representative (e-mail message from Alfredo Fernandez, 11/22/17).

- 7.5 HP AC VFD Baldor Premium Efficiency Back Drive Motor
- Prefabricated Frame Modification Assembly to accommodate new Back Drive Motor
- NEMA 4X Centrifuge Operator Panel
- NEMA 12 Centrifuge Starter Panel
- ABB PLC
- ABB Model 800 HMI (PP845)
- ABB Variable Frequency Drives
- Power Loss Ride through Protection Feature

The Alfa Laval criteria listed above corresponds to an approximate hydraulic capacity of 60,000 gpd and a solids capacity of 10,000 ppd. These values are consistent with the typical operation of the centrifuge as reported by the DCMWTP operations staff (10.5 hrs/day, 7 days/wk) generating approximately 32 cubic yards (CY) of wet solids each week. One cubic yard of dewatered sludge from water treatment residuals generally weighs approximately 1 ton or 2,000 lb. If the dewatered sludge is 26% dry solids, approximately 16,600 lb of dry solids is generated at the DCMWTP in a typical week (or 2,400 ppd). This general approximation is slightly greater (13%) than the values estimated by the model under average plant production conditions. The hydraulic loading rates to the centrifuge was calculated based on this approximation, assuming a 1.2% thickened sludge concentration and 73.5 equipment operating hours in a week. The hydraulic loading rate is approximately 38 gpm and is within the manufacturer's design capacity of 42 gpm.

The model uses turbidity values that are slightly higher than typical conditions, but the values predicted in the model are slightly lower than what appears to be normally generated. The difference could be explained by a possible underestimation in the model of solids generated from the use of ACH and Catfloc 4954. However, the possibility of a discrepancy with the "Solids-Liquid Mass Balance" model does not have a practical impact on the operation of the DCMWTP centrifuge. It is worth considering, however, due to the possibility that the amount of solids generated at the plant may be more significantly related to aluminum-based precipitates from ACH and possibly from Catfloc 4954. The reliable production of safe drinking water is the primary goal of the DCMWTP and a change to the doses of the ACH or Catfloc 4945 solutions should never be considered if it could have a detrimental impact to meeting that goal. However, it may be worth considering reducing these chemical doses if it could reduce the quantities of water treatment residuals generated at the plant without detrimentally affecting the treatment performance of the plant.

4.4 Accommodations for Water Treatment Residuals System Expansion

Recent improvements at the DCMWTP provided a footprint and support systems for both Centrifuge 1 and an anticipated second centrifuge. Specifically, space for the second centrifuge was provided on the same elevated platform as the existing centrifuge. Space and piping accommodations were also provided for a third centrifuge feed pump.

Accommodations related to electrical supply and controls for the second centrifuge were also provided. Feeder breaker LCP-732 in Motor Control Center 5 was designated for the second centrifuge. The feeder breakers for both the existing centrifuge and the second centrifuge are sized to accommodate 30-hp main drives and 7.5-hp back drives. A centrifuge control panel was also installed on the same elevated platform near Centrifuge 1. Accommodations were made with the control panel to support the second

centrifuge including, but not limited to, providing a second PLC for the future centrifuge and include the representation of the second centrifuge graphically on the visual HMI displays. Some efforts to fully integrate the second unit will almost certainly be necessary when it is installed in the future, but this effort will have been greatly simplified by these accommodations.

4.5 Proposed Conceptual Water Treatment Residuals System Improvements

OMWD is considering adding a second centrifuge at the DCMWTP to enhance reliability and redundancy for the dewatering of water treatment residuals generated at the plant. The proposed centrifuge will have the same operating capacity as the existing centrifuge. A third centrifuge feed pump is also proposed along with a second centrifuge feed line dedicated to the second centrifuge. **Figure 4-2** presents the proposed layout for the new centrifuge 2 (CEN-732), new centrifuge feed pump 3 (P-726-3) and new feed line. These new features are also shown schematically in **Figure 4-3**.




Figure 4-2. Layout of the new centrifuge and centrifuge feed pump

While the model of Centrifuge 1 (Aldec 406) is no longer manufactured, Alfa Laval currently manufactures a similar version (Aldec 45, **Figure 4-4**) that would provide at least the same capacity as the existing unit. Alfa Laval provided a data sheet for this unit (attached), and indicated it is designed for sludge with a 2% solids concentration at a flow rate of 70 gpm. The budgetary cost of this unit is \$250,000 including controls, delivery and start-up support, but excluding installation costs and the costs associated with constructing associated support systems.




Figure 4-3. Existing and new centrifuge feed pumps.




Figure 4-4. Picture and general dimensions for Alfa Laval ALDEC 45

Alfa Laval indicated that it will be possible to match many of the same features of the proposed centrifuge to the upgraded Centrifuge 1. The variable frequency drives that were provided in the 2010 upgrade are no longer available from Alfa Laval, but similar drives can be used providing essentially the same or greater functionality. The controls systems for the new centrifuge can be integrated with the existing control panel.

The new Centrifuge 2 is proposed to be located in the area on the elevated platform as planned in the LT2 Improvements project. The platform for the centrifuges appears to be structural adequate from a high level review. Considering vibration loading based on the proposed new improvements of having two centrifuges in operation, the natural frequency of the platform would need to be compared with the operating frequency of the equipment to verify that the platform frequency is outside the design ratio for the equipment, otherwise there can be an issue with resonance. If necessary, additional stiffening of the platform can be proposed. Also, in order to get the natural frequency of the platform it would have to be modeled with structural software. Such determination should occur in design. The adequacy of the other

systems in place, including the electrical feed for the new centrifuge, should also be verified as part of the preliminary design.

The new Centrifuge Feed Pump 3 (Netzsch NEMO Progressive Cavity Pump model NM053BY01L07K.2) and Centrifuge Feed Line 2 are recommended to match the existing assets. The A new electrical circuit breaker and variable frequency drive will be necessary for the proposed new progressive cavity pump, which has a 5-hp motor. The proposed pump has an updated design with allows for fully servicing the pump in-place. A technical data sheet for the pump is attached. Isolation valves, check valves and other mechanical appurtenances for the new pump are recommended to match the existing pumps.

The new feed line, as indicated in Figure 3, will provide additional redundancy to the existing system. This configuration would allow for any of the three pumps to convey flow to either centrifuge if only one centrifuge is in operation. The configuration would also allow for conveying flow to both centrifuges simultaneously with Centrifuge Feed Pump 2 serving as a swing spare.

It may also be necessary or advisable to install a dedicated polymer feed pump for Centrifuge 2. While polymer could be fed to Centrifuge 2 through the same system that feeds Centrifuge 1, a second pump would provide redundancy, would simplify the operation of the centrifuge polymer feed system, and would allow for the simultaneous operation of both centrifuges. Adding a second polymer feed pump and new lines is therefore recommended.

4.6 Electrical Considerations

The electrical considerations for the centrifuge system were discussed in Section 1.

4.7 Operational Considerations

The existing water treatment residuals system is typically operated for 10.5 hours each day, seven days each week. The installation of the second centrifuge will provide OWMD with additional operational flexibility. Assuming the new centrifuge is operated at the same loading rate as the existing unit, the simultaneous operation of the two centrifuges could reduce the operating time each day by 50%, or it could reduce the required number of days of centrifuge operation as long as adequate thickened sludge storage is available. **Table 4-3** presents a simple comparison of operational approaches assuming a total of 73.5 hours of equipment time is required each week for the dewatering of water treatment residuals at the DCMWTP. The dual centrifuge operation could reduce the operating time to well within one 8-hour shift over both a 5-day or 7-day operating week.

Table 4-3. Simple comparison of single to dual centrifuge operation at the DCMWTP assuming 73.5 hours equipment operation time required per week.

Mode of Operation	Daily Hours of Operation	
	7-Days	5-Days
Single centrifuge operation	10.5	14.7
Dual centrifuge operation	5.25	7.4

Other improvements being considered as part of this study include the addition of a dissolved air flotation (DAF) process in parallel with the existing lamella plate settlers in Stage 3 for the thickening of water treatment residuals. Depending on the operation, the DAF unit could be expected to routinely produce a higher concentration of solids in the thickened sludge when compared to the lamella plate settlers. However, since the thickened sludge from both types of thickening processes will be collected and stored in the thickened sludge storage tanks, the thickened sludge will be blended and equalized, and a relatively uniform stream can be expected to be conveyed to the centrifuges.

In discussing the potential for variability in thickened sludge characteristics, Alfa Laval indicated little concern for the operation of the centrifuges, except a potential reduction in hydraulic capacity due to a slight reduction in the efficiency of the centrifuge due to the thicker solids concentration. For instance, an increase of thickened sludge concentration to 4% would reduce the hydraulic capacity of the new unit to approximately 35 gpm, while the solids capacity would remain constant. However, OMWD currently has the capability of reducing the solids concentration in the existing sludge storage tanks by adding water and mixing the sludge in the tanks with sludge recirculation pumps. This capability will be useful for controlling the concentration of solids in the thickened sludge in order to optimize the performance of the centrifuges.

Another improvement under consideration is related to the capture of the raw water strainer backwash stream. One component of the solids in this waste stream is likely grit, including Asiatic clam shells. This material can be expected to have a detrimental impact on the lifetime of certain wear items in the centrifuges. The service or replacement of some of these wear items can be significant as it involves servicing of the centrifuge at the manufacturer's facilities. Alfa Laval indicated that it is possible to provide a tungsten-carbide material upgrade for the feed zone of the centrifuge that would mitigate some of the wear caused by abrasive solids. However, it is recommended to capture the abrasive solids ahead of the treatment system and avoid introduction to the centrifuges. This proposed improvement is addressed in greater detail in Section 1.

4.8 Recommendations

Table 4-4 summarizes our findings and proposed improvements for improvements to the DCMWTP Stage 4 water treatment residuals system.

Table 4-4 – Summary of Proposed Modifications

	Item	Comment
1	Centrifuge 2	Proposed model will operate similarly to existing centrifuge, and can be fully integrated with the existing control system.
2	Centrifuge Feed Pump 3	Addition of the third centrifuge feed pump, with associated mechanical and piping improvements, will accommodate simultaneous operation of both centrifuges with redundancy.
3	Dewatering Polymer Feed Pump 2	The second polymer feed pump, feed line and associated mechanical improvements will be dedicated to Centrifuge 2.

4.9 Estimation of Probable Cost

Table 4-5 – Estimation of Probable Cost for Centrifuge Addition

Item Description	Total Costs
Equipment	\$307,200
Mechanical	\$13,600
Electrical	\$32,100
Instrumentation and Control	\$28,900
Total Installed Equipment	\$381,700

Item	Description	Total Cost
1	Total Installed Equipment	\$381,700
2	General Conditions (allowed factor at this time) 10.0%	\$38,170
	Subtotal:	\$419,870
3	Contractor Overhead 10.0%	\$41,987
	Subtotal:	\$461,857
4	Contractor Profit 10.0%	\$46,186
	Subtotal:	\$508,043
5	Sales Tax (on materials only) 8.5%	\$23,931
	Subtotal:	\$531,974
6	Escalation at 3% annually* 6.9%	\$36,583
	Subtotal:	\$568,557
7	Bond and Insurance 3.0%	\$17,057
	Subtotal:	\$585,613
8	Contingency 20.0%	\$117,123
	Probable Bid Cost	\$703,000
9	Engineering 8.0%	\$56,240
10	CM 10.0%	\$70,300
11	Legal/Admin/Permitting 2.0%	\$14,060
	Probable Project Cost	\$843,600

*Assumes construction starts January 2020

5. Potential Alternatives for DBPs Reduction

This section presents the findings from the evaluation of potential alternatives that could reduce disinfection byproducts (DBPs) at the DCMWTP and in the distribution system. Over the past year, OMWD has been impacted by a change in imported raw water blending ratio, which has led to variable source water quality, increased organics loading, and rising THM concentrations. The THM issue has been exacerbated at times by the presence of pre-formed THMs in the source water due to chlorination of the raw water by MWD. The primary objective of this study is to evaluate options to achieve the required disinfection credit under all source water conditions while maintaining DBP levels within regulatory compliance, meeting OMWD goals, and achieving optimized pathogen protection.

5.1 Background

Raw Water Sources for the DCMWTP

The source water for the DCMWTP originates from the Colorado River Water (CRW) and/or the State Water Project (SWP) via MWD. MWD controls the blend ratio between these two sources; that is, the source water at the DCMWTP consists of some percentage of CRW, with the remaining fraction from SWP. However, the water quality of these two sources can differ considerably, with the SWP typically containing more DBP precursors relative to the CRW. As such, when MWD increases the ratio of SWP water, OMWD experiences higher formation of DBPs at the DCMWTP and in the distribution system. Since OMWD has no control over the blend ratios, it must be prepared to treat a source water with higher fractions of SWP while maintaining the plant capacity and regulatory compliance.

Regulated Disinfection Byproducts

Regulatory compliance associated with disinfection byproducts requires a balance among several simultaneous objectives that include the acute risk of pathogens exposure, the long-term risk of suspected carcinogenic DBPs, and the acute and long-term impacts of exposure to lead and copper in the distribution system. These objectives are regulated among Safe Drinking Water Act requirements associated with the Long Term 2 Enhanced Surface Water Treatment Rule (LT2ESWTR), Stage 2 Disinfectants and Disinfection Byproducts Rule (S2D/DBPR), and the Lead and Copper Rule (LCR), respectively. While OMWD has historically been in compliance with the LT2ESWTR, S2D/DBPR, and the LCR, it is important to understand the regulations, so that the process/system changes that may be implemented to help reduce DBPs will not adversely impact compliance with these rules.

Compliance with the maximum contaminant limits (MCLs) for TTHM (80 µg/L) and HAA₅ (60 µg/L) is determined through the use of a Locational Running Annual Average (LRAA) at critical monitoring sites identified during the Initial Distribution System Evaluation (IDSE). The LRAA approach uses the annual average at each sampling location to determine compliance, addressing concerns of spatial variation in DBP exposure throughout the distribution system. The number of system monitoring locations again depends on the size of the population served by the given water system. The IDSE and LRAAs calculation will lead to lower DBP concentration requirements overall. However, this approach may still allow individual DBP samples above the MCL even when the system is in compliance. The rule requires systems that exceed operational evaluation levels (OELs) to evaluate system operational practices and identify opportunities to reduce DBP concentrations in the distribution system.

DBPs are formed by a chemical disinfectant (e.g., free chlorine) reacting with natural organic matter (NOM). Formation begins as soon as chlorine is added to the water at the DCMWTP and may continue as long as free chlorine and NOM are available. While a significant percentage of DBP formation may occur during primary disinfection, MCL violations typically occur in the distribution system as a result of continued exposure to free chlorine and extended contact time.

Parameters affecting DBP formation include detention time, chlorine residual, NOM concentration, pH and temperature. TTHM formation increases with an increase in each of these factors. The same is generally true for HAA₅ formation, with two notable exceptions: HAA₅ formation is favored as pH decreases, and, at very long detention times and low disinfectant residuals, biological degradation of HAA₅ can occur, causing a decrease in HAA₅ concentration. Among these factors, chlorine residual, pH, and NOM concentration are typically controlled at the water treatment plant (WTP), while temperature is not cost-effective to control, leaving detention time (water age) as the primary parameter that may be influenced by distribution system design and operation. Reducing water age by modifying distribution system design and operation is therefore one important aspect of DBP control, although reducing water age alone may not be sufficient to attain S2/DBPR compliance.

Many utilities establish internal objectives or goals for DBP concentrations to ensure compliance and/or establish a “buffer” to the MCL. Potential DBP compliance goals are outlined as follows:

- No LRAA exceeding the MCL
- No LRAA exceeding 80% (or other percentage) of the MCL
- No OEL exceeding the MCL
- No Quarterly value exceeding the MCL

OMWD would like to target LRAA values for TTHM and HAA₅ equal to or below 60% of the MCL, which is approximately the averages that historically have been achieved prior to the recent source water blends with a significantly higher ratio of SWP. These historical trends are shown in later sections of this memorandum.

Unregulated Disinfection Byproducts

Many DBPs have been identified that are not included within the current regulations for THMs and HAA₅. Several of these emerging DBPs may be more prevalent in finished waters and/or harmful to public health than those currently regulated. As such, researchers continue to investigate the occurrence and toxicity of the numerous potential byproducts formed as a part of disinfection. These studies, along with the Environmental Protection Agency’s (EPA’s) focus during the Contaminant Candidate List (CCL) and Unregulated Contaminant Monitoring Rule (UCMR) processes, may ultimately lead to expansion of the regulated DBPs. Thus, any treatment changes considered by OMWD should be flexible and/or rigorous enough to handle these potential short- and long-term regulations.

5.2 Water Quality and Disinfection Byproduct Characteristics

Water quality evaluation for this memorandum focused on historical TOC and DBP concentrations. Between 2013 and early 2017, the TOC and DBP levels were relatively consistent, with infrequent peaks occurring throughout this period. The DCMWTP does not regularly measure dissolved organic carbon (DOC) in the source water or finished water, but did perform a study to correlate DOC to TOC. The study

indicated that the DOC fraction in the TOC is approximately 0.96 (96%). During the first quarter of 2017, MWD changed the source water blend to a higher fraction of SPW, which is clearly noticeable in water quality recorded at the plant. The following figures summarize the trends associated with TOC and DBPs.

- Figure 5-1** – Source water TOC, finished water TOC, and the corresponding percent removal are shown in this chart. The significant shift in source water TOC is shown by the high peak in March-April 2017. Based on this data, the DCMWTP achieves approximately 15% TOC removal within the plant. Note that the percent removal of TOC required by EPA’s Stage 1 D/DBP Rule is 15% when alkalinity is greater than 120 mg/L as CaCO₃ and source water TOC is between 2 and 4 mg/L and is 23% when alkalinity is between 60 and 120 mg/L as CaCO₃ and source water TOC is between 2 and 4 mg/L. The percentages rise to 25% (ALK>120) and 35% (60<ALK<120) when source water TOC increases above 4 mg/L.
- Figure 5-2** – As shown in this chart, the TTHM concentrations in the finished water and at the monitoring points in the distribution system were historically at or below 60% of the MCL of 80 µg/L. When the source water changed during the first quarter of 2017, the TTHM concentrations increased significantly. During this time, the chart also indicates that significant formation continued after the finished water monitoring point.
- Figure 5-3** – Compliance with the S2D/DBPR is based on long-term running annual averages at each monitoring location in the distribution system. The LRAA is based on current and the previous three quarterly results. As shown in the chart, the peak in early 2017 did not result in non-compliance as the historical levels have been low. However, the upward trend is noted and could lead to a violation if the source water quality was not improved.
- Figure 5-4. TTHM OEL Trends** – DBP regulations also include early indicators of non-compliance by establishing operational levels that lead to system evaluation and changes if exceeded. Since the OEL calculation emphasizes current quarter results, the OEL for TTHM in early 2017 spiked above 80% of MCL. OEL triggers would be exceeded if source water quality remained poor.
- Figure 5-5. HAA5** – Although the primary focus of this study is TTHM, this figure indicates that the spike in early 2017 resulted in high levels of HAA₅, which approached 80% of the MCL in at least one of the sampling locations.
- Figure 5-6. TOC vs. TTHM** – DBP formation potential is a function of multiple parameters. However, one of the key water quality characteristics is organic carbon, and a spike in source water TOC in early 2017 was reflected in a DBP spike. In this chart, the finished water TOC is plotted along with finished water TTHM and TTHM readings at one of the sampling locations within the distribution system. As it can be seen in this chart, the general patterns of TOC change in the finished water are reflected in the resulting DBP production (with a few exceptions), indicating that TOC plays an important role in DBPs formation potential.
- Figure 5-7. Lack of Simple Correlation between FW TOC and FW TTHM** – Concentrations of finished water TTHMs was plotted against the finished water TOC. As seen in this chart, there is no simple correlation among the data, which emphasizes that variation in DBP production is

also a result of other water quality characteristics (e.g., pH and water temperature), specific component groups within the TOC measurement (e.g., humic and fulvic acids), and distribution system dynamics (e.g., water age).

In terms of the other important water quality characteristics in DBP formation, the plant staff at the DCMWTP did notice a shift in pH when the source water fraction of SPW increased. Specifically, the pH decreased from the typical pH value in low-8 range to values closer to the mid-7 range. At this time, MWD was supplying a blend that consisted of approximately 60% SPW and 40% CRW. In order to increase the pH during this time, the plant fed sodium hydroxide to increase the pH of the finished water back into the low-8 range. This finished water pH is targeted to minimize distribution system corrosion (i.e., increase LSI).




Figure 5-1. TOC Concentrations in Raw and Finished Water at the DCMWTP




Figure 5-2. TTHM Concentrations at Sampling Sites in the Distribution System




Figure 5-3. TTHM LRAA Trends in the Distribution System




Figure 5-4. TTHM OEL Trends in the Distribution System




Figure 5-5. HAA5 Concentrations at Sampling Sites in the Distribution System




Figure 5-6. TOC vs. TTHM Concentrations in Finished Water




Figure 5-7. Lack of Simple Correlation between FW TOC and FW TTHM

5.3 Existing Disinfection Practices at the WTP

Primary disinfection is achieved at the DCMWTP through a combination of removal credits for the UF membrane system and inactivation credits from free chlorine. The free chlorine must achieve 0.50-log *Giardia* inactivation and 3-log virus inactivation. The DCMWTP does not have a chlorine contact tank or clearwell onsite and, thus, must use approximately 4,925 linear feet of finished water piping (360 LF 42"-dia; 4,565 LF 48"-dia) for free chlorine contact time. Secondary disinfection (distribution system residual) is achieved with chloramines. The ammonia is injected approximately 1-mile downstream of the plant discharge in the distribution system, but before any storage reservoirs. OMWD staff currently report that there are no problems with nitrification or residual management within the distribution system.

The DCMWTP currently has three available chlorine feed points within the plant, including the following:

- Upstream of Strainers – This feed point is not currently in use, but the capability is maintained to help control biological activity/mussels in the strainers.
- Upstream of the Raw Water Equalization (RWEQ) Tanks – A low dose of free chlorine is currently fed at this location for control of biological activity/mussels in the Stage 1 Membranes. The sodium hypochlorite is dosed upstream of the RWEQ Tanks and the residual is measured downstream of the RWEQ tanks. The raw water target residual at this location had been approximately 1.0 mg/L; however, when the SPW ratio increased and the TTHM concentrations began to rise in early 2017, the raw water chlorine residual was lowered to 0.8 mg/L or less to help minimize DBP formation.
- Downstream of Stage 1 Membranes – This location is the DCMWTP's primary chlorine feed location for disinfection. The current dose target is set to achieve a residual of 2.9 mg/L.

5.4 Options for DBP Reduction

As DBPs present significant regulatory compliance concerns for OMWD, readily-implementable, proven, and feasible alternatives are needed. Common strategies for reducing DBP formation are listed below:

- Source water management and/or change.
- Treatment processes/improvements, implemented at the DCMWTP, to reduce DBPs precursors and/or minimize formation of DBPs.
- Strategies involving the distribution system to remove DBPs and/or reduce water age.

Evaluation of these strategies involves a stepwise assessment of operational and treatment improvements, with the goal of determining the most cost-effective method for ensuring regulatory compliance within a margin of safety. A list of alternatives and actions which may be used to address DBP compliance is shown in **Table 5-1**. **Table 5-2** describes the relevance to, and technical feasibility at the DCMWTP for each of these potential DBP reduction alternatives.

Table 5-1. DBP Reduction Alternatives

Potential Alternative or Action
Source Water Management
Develop TOC/UV254 correlation to manage source water episodes
Optimize Current Plant Operations
Disinfection
Alternate Coagulants
Powdered Activated Carbon
Implement Large Scale Treatment Modifications
Primary Disinfection
Alternate Pre-oxidants
Ion Exchange Resins [e.g., Magnetic Ion Exchange (MIEX®)]
Filter GAC Cap
Biological Filtration
Post-Filter Granular Activated Carbon
Membranes
Add/Improve Clearwell(s)
Implement Distribution System Operation Strategies for Reducing Water Age
Flushing
Examine Disconnected Loops / Dead Ends
Take Tanks Offline
Optimize Tank Operation
Implement Distribution System Treatment
Tank Aeration
Biologically Active Carbon

Table 5-2. Options for DBP Reduction at the DCMWTP

Item	Group	Potential Alternative or Action	Relevance to DCMWTP	Consider in Screening Evaluation
1	Source Water Management	Develop raw water TOC/UV254 to TTHM and HAA5 correlation curves to manage source water episodes. Develop triggers for plant adjustments.	It would be beneficial for the District to continue to characterize the daily source water quality (e.g., TOC/DOC, Cl residual from MWD, etc.) including using online instrumentation. Bench-scale testing should also be considered to check formation potential at various raw water quality levels. This data may be available through MWD and SDCWA but would need to be correlated to the DCMWTP. These improvements will help identify changes in source water quality but are only useful as an indicator of potential for elevated DBPs. Downstream adjustments will still need to be made.	Yes (as a general recommendation)
2		Change blending ratio of source waters	The District does not have control of blend ratio.	No
3		Switch raw water sources	District may not have this flexibility. Reservoir water could be used but may not decrease the formation potential.	No
4	Optimize Current Plant Operations	Optimize existing disinfection process	Because plant does not have a contact basin and is disinfectant contact time is limited to the volume of the existing finished water piping, flexibility for improvements to current disinfection process is limited. This option would include optimization of chlorine dosing and better control of chloramination process (chlorine to ammonia ratio, improve mixing, feedback). [Note that this should be a goal no matter the other options selected]. Also, the plant could consider addition of a dedicated contact tank to have better control over chloramination process - this option is included below.	Yes
5		Optimize existing coagulation process (e.g., pH control, alternative ACH brand)	Coagulants typically can be optimized for DBP precursor removal by increasing dose and/or decreasing pH. However, the dose at the DCMWTP is limited so as to not negatively impact the operations of the Stage 1 UF membranes. The plant increased the dose from 2.5 mg/L to near 5 mg/L, which did not significantly improve TOC removal but did begin to negatively affect the membrane flux. Thus, it is unlikely that the current coagulant could be optimized for enhanced coagulation at doses low enough to not hinder membranes without a settling step. Jar testing would be needed to determine TOC removal as a function of pH and dose.	Yes
6		Switch to alternative coagulants	Iron coagulants are typically more amenable to lower pH and, thus, higher precursor removal. However, as referenced above, it is unlikely that a high enough dose could be added for enhanced coagulation without negatively impacting the Stage 1 membranes. Conventional pre-treatment facilities for coagulation/flocculation/sedimentation would eliminate this limitation and is considered in alternatives below. Bench-scale jar testing would be needed to estimate DBP reduction as a function of coagulant dose and pH. The potential for increased solids production and the necessary solids handling capacity would need to be considered. Without a settling step, it is unlikely that a change in coagulants would have any impact at doses low enough to not hinder the membranes operation.	Yes
7		Add powdered activated carbon (PAC) to raw water	The existing Stage 1 membranes can handle PAC; however, the type and dose would need to be in compliance with Zenon's recommendations in order to avoid nullifying the existing and new warranties on the membranes. The dose would be limited because of this concern and, thus, precursor removal (and preformed DBP removal) is likely to be small. Jar testing would need to be performed to determine the optimum PAC type and dose for DBP reduction.	Yes
8	Implement Large Scale Treatment Modifications	Change primary disinfection process - UV disinfection	A UV disinfection system can be installed to deliver the necessary 0.5-log <i>Giardia</i> inactivation credit to replace the need for extended free chlorine contact time. The system can also be upsized to deliver 3-log virus credit to completely eliminate the need for free chlorine contact time. This system would then allow the plant to immediately inject ammonia downstream of the post-membrane chlorine site to minimize the formation of disinfection byproducts. The system could also be designed to support a potential future upgrade to an Advanced Oxidation Process (AOP) (e.g., UV/H ₂ O ₂) system for destruction of taste and odor (T&O) compounds and/or emerging contaminants.	Yes
9		Change primary disinfection process - ozone	District has a 60% design for ozone/BAC. Ozone could be used for primary disinfection, precursor destruction, and/or pretreatment for biologically active carbon contactors. In order to accomplish multiple objectives, may need new contact basins in addition to footprint for the ozone generators. Brominated DBPs were noted in historical water quality data; source water bromide and ozone would result in bromate formation. Potential for AOP options for future contaminants.	Yes
10		Change primary disinfection process - chlorine dioxide	ClO ₂ can be used for primary disinfection but may require an onsite contact tank to control CT and residual. Dose would be limited by MCL for chlorite formation. ClO ₂ would also provide some precursor destruction.	Yes
11		Switch to alternative pre-oxidants - chlorine dioxide	The plant does not currently use a preoxidant; however, there is chlorine residual in the source water and the plant does add a small dose of chlorine prior to the RWEQ tanks for biological control in the Stage 1 membrane process. This chlorine could be replaced by chlorine dioxide if a residual could be carried into the membranes. Dose may not be high enough to significantly degrade precursors. Chlorite formation would need to be considered. Bench-scale testing could be performed to determine impact of replacement of pre-chlorine with chlorine dioxide.	Yes

Item	Group	Potential Alternative or Action	Relevance to DCMWTP	Consider in Screening Evaluation
12	Implement Large Scale Treatment Modifications	Switch to alternative pre-oxidants - ozone	Ozone can be used as a pre-oxidant; however, because of the expense required to implement ozone, it should be considered for multiple objectives, e.g., primary disinfection. See item above.	No
13		Incorporate proprietary TOC reduction resins (e.g., MIEX)	Several vendors offer proprietary ion exchange resins targeting TOC removal (e.g., MIEX, Tonka). Implementation would require construction of contact/settling tanks. Additional solids handling and disposal would need to be considered. In addition, regeneration waste water (brine) would need to be disposed/recycled. Limited site space for contactors upstream of Phase 1 membranes.	Yes
14		Add a GAC cap to filters	DCMWTP does not have conventional media filters.	No
15		Convert to biological filtration	DCMWTP does not have conventional media filters.	No
16		Add post-filter GAC	Post-filter GAC could accomplish multiple objectives, including TOC/precursor removal to minimize DBP formation downstream and removal of pre-formed DBPs from the source water. GAC can also help mitigate T&O issues as well as emerging contaminants. Pilot-testing would be required to determine best media and the time to break-through, which impacts operational costs. Many pressure contactors needed for 100% flow treatment; may only need a 50% flow treatment blend to shave peak TOC issues. Site space, capital costs, and GAC replacement costs must be considered. Backwash water handling may require additional BWEQ tank. Note that GAC located upstream of the Stage 1 membranes could be explored to serve as pretreatment to the membranes in addition to removal of DBP precursors and pre-formed DBPs. In this raw water location, the GAC filters would also serve as a particle removal process, which could impact operations in terms of backwash frequency.	Yes
17		Add high-pressure membranes	High-pressure membranes (nanofiltration, RO) can remove high molecular weight DBPs (and precursors such as TOC). However, these membranes are energy-intensive and generate considerable volumes of reject water that would need to be disposed of. Capital and operational costs would be high. These membranes would also be removing more characteristics than needed and could increase aggressiveness of water.	Yes
18		Add clearwell/contact basin to optimize existing disinfection process.	As noted in the OMWD's LT2 study, the addition of a contact tank/clearwell could help the plant optimize the disinfection and chloramination process. Hydraulics would need to be considered as re-pumping might be necessary. Size of tank would be a function of CT and needed operational storage, as well as site space limitations. Since the plant has resolved previous issues related to flow/pressure variability, improvement would be minimal.	Yes
19		Install finished water aeration within treatment plant - In a new contact basin.	THMs, especially chloroform, are volatile and can be stripped using an aeration process. A new contact tank could be installed to facilitate aeration as well as optimize the disinfection process. Hydraulics would need to be considered as re-pumping might be necessary downstream of the tank. Note that HAAs are not removed by aeration.	Yes
20		Install aeration within treatment plant - In existing RWEQ tanks.	Although THMs are volatile, the stripping process does require minimum air:water ratios and contact time. The RWEQ tank volumes are relatively small and result in minimal contact time (minutes). Information on the tank dimensions and flows was provided to aeration system manufacturers, and they indicated that detention time was too short to effectively strip THMs. Thus, this option would not be effective.	No
21		Implement full conventional pretreatment (coagulation/flocculation/sedimentation) prior to membranes	Installing conventional coagulation, flocculation, and sedimentation upstream of the Stage 1 membranes would offer the flexibility to increase/optimize coagulant selection and dose to perform enhanced coagulation for TOC/precursor removal. Site space and solids production would be a concern. Hydraulics could also be an issue if trying to install such system between the energy-recovery units and the RWEQ tanks.	Yes
22	Implement Distribution System Optimization Strategies to Reduce Water Age	Distribution System Optimization: - Implement flushing program/auto-flushers - Eliminate dead-ends (impact likely small) - Take unneeded distribution storage tanks offline - Optimize operations to improve turn-over/reduce water age	Full-characterization of the distribution system was not a part of this project's scope. Modeling may be required to determine if/how tanks could be removed/optimized to minimize water age. Based on DBP data, there does not seem to be a single "problem" zone that could be targeted as all sample points tended to trend together. Although more would need to be known about the distribution system to quantify DBP reduction by water age reduction, it is still recommended that the District consider distribution system optimization as part of best practices/continual improvement.	No
23	Implement Distribution System Treatment	Install tank aeration in distribution system	Installation of aeration systems within distribution system storage tanks can be an effective method for stripping of THMs. The tanks within the District's system appear to be more than sufficiently sized to incorporate aeration systems. Hydraulics would need to be studied/modeled to determine how these tanks operate under high/low demand periods and which ones could have the most impact in terms of DBP reduction in any/all problematic areas. Since the DBP sample sites tend to trend together, aeration systems may need to be installed in numerous tanks to effectively reduce THM levels. Note that HAAs are not effectively removed by aeration.	Yes
24		Install BAC in distribution system	Biologically-active carbon can reduce both THMs and HAAs in the distribution system in problematic areas. However, these systems can be cost-, site-, and operationally-intensive. For the District's system in which there does not seem to be one primary problematic area, multiple systems might be needed. Backwash water disposal is needed. BAC is best suited for areas of high HAAs. District's current problem is primarily THMs.	No

5.5 Screening-Level Evaluation

As shown in **Table 5-2**, there are numerous potential options that could be implemented to optimize the disinfection process and/or reduce DBP formation at the DCMWTP. The first step in narrowing the list of options was to determine which options were not technically feasible for this installation, and these options are identified in the last column of **Table 5-2**. For the remaining options, a list of screening-level criteria was developed to prioritize the most effective options. For this analysis, the following criteria were selected for the initial evaluation:

- Potential to Reduce DBPs (Size of Impact)
 - Not all of the options work equally well on DBP reduction. Thus, the potential impact of the process on DBP formation was considered by this criterion.
- Operational Complexity
 - This criterion is intended to indicate how well the process change could be incorporated into existing treatment system and the ease/difficulty with which the process could be operated at the plant.
- Cost
 - A relative high-level judgement on the capital and operating costs required for implementation of the process.
- Will Easily Fit on Site
 - Site space is limited at the DCMWTP. Thus, this criterion provides a relative comparison of the size of the footprint required for the option.
- Will Easily Fit into Hydraulic Profile
 - This criterion is intended to distinguish whether the option could fit within the hydraulic grade line currently established between the source water and the distribution system.
- Will Help Reduce T&O
 - OMWD has experienced taste-and-odor events in the past, and, thus, the potential to achieve multiple objectives at the plant was considered as part of the evaluation.
- Increases Solids Production
 - As described in previous technical memoranda for this project, solids handling and treatment are critical limitations within the treatment plant. Some of the options considered for DBP reduction will produce a separate solids stream that must be considered within the evaluation.
- Will Produce Additional Liquid Waste Stream that will Need to be Recycled
 - Similar to the solids criterion, several of the DBP reduction options could produce a waste stream that must be handled within the DCMWTP. As OMWD targets zero-discharge, this liquid waste stream would need to be routed through the secondary phases and ultimately recycled.
- Potential to Negatively Impact Membrane Performance
 - The performance of the Stage 1 membranes is critical to the finished water quality and overall productivity of the DCMWTP. Thus, any process changes should not negatively impact the Stage 1 (or Stage 2) membranes.

Not all of these criteria are equal in importance for evaluating the processes. Weighting factors from 1 to 10, where 1 is least important and 10 is most important, were applied to each of the criteria. The

weighting factors selected for the screening evaluation are shown in **Table 5-3**. These factors may be modified by OMWD as necessary to reflect the importance and priorities associated with a disinfection optimization / DBP reduction project.

Table 5-3. Criterion Weighting

Criterion	Weighting Factor
Potential to Reduce DBPs (Size of Impact)	10
Operational Complexity	4
Cost	8
Will Easily Fit on Site	7
Will Easily Fit into Hydraulic Profile	6
Will Help Reduce T&O	2
Increases Solids Production	7
Will Produce Additional Liquid Waste Stream that will Need to be Recycled	8
Potential to Negatively Impact Membrane Performance	9

Each of the DBP reduction options was then evaluated under each criterion and a score assigned. The resulting decision matrix is shown in **Table 5-4**. The results of the decision matrix, prioritized by total weighted score, are shown in **Table 5-5**.

Table 5-4. Screening Level Decision Matrix

Criterion No.:	1		2		3		4		5		6		7		8		9			
Criterion:	Potential to Reduce DBPs		Operational Complexity		Cost		Will Easily Fit on Site		Will Easily Fit into Hydraulic Profile		Will Help Reduce T&O		Increases Solids Production		Will Produce Additional Liquid Waste Stream that will Need to be Recycled		Potential to Negatively Impact Membrane Performance			
Weight:	10		4		8		7		6		2		7		8		9			
Option	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Total Raw Score	Total Weighted Score
Develop TOC triggers for plant adjustments.	May have Medium-Small Impact - 2	20	Low - 3	12	Low - 3	24	Yes - 3	21	Yes - 3	18	No - 1	2	No - 3	21	No - 3	24	No - 3	27	24	169
Optimize existing disinfection process	Likely to have Small or No Impact - 1	10	Medium - 2	8	Low - 3	24	Maybe - 2	14	Maybe - 2	12	No - 1	2	No - 3	21	No - 3	24	No - 3	27	20	142
Optimize existing coagulation process	Likely to have Small or No Impact - 1	10	Low - 3	12	Low - 3	24	Yes - 3	21	Yes - 3	18	No - 1	2	Yes - 1	7	No - 3	24	Yes - 1	9	19	127
Switch to alternative coagulants	Likely to have Small or No Impact - 1	10	Medium - 2	8	Low - 3	24	Yes - 3	21	Yes - 3	18	No - 1	2	Yes - 1	7	No - 3	24	Yes - 1	9	18	123
Add powdered activated carbon (PAC) to raw water	May have Medium Impact - 3	30	Medium - 2	8	Low - 3	24	Yes - 3	21	Yes - 3	18	Maybe - 2	4	Yes - 1	7	No - 3	24	Yes - 1	9	21	145
Change primary disinfection process - UV disinfection	Highly Likely to have Large Impact - 5	50	Medium - 2	8	Medium - 2	16	Maybe - 2	14	Maybe - 2	12	No - 1	2	No - 3	21	No - 3	24	No - 3	27	23	174
Change primary disinfection process - ozone	May have Medium Impact - 3	30	High - 1	4	High - 1	8	Maybe - 2	14	Maybe - 2	12	Yes - 3	6	No - 3	21	No - 3	24	No - 3	27	21	146
Change primary disinfection process - chlorine dioxide	May have Medium Impact - 3	30	High - 1	4	Medium - 2	16	Maybe - 2	14	Maybe - 2	12	Maybe - 2	4	No - 3	21	No - 3	24	No - 3	27	21	152
Switch to alternative pre-oxidants - chlorine dioxide	Likely to have Small or No Impact - 1	10	Low - 3	12	Low - 3	24	Yes - 3	21	Yes - 3	18	Maybe - 2	4	No - 3	21	No - 3	24	No - 3	27	24	161

Criterion No.:	1		2		3		4		5		6		7		8		9			
Criterion:	Potential to Reduce DBPs		Operational Complexity		Cost		Will Easily Fit on Site		Will Easily Fit into Hydraulic Profile		Will Help Reduce T&O		Increases Solids Production		Will Produce Additional Liquid Waste Stream that will Need to be Recycled		Potential to Negatively Impact Membrane Performance			
Weight:	10		4		8		7		6		2		7		8		9			
Option	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Selection - Score	Weighted Score	Total Raw Score	Total Weighted Score
Switch to alternative pre-oxidants - ozone	May have Medium-Small Impact - 2	20	Medium - 2	8	Medium - 2	16	Yes - 3	21	Yes - 3	18	Maybe - 2	4	No - 3	21	No - 3	24	No - 3	27	23	159
Incorporate proprietary TOC reduction resins (e.g., MIEX)	May have Medium Impact - 3	30	Medium - 2	8	Medium - 2	16	Maybe - 2	14	Maybe - 2	12	Maybe - 2	4	Yes - 1	7	Yes - 1	8	No - 3	27	18	126
Add post-filter GAC	Highly Likely to have Large Impact - 5	50	Medium - 2	8	High - 1	8	Maybe - 2	14	Maybe - 2	12	Yes - 3	6	No - 3	21	Yes - 1	8	No - 3	27	22	154
Add high-pressure membranes	Highly Likely to have Large Impact - 5	50	High - 1	4	High - 1	8	Maybe - 2	14	No - 1	6	Maybe - 2	4	Yes - 1	7	Yes - 1	8	No - 3	27	17	128
Add clearwell/contact basin to optimize disinfection process.	May have Medium-Small Impact - 2	20	Low - 3	12	Medium - 2	16	Maybe - 2	14	Maybe - 2	12	No - 1	2	No - 3	21	No - 3	24	No - 3	27	21	148
Install finished water aeration within treatment plant - In a new contact basin.	May have Medium Impact - 3	30	Medium - 2	8	Medium - 2	16	Maybe - 2	14	Maybe - 2	12	No - 1	2	No - 3	21	No - 3	24	No - 3	27	21	154
Implement full conventional pretreatment (coag/floc/sed) prior to membranes	Likely to have Large-Medium Impact - 4	40	High - 1	4	Medium - 2	16	Maybe - 2	14	Maybe - 2	12	No - 1	2	Yes - 1	7	Maybe - 2	16	No - 3	27	18	138
Install tank aeration in distribution system	May have Medium Impact - 3	30	Medium - 2	8	Medium - 2	16	Yes - 3	21	Yes - 3	18	No - 1	2	No - 3	21	No - 3	24	No - 3	27	23	167

Table 5-5. Decision Matrix Results

Item	Group	Alternative	Total Weighted Score
8	Implement Large Scale Treatment Modifications	Change primary disinfection process - UV disinfection	174
1	Source Water Management	Develop raw water TOC/UV254 to TTHM and HAA5 correlation curves to manage source water episodes. Develop triggers for plant adjustments.	169
23	Implement Distribution System Treatment	Install tank aeration in distribution system	167
11	Implement Large Scale Treatment Modifications	Switch to alternative pre-oxidants - chlorine dioxide	161
12	Implement Large Scale Treatment Modifications	Switch to alternative pre-oxidants - ozone	159
16	Implement Large Scale Treatment Modifications	Add post-filter GAC	154
19	Implement Large Scale Treatment Modifications	Install finished water aeration within treatment plant - In a new contact basin.	154
10	Implement Large Scale Treatment Modifications	Change primary disinfection process - chlorine dioxide	152
18	Implement Large Scale Treatment Modifications	Add clearwell/contact basin to optimize existing disinfection process.	148
9	Implement Large Scale Treatment Modifications	Change primary disinfection process - ozone	146
7	Optimize Current Plant Operations	Add powdered activated carbon (PAC) to raw water	145
4	Optimize Current Plant Operations	Optimize existing disinfection process	142
21	Implement Large Scale Treatment Modifications	Implement full conventional pretreatment (coag/floc/sed) prior to membranes	138
17	Implement Large Scale Treatment Modifications	Add high-pressure membranes	128
5	Optimize Current Plant Operations	Optimize existing coagulation process (e.g., pH control, alternative ACH brand)	127
13	Implement Large Scale Treatment Modifications	Incorporate proprietary TOC reduction resins (e.g., MIEX)	126
6	Optimize Current Plant Operations	Switch to alternative coagulants	123

5.6 Potential Alternatives for DCMWTP

The results of the screening decision matrix indicate several key potential solutions to help reduce DBP formation at the DCMWTP and in the distribution system, including:

- Changing/modifying the primary disinfection system by adding a UV disinfection system.
- Use air-stripping of TTHM to reduce levels in the distribution system.
- Consider installation of a new oxidation process (e.g., ozone).
- Utilize granular activated carbon at the treatment plant.

These options are considered in more detail in **Table 5-6**. Sample site plans for several of these options are shown in **Figure 5-8**, **Figure 5-9**, and **Figure 5-10**. All new processes would be optimized around the locations of existing yard pipes.

Table 5-6. Level Two Evaluation of Potential Options

Parameter	Alternatives					
	Install UV Disinfection for Giardia Credit	Install UV Disinfection for Giardia and Virus Credit	Add Aeration/Mixing to One or More Storage Reservoirs in Distribution System	Add/change Pre-oxidant to Ozone or Chlorine Dioxide	Install GAC Contactors	Install GAC Contactors and Pre-Ozone
Design Criteria	0.5-1.0 log Giardia	3-log Virus	30-50% TTHM Reduction	Pre-oxidant doses, assume side-stream injection of ozone	50% Plant Flow Capacity / Blend	50% Plant Flow Capacity / Blend
DBP Reduction Mechanism	Elimination of extended free chlorine contact time in FW pipe; determine only that necessary for virus inactivation, then inject ammonia for chloramination.	Elimination extended free chlorine contact time in FW pipe; inject ammonia for chloramination immediately after primary free chlorine feed.	Air stripping of formed TTHMs	Oxidization of DBP precursors	Removal of pre-formed DBPs; removal of DOC	Removal of pre-formed DBPs; removal of DOC; biological degradation of pre-formed HAAs
Effectiveness on THMs	High	High	High	Low	Medium	High
Effectiveness on HAAs	High	High	None	Low	Medium	High
Disinfection credit - Giardia	UV	UV	Free Cl CT	Free Cl CT (plus ozone or ClO2 if designed as such)	Free Cl CT	Free Cl CT (plus ozone if designed as such)
Disinfection credit - Viruses	Free Cl CT	UV	Free Cl CT	Free Cl CT	Free Cl CT	Free Cl CT
Disinfection Multi-barrier / Crypto	UV	UV	None	None (unless ozone designed at disinfectant doses)	None	None (unless ozone designed at disinfectant doses)
T&O Reduction	None	Low	None	Medium	High	High
Location in Process Flow	Post Stage 1 Permeate Pumps	Post Stage 1 Permeate Pumps	Distribution System	Pre RWEQ Tanks	Post Stage 1 Permeate Pumps	GAC - Post Stage 1 Permeate Pumps; Ozone – Pre- or Post- Stage 1 Membranes
Location on Plant Site	Between BWEQ and new DAF facility	Between BWEQ and new DAF facility	Distribution System	Northeast of Stage 1 Membrane Building	Between BWEQ and new DAF facility -or- Southwest of existing fence-line in open area	Between BWEQ and new DAF facility -or- Southwest of existing fence-line in open area
Hydraulic Profile Impacts	Headloss should fit within HGL between Stage 1 Permeate Pumps and Distribution System Reservoirs	Headloss should fit within HGL between Stage 1 Permeate Pumps and Distribution System Reservoirs	Minimal - To be installed inside reservoirs in distribution system	Side-stream injection could be used to avoid maintenance of diffusers. Ozone contactors would need to be installed within HGL between energy recovery and Phase 1 membranes	Location between Stage 1 Permeate Pumps and Distribution system but would need to confirm available HGL since headloss can be significant.	Location between Stage 1 Permeate Pumps and Distribution system but would need to confirm available HGL since headloss can be significant, especially under biologically-active conditions. See ozone for side-stream injection.
Potential Size of Impact on DBP Reduction	High	High	Medium	Low	High	High
Planning-level Capital Costs	\$2M-\$3M	\$5M-\$7M (est.)	\$400k-\$700k per Reservoir	\$8M-10M	\$13M-\$15M	\$22M-\$25M (est.)
O&M Cost Impacts	Medium	Medium	Low	Low	High	High
General Advantages, Disadvantages, and/or Considerations	Fits within site space and hydraulic profile	Fits within site space and hydraulic profile	Can be installed within existing tanks and targeted at problem areas	Ozone has potential to form bromate if bromide present in source waters.	Contactors require backwashing, which creates new waste stream that would need to be recycled	Ozone has potential to form bromate if bromide present in source waters
	Capital and O&M costs relative to other options	No free chlorine contact needed to meet inactivation credits	Does not remove HAAs	Chlorine dioxide has potential to form chlorite	GAC replacement costs can be high	Contactors require backwashing, which creates new waste stream that would need to be recycled
	Does not remove pre-formed DBPs nor DBP precursors	Does not remove pre-formed DBPs nor DBP precursors	Flow must pass through tanks (i.e., not bypass during high-demand periods)	Potential to deliver biologically unstable water into distribution system (e.g., risk of nitrification) if no downstream biological filtration/contactors.		
	Does not degrade many emerging contaminants unless expanded to AOP	Does not degrade many emerging contaminants unless expanded to AOP				
Design Options	Expansion for AOP	Expansion for AOP	Construction of contact tank at DCMWTP for aeration	Ozone contact tanks vs. side-stream injection	Capacity of GAC (blend ratio)	Capacity of GAC (blend ratio); ozone contactors vs. side-stream injection

Parameter	Alternatives					
	Install UV Disinfection for Giardia Credit	Install UV Disinfection for Giardia and Virus Credit	Add Aeration/Mixing to One or More Storage Reservoirs in Distribution System	Add/change Pre-oxidant to Ozone or Chlorine Dioxide	Install GAC Contactors	Install GAC Contactors and Pre-Ozone
Info/Action Needed to Confirm Effectiveness/ Costs	Confirm performance curves of Permeate Pumps vs. HGL of distribution system reservoirs	Confirm performance curves of Permeate Pumps vs. HGL of distribution system reservoirs	Confirm dimensions of system reservoirs	Confirm bromide concentrations (if any) in source/finished waters	Confirm performance curves of Permeate Pumps vs. HGL of distribution system reservoirs	Confirm performance curves of Permeate Pumps vs. HGL of distribution system reservoirs
	Measure UVT of finished water over extended period	Measure UVT of finished water over extended period	Confirm actual detention time and flow rate in/out of reservoirs during both low- and high-demand periods	Bench-scale testing to determine impact on DBP formation potential under various doses	Pilot-scale tests to determine break-through curves for TOC, TTHM, and HAA5 for various carbon types and EBCTs.	Pilot-scale tests to determine break-through curves for TOC, TTHM, and HAA5 for various carbon types and EBCTs.
	Perform bench-scale tests to show change in DBP formation potential under varying contact times		Consider desktop modeling and/or vendor-testing to determine expected reductions in THMs.	Bench-scale testing to determine residual decay and formation of byproducts (bromate, chlorite/chlorate)	Blend-ratio of GAC-treated vs. untreated finished water needed to meet DBP objectives	Blend-ratio of GAC-treated vs. untreated finished water needed to meet DBP objectives
	Confirm contact time needed for virus inactivation credit					
Recommendations	Yes - Proceed with BODR	Design of Giardia inactivation only since minimal CT needed for virus credit.	Distribution system modeling	Bench-scale testing	Pilot-scale testing	Pilot-scale testing




Figure 5-8. Option for GAC Siting



Figure 5-9. Alternative for GAC Siting




Figure 5-10. Option for UV Siting

5.7 Recommendations

Table 5-6 presented general recommendations as part of the evaluation of each alternative. The alternatives can be prioritized based on cost-benefit in terms of expected DBP reduction and estimated capital costs. The results are shown in **Table 5-7**.

Table 5-7. Prioritized Alternatives

Alternative	Overall Expected Impact on DBP Reduction	Taste &Odor Reduction	Planning-level Capital Cost Estimates
Install UV Disinfection for Giardia Credit	High	No	\$2M-\$3M
Install UV Disinfection for Giardia and Virus Credit	High	No	\$5M-\$7M (est.)
Install GAC Contactors	High	Yes	\$13M-\$15M
Install GAC Contactors and Pre-Ozone	High	Yes	\$22M-\$25M (est.)
Add Aeration/Mixing to One or More Storage Reservoirs in Distribution System	Medium	No	\$400k-\$700k per Reservoir (Assume 7 Reservoirs, or Approx. \$5M)
Add/change Pre-oxidant to Ozone or Chlorine Dioxide	Low	Yes	\$8M-10M

Most of these DBP reduction processes require some form of bench- or pilot-scale testing to confirm expected reduction in formation potential and the capital and operating costs.

- UV systems do not typically need piloting if designed for disinfection only; however, UVT measurements will be needed to establish design and operating doses. In addition, water quality characteristics need to be examined to determine the potential for fouling of the quartz sleeves. Fouling potential can be experimentally-tested if water quality review identifies potentially problematic characteristics.
- GAC should be piloted to determine overall effectiveness, which can be measured by break-through curves generated for TOC and pre-formed DBPs. These break-through curves help establish design conditions (e.g., required empty-bed contact time) and operating costs (i.e., GAC replacement frequency). DBP formation potential is measured on each of the column effluent streams to determine expected reduction of both TTHM and HAA₅. Pilot testing also evaluates different types of carbon to determine the most cost-effective option. Carbon options can be tested on the bench-scale with Rapid Scale Small Column Tests (RSSCTs), but it is recommended that pilot-scale units be used to better predict operating conditions as well as carbon effectiveness. Depending on OMWD preferences, this testing can be done on both warmer and colder waters (i.e., two seasons). The cost of piloting is a function of the number of carbons tested and the length of the tests, but previous pilots have been completed in the \$50,000 - \$100,000 range per season of testing. The blend of source water would need to be determined.

- Ozone as a pre-oxidant to GAC can also be tested as part of the pilot experiments. Ozone fed prior to GAC frequently changes the process into a biologically-active carbon (BAC). As this testing involves the development of a biomass within the column, it often is a longer trial period, which will increase the piloting costs.
- Aeration effectiveness on TTHM stripping can be modeled and/or tested. The vendors have desktop models that are used to predict TTHM removal. The models are based on tank volume, tank size, flow rates in and out of the tank, detention time, and water quality characteristics. Testing is more complex given the need to match air:water ratios and is often not needed if tank modeling is matched with accurate distribution system hydraulic modeling and operation.
- Ozone alone (i.e., without GAC) can be evaluated on the bench-scale with jar testing. The costs are a function of the number of ozone doses and source water quality changes to be tested. Often these jar tests can be performed in as little time as one week and cost approximately \$20k-\$40k per season.

There are also several general good practices that OMWD should continue to help with DBP reduction. With the free chlorine CT currently being achieved in the finished water piping, the downstream injection of ammonia should be evaluated to determine effective mixing and to evaluate chlorine-to-ammonia ratios. In addition, the distribution system should be evaluated through modeling and/or SCADA-data review to determine optimum operations to minimize water age in the system.

In summary, it is recommended that OMWD:

1. Begin collecting UV transmittance data (at 254 nm) of the source water, post Stage 1 Membranes, and finished water. The data should be collected at least once per day for a period of at least six months. On several days during the early part of this period, multiple samples should be collected throughout the day to determine if/how transmittance changes on a diurnal basis. An absorbance scan from 200 nm to 400 nm should be completed once per month. All of these activities can be completed by plant-staff.
2. Plan and budget for a UV disinfection basis-of-design report.
3. Plan and budget for pilot testing of GAC with or without ozone.
4. Collect data specific to each of the storage reservoirs within the distribution system and submit to aeration/mixer vendors to better refine costs and performance of TTHM reduction systems.



Appendix A – Vendor Submittals

Treatment Technology	Quote Detail	Contact
Liquid Phase GAC (Calgon)	<ul style="list-style-type: none">• \$225K per unit vessel (Include freight and initial fill with GAC)• Replacement media cost: Approx. \$1.55/lb (including disposal), which at 40,000 lb/vessel equals \$62,000/vessel. Currently assuming 14 vessels: 14 x \$62k = \$870,000.	Ben Goecke bgoecke@calgoncarbon.com 425-286-0754 Email Quote on 12/4/2017
LPUV (Trojan)	<ul style="list-style-type: none">• \$ 110K for unit LPUV (Model SwiftSC D30)• \$ 280 for unit each lamp (each reactor has 30 lamps, lamp changeout is every 12,000 hr)	Jordan Fournier jfournier@trojanuv.com 519-457-3400 Email Quote on 12/4/2017
Aeration (Solarbee)	<ul style="list-style-type: none">• \$ 426K per reservoir (Include 5 aerators, 1 ventilation, 5 control panels), target 35-45% THM removal• Vendor does not recommend aeration of raw water equalization tank due to low retention time	Harvey Hibl harvey.hibl@medoraco.com 303-887-5323 Quote on 12/1/2017
Aeration (PAX)	<ul style="list-style-type: none">• \$ 733K per reservoir (Include 1 mixer, 2 ventilations, 9 surface aerators, 1 control panel), target 46% TTHM removal• Vendor does not recommend aeration of raw water equalization tank due to low retention time	Kevin Sanner ksanner@ugsicorp.com 310-975-9719 Quote on 12/4/2017

For additional information, reference following vendor information sheets.



San Diego Office
10650 Treenna Street
Suite 208
San Diego, CA 92131
858.842.1674

June 29, 2022

DRAFT Technical Memorandum

To: Geoff Fulks – Operations Manager
Lindsey Stephenson, PE – Engineering Manager
Tom Arellano – Water Treatment Facilities Supervisor
Evan DeWindt – Water Treatment Plant Lead Operator
Olivenhain Municipal Water District
19090 Via Ambiente Road, Escondido, CA 92029

From: Tom Bloomer, PE
Senior Associate Engineer
Joe Wendt, PE
Senior Project Manager
Peterson Structural Engineers, Inc.

Subject: David. C. McCollom Water Treatment Plant Condition Assessment

PSE Project Number:

2103-0037

Project Background/Executive Summary

Peterson Structural Engineers (PSE) has conducted a structural condition assessment at the David C. McCollom Water Treatment Plant (DCM WTP)(33.068569°, -117.140351°) at the request of owner and operator Olivenhain Municipal Water District (OMWD, District), in response to areas of deterioration and corrosion observed by District staff at the DCM WTP. Areas of concern identified and addressed in the condition assessment include the floor slab of the sodium hypochlorite room, the primary and secondary stage basins, and the stainless-steel pipes in the blower room.

Site visits to the DCM WTP were conducted by PSE employees on January 26th, January 27th, and March 22nd, 2022, to observe the extent of the deterioration at the locations listed in Table 1 and investigate and opine on potential drivers for the deterioration. This technical memorandum will summarize the results of the structural condition assessment, as well as provide recommendations and engineers opinion of probable cost for repair and rehabilitation. See Figure 1 for the investigated locations in plan. Our references to locations within each structure assessed will be based on the Plant North arrow shown on the as-built drawings.

Based on the as-built drawings provided, PSE understands that the DCM WTP was constructed in 2000 and received improvements associated with the LT2 requirements in 2011.

Table 1: Structures Evaluated

Structure Description	Summary of Observed Issue
Secondary Stage Basin 2	Liner in good condition, Loss of cementitious matrix in corewall
Primary Stage Basin 3	Leakage at south wall
Sodium Hypochlorite Room - Floor Slab	Concrete cracking, delamination of mortar overlay
Exterior Masonry Wall – Sodium Hypochlorite & Fluoride Rooms	Cracking, efflorescence, and deterioration of cementitious matrix
Blower Room – Pipe Gallery	External corrosion at welded joints




Figure 1: Locations of Areas Evaluated at David C. McCollom Water Treatment Plant

Condition Assessment

1st and 2nd Stage Basins

Based on the as-built drawings, the primary stage consists of (10) basins 50'-0" by 10'-0" by 11'-0" deep. The secondary stage consists of (2) basins 31'-0" by 9'-11" by 13'-0" deep, and (1) basin 31'-0" by 9'-10" by 13'-0" deep. Based on correspondence with the District, we understand that in 2006 the District installed a high-density polyethylene (HDPE) sheet liner in each of the primary and secondary stage basins to protect the concrete from observed deterioration and sloughing of the concrete that was causing the membranes to foul.

In preparation for the site visit, the District cut (7) rectangular openings, measuring between 68 in² and 132 in² in area, in the liner of the secondary stage basin No. 2. (1) opening was cut around a pipe penetration on the north wall approximately 3'-4" off the ground, and (2) holes were cut in the liner of each of the remaining walls, at approximately 1 ft and 9 ft off the ground. PSE was assisted with confined space entry into secondary stage basin No. 2 by Capstone Fire and Safety Management. The concrete that was visible through the openings in the liner varied in condition from fair to poor.

On the north wall of the basin, the concrete surrounding the pipe penetration appeared to be extremely deteriorated and eroded (Photograph 1). The cement matrix was worn away, exposing pieces of aggregate up to 1 ¼" in size. The east wall appeared to have minor surface deterioration and slight aggregate exposure but was in generally good condition at both locations where the liner was cut (Photograph 2 & Photograph 3). The concrete visible behind the lower cut in the liner on the south wall was also minorly deteriorated but in overall good condition (Photograph 4). At the upper liner cuts on the south and west walls, the concrete had minimal deterioration and was in overall good condition, possibly due to the positioning of the cuts very close to or above the normal water level. The concrete behind the lower liner cut on the west wall had significant deterioration and aggregate exposure (Photograph 5).

Additionally, the floor liner was observed to have several small holes, evidenced by sediment that leaked out as the liner was stepped on (Photograph 6). Several of the structural members at the top of the basin wall that are used to support the grating over the basin were observed to be moderately corroded (Photograph 7).

On the exterior of the basins, there were approximately (3) vertical cracks along the south wall of the basins, at secondary stage basin No. 3, primary stage basin No. 7, and primary stage basin No. 3. The cracks observed at secondary stage basin No. 3 and primary stage basin No. 7 appear to have autogenously healed¹ leaving behind a white efflorescence² (Photograph 8). The crack at primary stage basin No. 3 was observed to be actively leaking (Photograph 9). An effort was made by DN Tanks to pressure inject an NSF 61 certified foam into the crack during the visit. Initially the injection slowed the leak. However, when we returned to the site in late March the leak had increased since January but appeared to still be less than the original flow rate.

¹ Autogenous healing is the self-healing principle of a crack that is experiencing a slow flow of water that carries elements in the concrete mixture to the surface that ultimately blocks further passage of water.

² Efflorescence is the white salt deposit on the surface of the wall that results after the water has evaporated from the surface.

Sodium Hypochlorite Room Floor Slab

The sodium hypochlorite room is on the second story of a reinforced concrete masonry structure. On the first floor of the building, and immediately below the sodium hypochlorite room, is the fluoride room. According to information from District staff, the sodium hypochlorite room was originally an office, and the fluoride room was originally storage space before both rooms were converted to their current purposes. PSE understands that there have been two sodium hypochlorite systems installed in the sodium hypochlorite room over the life of the plant, both of which have had issues with leaks. The original on-site sodium hypochlorite generation system was replaced in 2014 with a PSI Microclor OSHG MC 2400 unit. Prior to installation of the PSI OSHG system, carpeting in the sodium hypochlorite room was removed and the floor was coated with Tnemec Hi-Build Epoxoline II Series L69. It is hypothesized that the carpet in the room when the original system was operating may have exacerbated the deterioration of the concrete since it likely retained the moisture of the highly concentrated chlorine mixture (NaOCl) for extended periods of time. It is important to note that the American Concrete Institute (ACI) Manual of Concrete Practice Code 350 – “Code Requirements for Environmental Engineering Concrete Structures” identifies Sodium Hypochlorite (up to 15%) as a Group 3B – Corrosion of Concrete, and that concrete exposed to this Group of chemicals should be given a protective coating.

Although we understand the current system to be less prone to leaks when compared to the original system, the PSI OSHG system was observed to be actively leaking while PSE was on site on January 26th (Photograph 10). During our visit in March, we observed that the leaking had been controlled by directing the flows into 5-gallon buckets and there was a blower in the room to dry up the previous spills.

The top surface of the slab in the sodium hypochlorite room was observed to have severe cracking and spalling in the areas around the equipment (Photograph 11 & Photograph 12). The underside of the slab, the ceiling of the fluoride room, was observed to have cracks up to 0.1 inches wide and blistering in the white coating (Photograph 13). Figure 2 is an approximate map in plan of the cracks. The 12” thickened slab edge displayed significant cracking up to 0.06” thick, and spalling, especially on the exterior face of the edge above the doorway (Photograph 14 & Photograph 15).

When sounded with a hammer, several large hollow areas spanning the full height of the thickened slab edge were observed. Some of the cracks in the concrete edge propagated into the masonry above or below the concrete. Two cracks in the slab edge on the south wall extended through the masonry to the ground (Photograph 16). Additional cracks were present in the masonry walls of the structure, including a full-height crack in the southwest corner of the fluoride room with efflorescence around it (Photograph 17). A 51” long vertical crack was also observed on the exterior of the southwest corner (Photograph 18). PSE noted moderate corrosion on the interior of the fluoride room door, indicating that the chlorinated solution from the sodium hypochlorite room is likely leaking through the cracks and down into the door frame (Photograph 19).




Figure 2: Map of Cracks in Underside of Slab

At the January 27th site visit, PSE was joined by an employee of DN Tanks, who performed investigative removal of the concrete in the top of the slab in the sodium hypochlorite room to expose the top layer of reinforcement. Figure 3 shows an approximate map of the locations where the investigations were conducted. The exposed reinforcement was observed to be moderately corroded (Photograph 20 & Photograph 21). The clear cover varied from $\frac{3}{4}$ " to $3\frac{1}{2}$ " in the exposed areas. The original as-built drawings state the clear cover shall be $1\frac{1}{2}$ ". DN Tanks also removed a portion of the CMU block and grout on the exterior southwest corner of the structure to expose the vertical reinforcement. The reinforcement in that location was also moderately corroded (Photograph 22).




Figure 3: Areas of Investigative Concrete Removal in Top of Slab

Based on initial findings, PSE returned to DCM WTP with DN Tanks on March 22, 2022, to perform investigative concrete removal on the underside and edge of the slab. Concrete was removed from the underside of the slab in three areas, (2) of which corresponded to areas of cracking in the slab, the other area serving as a control area to estimate the overall condition of the reinforcement. See Figure 4 for an approximate map of the areas of investigation. In the two cracked areas, which sounded disbonded or hollow when struck with a hammer, the concrete chipped apart very easily and small voids were observed in the slab, indicating existing delamination at the underside of the slab surface. The exposed reinforcement in both directions was moderately to significantly corroded (Photograph 23 & Photograph 24). In the area where the slab was not cracked, chipping into the concrete was more difficult, indicating that the concrete in these locations was well consolidated and in apparent good condition in that location. The reinforcement exposed in this area was free from corrosion (Photograph 25). Concrete removal was performed in one location on the slab edge above the fluoride room doors. The exposed rebar in this location was observed to be severely corroded with moderate section loss (Photograph 26). This location was selected because the area was already starting to spall and break away from the slab. Concrete removal in other locations, such as the larger hollow areas to the right of the door frame, was determined to be inadvisable due to the difficulty in repairing a larger area of concrete.




Figure 4: Areas of Investigative Concrete Removal in Underside and Edge of Slab

Blower Room Pipes

The stainless-steel piping in the blower room was found to be moderately corroded along the welds (Photograph 27 & Photograph 28). No section loss was noted on the exterior of the piping. The exterior welds on the piping were observed to be in overall good condition, with minor to moderate corrosion and staining. Welded patch plates were observed on the pipes in locations that appear to have had leaks in the past. The lack of material loss on the exterior of the pipes indicates that the corrosion may be originating from the welds on the interior of the pipe. Additional information on the condition of the pipes may be found in Appendix C: Harper and Associates Report.

Structural Analysis

The sodium hypochlorite system is assumed to weigh 2,500 lbs based on information from the manufacturer. This load is assumed to be distributed evenly across the floor slab as an area load equivalent to 12 pounds per square foot. As indicated in the original as-built drawings and as found in the investigative removal of concrete from the slab, the slab is reinforced in the north-south direction with #5 bars at 8" o.c. (Bottom), and in the east-west direction with #4 bars at 16" o.c. (Top) and 8" o.c. (Bottom). A two-way analysis of the slab was conducted in SAP2000, assuming pinned edges on the south, east, and west sides, and a fixed edge on the north side where the slab connects to the main building. The slab was analyzed for self-weight, the weight of the chlorination system, and an assumed 125 psf live load. The model indicates that the slab requires a minimum of 0.16 in²/ft of steel at the bottom face of the slab. The bottom steel provided in the slab, 0.3 sqin/ft, is significantly more than the required steel for the given loading, assuming no section loss of the existing reinforcing. The section loss in the reinforcing steel due to corrosion does not appear to reduce the reinforcing steel area to an amount lower than the minimum required. Therefore, the slab appears to be adequate for the given loading in its existing observed condition. However, action to prevent further deterioration and corrosion of the reinforcement is very strongly recommended.

Recommendations

Note that the cost estimates provided are intended to be considered equivalent to a class 4 estimate per the Association for the Advancement of Cost Engineering (AACE) International Recommended Practice No. 18R-97 (Cost Estimate Classification System – as applied in engineering, procurement, and construction for the process industries) and were prepared to form the basis for project screening and preliminary budget approval for the work. The estimates were developed to consider the probable construction costs (material, labor, and equipment) of recommended improvement projects for the basins, sodium hypochlorite room and pipes in the blower room and do not consider soft costs (engineering, permitting, project management, etc.) that may be needed. In addition, the estimate assumes that each recommendation would be performed as a separate project. There may be cost savings if multiple projects were to be performed concurrently. Given the preliminary nature of the estimates provided, it is recommended that an additional 30% contingency be considered for planning purposes. While the objective is to provide a cost estimate that is as close to the actual costs as possible, it can vary significantly due to varying factors which include but are not limited to the contractor's experience and project understanding as well as the state of economy, and bidding climate.

1st and 2nd Stage Basins

It is recommended that the existing liner is removed, and a coating system is applied to the concrete surfaces in the primary and secondary stage basins. Following the removal of the liner, the concrete surface should be thoroughly inspected and areas that have significant damage should be repaired in accordance with the selected coating system. After the inspection and repairs, the surfaces receiving the coating system shall be properly prepared to meet the coating manufacturer's recommendations and ensure a competent bond to the concrete. The District may consider a polyurethane coating or a compound fiberglass mat reinforced coating system, such as Tnemec series 215ML/22. PSE understands that this coating system has recently been installed on the interior surfaces of the basins at the San Diego County Water Authority's Twin Oaks WTP. Alternatively, the HDPE liner can be replaced with a new, properly sealed HDPE liner. However, as is evident with the current HDPE liner system, it is very difficult to ensure moisture does not penetrate behind the liner, so a coating system is recommended over a new liner.

Based on information from the coating contractor completing the basin re-coating at Twin Oaks and the product manufacturer, the cost to coat all of the basins at DCM is estimated to be between \$1.1 and \$1.85 Million. This estimate assumes that three adjacent basins can be initially taken offline to prevent vapor transmission through the common wall during the application of the new coating. After the first basin is coated, only 2 basins will be required to go offline at a time. The estimate assumes a continuous operation to coat all the basins (primary and secondary, total of 13) and also includes mobilization, labor, materials, and demobilization/project close-out. The estimate also includes an allowance for patching large cracks and/or voids up to 15% of the total surface area being coated. The removal of the existing liner as well as the removal and storage of the membranes is excluded.

Sodium Hypochlorite Room Floor Slab

It is recommended that any additional existing cracking and delamination in the floor slab in the sodium hypochlorite room be repaired by chipping out damaged concrete as necessary and filling in with a corrosion inhibiting bonding agent, such as Sika Armatec 110 EpoCem, and then repaired with a repair mortar such as SikaTop 122+. The repaired concrete surfaces are recommended to be coated in the sodium hypochlorite and fluoride rooms in order to prevent any further deterioration of the concrete and corrosion of the reinforcement.

Continued deterioration of the slab and reinforcement may weaken the slab and create an unsafe condition. Thus, it is recommended that repairs should take place in the next 6 months.

To ensure a more chemically resilient floor, PSE contacted Tnemec to provide input on a possible coating system. The objective of the coating system is to create a barrier to the concrete, similar to a secondary containment system. Tnemec recommends using their Ultra-Tread® S Series 242 and/or 245 depending on the depth of the material being broadcast over the floor. Ultra-Tread® is a polyurethane modified concrete that behaves like a flowable mortar floor topping. It is anticipated that the existing floor will need a self-leveling mortar as a filler in locations that exceed a depth of ½". Following the application of Ultra-Tread® the surface will be coated with Tneme-Glaze Series 280 which is a modified polyamine epoxy. Each one of these products has chemical resistance properties including sodium hypochlorite.

Based on information from Tnemec, the cost to install the coating system described above is estimated to be between \$20,000 and \$30,000. This cost may be reduced if done in conjunction with the rehabilitation work on the basins. The high cost per square foot is the result of the small surface area being coated and the number of steps and professional installers required to complete the project. The estimate includes mobilization, labor, materials, and demobilization/project close-out. The estimate does not include the removal of the PSI OSHG system.

In addition to replacing the existing coating with a more resilient coating, it would be beneficial to include a drainage system that would direct any leaks outside of the room. Our site visit identified a pipe conduit through the south block wall that could be repurposed as a drain. If leaks are directed to a storage vessel that can accommodate a sump pump or flow by gravity it would be possible to direct the sodium hypochlorite solution out through this conduit. Installing a drainage system will help prolong the life of the coating system. The cost to install this system is estimated to be between \$7,500 and \$10,000. The District's staff may wish to consider developing and installing this system to save money.

Blower Room Pipes

It is recommended that further investigation is conducted on the condition of the interior welds on the pipes to determine the state of their condition. This may be done using a scope camera. The welds may then be evaluated for any potential repairs, and, if necessary, a dye penetrant may be used on any new and existing welds to confirm that all defects have been found and repaired.

Conclusion

PSE appreciates the opportunity to share our findings and be part of the evaluations and condition assessments at the District's DCM WTP. We share the District's concern regarding the condition of the structures included in this Technical Memorandum and recommend the repairs presented are implemented as soon as possible to prevent further deterioration and risk to on-site personnel.

PSE recommends the District continue to periodically monitor and maintain the overall condition of the structures and document any changes to the conditions presented.

Endorsement

This report was prepared by Tom Bloomer, PE (CA License 64361), or under his direct supervision while an employee of Peterson Structural Engineers. All work is original and represents the opinions of a professional engineer registered in the State of California.

Appendix A: Photographs



Photograph 1: Concrete at Pipe Penetration on North Wall (01/26/2022)



Photograph 2: Concrete at Lower Liner Cut on East Wall (01/26/2022)



Photograph 3: Concrete at Upper Liner Cut on East Wall (01/26/2022)



Photograph 4: Concrete at Lower Liner Cut on South Wall (01/26/2022)



Photograph 5: Concrete at Lower Liner Cut on West Wall (01/26/2022)



Photograph 6: Hole in Floor Liner and Sludge (01/26/2022)



Photograph 7: Corrosion on Basin Steel Beams (01/26/2022)



Photograph 8: Crack and Efflorescence in Primary Basins



Photograph 9: Leaking Crack in Primary Stage Basin No. 3 (01/26/2022)



Photograph 10: Leaking from Chlorination System in Sodium Hypochlorite Room (01/26/2022)



Photograph 11: Damage to Sodium Hypochlorite Room Floor Slab (01/26/2022)



Photograph 12: Damage to Sodium Hypochlorite Room Floor Slab (01/26/2022)




Photograph 13: Cracking in Fluoride Room Ceiling Slab (01/27/2022)




Photograph 14: Cracking and Spalling in Slab Thickened Edge (01/27/2022)




Photograph 15: Damage to Slab Thickened Edge (01/27/2022)



Photograph 16: Cracking in Slab Thickened Edge and Masonry Wall (01/27/2022)



Photograph 17: Vertical Crack in Southwest Corner of Fluoride Room (01/27/2022)



Photograph 18: Exterior Vertical Crack at Southwest Corner of Fluoride Room (01/27/2022)



Photograph 19: Corrosion on Door of Fluoride Room (01/26/2022)



Photograph 20: Exposed reinforcement in Sodium Hypochlorite Room Floor Slab (01/27/2022)




Photograph 21: Exposed reinforcement in Sodium Hypochlorite Room Floor Slab (01/27/2022)




Photograph 22: Exposed Reinforcement at Southwest Corner of Fluoride Room (01/27/2022)



Photograph 23: Exposed Reinforcement in Ceiling of Fluoride Room, at Cracking Location (03/22/2022)



Photograph 24: Exposed Reinforcement in Ceiling of Fluoride Room, at Cracking Location (03/22/2022)



Photograph 25: Exposed Reinforcement in Ceiling of Fluoride Room, in Area Without Cracks (03/22/2022)



Photograph 26: Exposed Reinforcement in Thickened Slab Edge (03/22/2022)



Photograph 27: Corrosion on Blower Room Piping (01/26/2022)



Photograph 28: Corrosion on Blower Room Piping (01/26/2022)

Appendix B: Budget Level Cost Estimates

Dimensions Represent the Area to be Coated				
Description/Dimensions	Length (ft)	Width (ft)	Height (ft)	Total Area to be Coated (SQFT)
Sodium Hypochlorite Room	17.33	14.33	0.67	290.67
First Stage Basins (10 total, price given per basin)	50.0	10.0	11.0	1820.00
Second Stage Basins (3 total, price given per basin)	31.0	9.92	13.0	1371.25
***Areas for the basins are only the interior surface currently covered by the HDPE liner.				

Unit costs account for the total surface area being treated				Budget Level Estimates			
Description/Estimates	Lower Estimate (includes prep, labor and material) Per SQFT	Upper Estimate (includes prep, labor and material) Per SQFT	Contingency	Rough Order Planning Estimate - Lower Range	Rough Order Planning Estimate - Upper Range	Total Lower Range Estimate (all Basins)	Total Upper Range Estimate (all Basins)
Sodium Hypochlorite Room	\$50.00	\$75.00	35%	\$19,620.00	\$29,430.00		
First Stage Basins (10 total, price given per basin)	\$35.00	\$60.00	35%	\$85,995.00	\$147,420.00	\$859,950.00	\$1,474,200.00
Second Stage Basins (3 total, price given per basin)	\$45.00	\$70.00	35%	\$83,303.44	\$129,583.13	\$249,910.31	\$388,749.38
					TOTAL	\$1,109,860.31	\$1,862,949.38

Appendix C: Harper and Associates Report



HARPER & ASSOCIATES ENGINEERING, INC.

CONSULTING ENGINEERS

1240 E. Ontario Ave., Ste. 102-312, Corona, CA 92881-8671

Phone (951) 372-9196 Fax (951) 372-9198

www.harpereng.com

CORROSION REPORT

PROJECT: Corrosion Engineering Evaluation of Stainless-Steel Piping and Liner in Second Stage Filter Basins

STRUCTURES: Membrane Building (Train No. 8)
Blower Room (Stainless-Steel Piping)

OWNER: Olivenhain Municipal Water District

LOCATION: Encinitas, California

INVESTIGATED BY: Andre Harper, Project Engineer

DATE: January 2022

I. GENERAL INFORMATION

A. Contract Information

Harper & Associates Engineering, Inc. was retained by PSE/Olivehain Municipal Water District to accomplish field investigation of the HDPE liner in second stage concrete filter basins and stainless-steel piping in the blower room to observe liner and pipe surfaces and conditions, with photographs taken to record conditions. Concrete surfaces, where exposed were also investigated in the filter basins. According to information provided by others the liner was installed sometime in 2012. This report has been prepared with observations, conclusions, recommendations, and cost estimates for accomplishing the work.

This Corrosion Report is prepared solely based on noted field investigation. Conclusions and recommendations are strictly those determined by Consultant to be consistent with the best and most experienced practice within the corrosion engineering profession.

B. Site Conditions

The concrete filter basins and pipe gallery are located in at the District owned treatment plant in Encinitas. There is adequate room adjacent to the filter basin for vehicles and equipment. No difficulty is anticipated for Contractor mobilization, assuming use of normal portable air compressor and related equipment.

There are other basins, piping and processes within the building which could be adversely affected by dust and contamination associated with abrasive blast cleaning and painting

operations. Accordingly, extreme caution must be exercised during all cleaning and painting operations.

C. Existing Liners and Piping

1. Based on the field investigation and records provided, the liner and piping systems are as follows:
 - a. Concrete Filter Basins – The concrete basins are lined with High Density Polyethylene (HDPE).
 - b. Blower Room Pipe Gallery – The 42” pipe is marked as Schedule 5s T-304-L. It is assumed that the other stainless-steel piping is the same.

II. INVESTIGATION

A. Investigation was accomplished as follows:

1. Surfaces were inspected by traversing the piping gallery and entering the filter basin via a ladder.
2. Light was supplied via natural light and a strobe for the pictures.
3. Various chipping tools were employed to examine typical areas of defective liner and corrosion on the piping.
4. Photographs were taken of typical and specific areas to illustrate condition of surfaces.

III. OBSERVATIONS

A. Based upon the above reported investigation, the following observations were noted:

1. HDPE Liner in Second Stage Filter Basins
 - a. The HDPE liner exhibits numerous defects, holes, and gaps along the seams. (Photos I-1 through I-25)
 - b. Minor to moderate corrosion is present on the beams supporting the grating. (Photos I-1 through I-6)
 - c. The HDPE liner is bulging out from the concrete wall in several locations. (Photos I-6, I-7, I-17, and I-18)
 - d. Severely exposed aggregate is present where the liner was cut around a pipe penetration. (Photo I-9)
 - e. Random holes were found in the liner and random pop rivets were found to be loose and/or missing. (Photos I-10 through I-13)

- f. Varying degrees of exposed aggregate are present where coupons of the liner were removed for inspection. (Photos I-14 through I-19)
 - g. Random seams between HDPE panels were found to be loose. (Photos I-20 and I-21)
 - h. Moisture and sludge were found to be coming up through the liner at miscellaneous holes, seams, and patches. (Photos I-22 through I-25)
2. Blower Room Stainless-Steel Piping
- a. Minor to moderate general corrosion and staining are present along the welds and random patch plates on the stainless-steel piping. (Photos I-1 through I-34)
 - b. Patch plates have been welded over welds that appear to have been leaking in the past. (Photos I-8 through I-12, I-14, and I-15)
 - c. Areas of darker corrosion and dark staining are present at random patches. (Photos I-18 through I-21)
 - d. Close-up photos illustrating that little to no exterior metal loss is present. (Photos I-20 through I-25)
 - e. Only minor stain and no patch plates are present on the smaller diameter stainless-steel piping. (Photos I-26 through I-34)

IV. CONCLUSIONS

A. Based on the above noted observations, the following conclusions are drawn:

1. HDPE Liner in Second Stage Filter Basins
- a. The HDPE liner is in generally poor condition based on the number of defects present and the amount of moisture and sludge that appears to be getting behind the liner and making contact with the concrete substrate. The concrete will continue to deteriorate over time if the sludge and water continue to get behind the liner. Based on the type of liner and installation procedures that were utilized for this particular HDPE liner, it is HAE's opinion that the liner was not installed in a manner that would prevent water from getting behind the liner and contacting the concrete. There are other liners and/or coating systems that could be used, that would prevent the water from contacting the concrete.
 - b. Minor to moderate random corrosion on the beams above the basin appears to be due to defects in the galvanized beams and possibly mechanical damage that could have occurred when personnel are working around the basins.
 - c. The liner bulging out from the concrete walls appears to be due to a

combination of the liner not being sufficiently mechanically bonded to the concrete walls and moisture and sludge getting behind the liner.

- d. The severely exposed aggregate is due to the concrete being exposed to chemicals in the water that deteriorate the surface layer. Low alkalinity will also adversely affect the concrete.
- e. Random holes in the liner appear to be mostly due to missing pop rivets, but some holes may be due to mechanical damage as the holes do not seem to fit the pattern the pop rivets were installed.
- f. Varying degrees of exposed aggregate found where coupons were removed are due to the reasons noted in A. 1. d. The varying degrees of deterioration most likely correspond with the length of time the concrete was exposed to the moisture behind the liner.
- g. HAE is not familiar with this particular liner material, and therefore does not know how the seams are connected. It could be a mechanical connection, thermal welding, glue or some other fastening method. It is also not known if the failure at the joints is widespread or if the failures are isolated.
- h. Moisture and sludge behind the liner is due to the various points of deterioration and holes in the liner discussed above.

2. Stainless-Steel Piping

- a. The vast majority of the exterior of the stainless-steel piping is in good condition with random spots of corrosion and staining present. The interior surfaces could not be inspected, but it is anticipated that the interior welds are severely corroded and are the primary source of the corrosion that is being found on the exterior of the piping.
- b. The patch plates and random spots of corrosion are likely due to porosity of the welds on the interior of the piping.
- c. Darker spots of corrosion appear to indicate the location of perforations.

V. RECOMMENDATIONS

- A. Based on the above noted observations and conclusions, the following recommendations are offered.

1. HDPE Liner Second Stage Filter Basins

- a. HAE recommends installing a Hypalon or HDPE liner that is completely sealed so water cannot flow behind the liner or applying a high-build coating system to all concrete surfaces. As can be seen below, the cost for a liner verses a high-build coating system is relatively close. However, installing the liner around all the piping and appurtenances would be very

difficult and it only takes one area that is not properly sealed to allow water to flow behind the entire liner in the basin. Therefore, HAE would recommend installing the high-build coating system. The coating will protect the concrete from further degradation and if random defects develop in the coating over time, it will not compromise the entire system.

- b. The corrosion on the overhead beams should be monitored, and if the minor to moderate corrosion leads to metal loss the corroded beam(s) should be replaced.
- c. At this time, no significant concrete damage was observed, but when the entire liner is removed there may be areas of damage. When a new liner or coating system is installed, an optional item should be included for cementitious repairs for significant concrete damage if needed.

2. Stainless-Steel Piping

- a. As it appears that the exterior of the piping is in relatively good condition, it is HAE's recommendation that the interior of the piping be evaluated to determine if the interior welds are porous or isolated imperfections are present. It may be necessary to grind out and replace defective portions or entire welds on the interior of the pipe.
- b. The existing and new welds should be tested with a dye penetrant to confirm that all defects are found and repaired.

VI. COST ESTIMATES

- A. Based on current and previous projects of similar scope, preliminary cost estimates for work as noted in RECOMMENDATIONS were calculated by using data from those projects. There are three (3) basins at 10'x33'x12' high and nine (9) basins at 10'x50'x12' high for a total of 21,550 sq. ft.

- 1. Furnish and install a HDPE or Hypalon Liner: Installation of a liner would be in the cost range of \$20 to \$25 per square foot for a total of 21,550 sq. ft. or \$431,000 to \$538,750, excluding removal of the existing liner.
 - a. 10'x33'x12' Basin = \$20,660 to \$25,825 per Basin
 - b. 10'x50'x12' Basin = \$28,800 to \$36,000 per Basin
- 2. Abrasive blast cleaning the concrete walls and floors and applying a polyurethane coating system would be in the cost range of \$22 to 28 per square foot for a total of 21,550 sq. ft. or \$474,100 to \$603,400, excluding removal of the existing liner.
 - a. 10'x33'x12' Basin = \$22,726 to \$28,924 per Basin
 - b. 10'x50'x12' Basin = \$31,680 to \$40,320 per Basin
- 3. Repairing random corrosion on the wall, columns and floor would be in the cost range of \$40 to \$50 per sq. ft. The quantity of repairs cannot be determined until the liner is removed and the interior of the basins can be better evaluated.

Respectfully submitted,

HARPER & ASSOCIATES ENGINEERING, INC.



Andre Harper
Project Engineer



HARPER & ASSOCIATES ENGINEERING, INC.

CONSULTING ENGINEERS

1240 E. Ontario Ave., Ste. 102-312, Corona, CA 92881-8671
Phone (951) 372-9196 Fax (951) 372-9198
www.harpereng.com

PHOTOGRAPHIC SURVEY

PROJECT: Corrosion Engineering Evaluation of Stainless-Steel Piping and Liner in Second Stage Filter Basins

STRUCTURE: Membrane Building (Train No. 8)
HDPE Lined Second Stage Filter Basin


OWNER: Olivenhain Municipal Water District

LOCATION: Encinitas, California

PHOTOGRAPHED BY: Andre Harper, Project Engineer

DATE: January 2022

- I-1 View of the upper portion of a 2nd stage basin and the galvanized grating above the basin.
Note minor to moderate corrosion on the beams supporting the grating.



- I-2 View of the temporary ladder and HDPE liner on the walls in the background.



- I-3 View of one of the support beams, illustrating minor to moderate corrosion on the beam.



- I-4 View of the upper wall of the basin, illustrating generally good condition of the HDPE liner.



- I-5 Same as Photo I-4, except in a different location. Note white pop rivets along the top edge of the HDPE liner and randomly on the lower surfaces.




- I-6 View of the upper portion of the HDPE liner, illustrating an area where the liner is bowed out from the wall.




- I-7 View of the lower portion of the basin, illustrating generally good condition of the liner material.




- I-8 View of a PVC pipe penetrating the concrete, illustrating the liner has been cut around the penetration and pop riveted to the concrete.



- I-9 Same as Photo I-8, except a closer view of the cut out. Note aggregate is severely exposed around the pipe.




- I-10 View of the liner, illustrating a hole with brown staining around the hole and moisture running down the liner below the hole.




- I-11 Close-up view of the liner, illustrating two holes with an unknown red material present.



- I-12 Close-up view of the liner, illustrating a hole with a white spot in the middle.



- I-13 View of the liner, illustrating a pop rivet that is coming loose.



- I-14 View of a cut out in the liner, illustrating generally good condition of the concrete in this location.



- I-15 Same as Photo I-14, except in a different location. Note lightly exposed aggregate.




- I-16 Same as Photos I-14 and I-15, except in a different location. Note moderately exposed aggregate in this location.



- I-17 View of a cut out near the bottom of the wall, illustrating the liner is bowed away from the concrete.



- I-18 Same as Photo I-17, except a scraper was utilized to illustrate the distance between the concrete and backside of the liner.




- I-19 Same as Photos I-17 and I-18, except in different location.



- I-20 View of a scraper inserted into a vertical lap seam, illustrating the seam is not tight in this location. Note the head of a white pop rivet above the scraper.



- I-21 Same as Photo I-20, except on the floor of the basin.



- I-22 View of the floor of the basin, illustrating spots of moisture coming up through the liner.



- I-23 Same as Photo I-22, except at the other end of the basin.



- I-24 View of a patch with 4 bolts penetrating through the liner, illustrating moisture coming through the patch and minor corrosion on the bolts.



- I-25 Close-up view of the floor, illustrating holes with moisture and sludge coming up through the holes.





HARPER & ASSOCIATES ENGINEERING, INC.

CONSULTING ENGINEERS

1240 E. Ontario Ave., Ste. 102-312, Corona, CA 92881-8671
Phone (951) 372-9196 Fax (951) 372-9198
www.harpereng.com

PHOTOGRAPHIC SURVEY

PROJECT: Corrosion Engineering Evaluation of Stainless-Steel Piping and Liner in Second Stage Filter Basins

STRUCTURE: Blower Room Stainless-Steel Piping

OWNER: Olivenhain Municipal Water District

LOCATION: Encinitas, California

PHOTOGRAPHED BY: Andre Harper, Project Engineer

DATE: January 2022


- I-1 View of stainless-steel piping transporting combined influent, illustrating corrosion staining at the circumferential welds.



- I-2 Same as Photo I-1, except in a different location. Note welded patches on circumferential welds.



- I-3 Same as Photos I-1 and I-2, except at a stainless-steel support stand. Note random spots of corrosion on the piping in this location.



- I-4 Same as Photo I-3, except at the backside of the piping.



- I-5 View of a butt strap and saddle, illustrating minor corrosion staining along the welds.



- I-6 View of a Victaulic coupling, illustrating very little to no corrosion on the coupling or along the edges.



- I-7 View of a circumferential weld, illustrating rust scale present where it appears the pipe has been leaking.



- I-8 View of a weld that appears to have been overlayed with an additional weld. Note dark spots where it appears leaks are present.



- I-9 View of a welded patch on the bottom side of the pipe, illustrating dark areas that appear to have been leaking.




- I-10 Same as Photo I-9, except in a different location.



- I-11 View of two weld patches on the topside of the pipe, illustrating stains running down the pipe where it appears leaking has been occurring.



- I-12 View of the pipe penetrating the north wall, illustrating minor corrosion staining on the welds and bolt heads at the flange.



- I-13 View of the tanks and piping just outside of the north wall, illustrating the apparent good condition of the piping.



- I-14 Same as Photo I-12, except on the other side of the piping. Note welded patches on the corner of the elbow.



- I-15 Same as Photo I-14, except just past the Victaulic coupling. Note welded patches in this location also.



- I-16 View of an elbow, illustrating staining where it appears leaking has been occurring.



I-17 Same as Photo I-16, except on the other side of the elbow.



I-18 View of the topside of the pipe, illustrating a welded patch that appears to have been leaking.



I-19 Same as Photo I-18, except rust scale has been scraped away to examine the substrate.



I-20 Same as Photo I-19, except a closer view of the area that was scraped. Note apparent pinhole where scraping was accomplished.



I-21 Same as Photos I-18 through I-20, except at a different patch. Note dark spot above the patch where it appears leaking has occurred.



I-22 Close-up view of the pipe, illustrating a dark wet spot at the junction of two welds where it appears leaking has occurred or is beginning to occur.



- I-23 Same as Photo I-22, except after the wet spot was wiped away and corrosion scraped. No obvious pinhole was seen.



- I-24 Close-up view of the pipe at a weld patch, illustrating dark corrosion along the top weld on the patch.



- I-25 Same as Photo I-24, except at a different patch. Note dark area at the bottom of the weld patch.



I-26 View of 1st stage air piping, illustrating the overall good condition of the piping.



I-27 Same as Photo I-26, except in a different location.



I-28 View of 2nd stage air piping, illustrating very minor corrosion on the piping and along random welds.



I-29 Same as Photo I-28, except in a different location.



I-30 Same as Photos I-28 and I-29, except in a different location. Note good condition of the piping.



I-31 View of backpulse piping, illustrating minor corrosion and staining on the stainless-steel piping and on the white Victaulic couplings.



I-32 View of 2nd stage permeate piping, illustrating random minor corrosion on the piping.



I-33 Same as Photo I-32, except in a different location.



I-34 Same as Photos I-32 and I-33, except at the north wall.



Appendix D: Coating Systems

SERIES 215ML/22

MAT-REINFORCED LINING SYSTEM

FOR MEMBRANE FILTER TANKS

With the advancement of membrane filter technology, many treatment facilities are moving to ultrafiltration or microfiltration systems, whether for raw water or for wastewater in the form of an ultrafiltration membrane or membrane bioreactor (MBR). These systems provide a high quality effluent with a much smaller plant footprint. Immersion-type filters which require tanks or basins are a popular choice due to their increased efficiency and ease of maintenance. However, the processes involved with operating and maintaining the filters, whether in water or wastewater treatment, can subject concrete tank linings to a unique set of demands. Tnemec, a leader in protective coatings for water and wastewater treatment, developed the Series 215ML/22 Mat-Reinforced Lining System to protect concrete from aggressive cleaning methods, impact, and thermal shock from elevated backwash/backflush temperatures, while ensuring safe contact with drinking water.

THE SYSTEM

Every coating in Tnemec's Series 215ML/22 Mat-Reinforced Chemical-Resistant Lining System is NSF/ANSI Standard 61-certified—from the primer, to the fiberglass-reinforced intermediate coat, to the topcoat. The lining consists of Series N140F Pota-Pox Plus, a penetrating concrete primer, Series 215 Epoxy Surfacer, a 100% solids epoxy bedding coat, with an embedded $\frac{3}{4}$ ounce fiberglass mat, and a topcoat of Series 22 Epoxoline. This high performance lining system was developed specifically to provide long-lasting performance in both membrane filtration and MBR process tanks.

THE BENEFITS

- » *Penetrating concrete primer*
- » *100% solids epoxy basecoat and topcoat*
- » *Fiberglass reinforcement*
- » *Chemical and permeation resistant*
- » *Resistant to impact and abrasion from cassette movement*
- » *Resistant to thermal shock from elevated temperature backwashing or backflushing*
- » *100% NSF/ANSI Standard 61 certified*




Primer
Series N140F Pota-Pox® Plus
3-6 Mils DFT

Bedding Coat
Series 215 Surfacing Epoxy
60-80 Mils DFT

Reinforcement
Series 211-215 Fiberglass Mat

Saturant Coat
Series 22 Epoxoline

Topcoat
Series 22 Epoxoline
20-30 Mils DFT



ULTRA-TREAD® S SERIES 245

PRODUCT PROFILE

GENERIC DESCRIPTION Polyurethane Modified Concrete

COMMON USAGE

Ultra-Tread S is a low odor, slurry applied, flowable mortar floor topping designed for monolithic applications in abusive service areas. It provides superior performance to other flooring systems such as acid brick, quarry tile and most polymer flooring systems. Designed for use in food and beverage facilities, pharmaceutical and processing areas, commercial and restaurant kitchens or anywhere a durable floor topping is required. Provides excellent chemical resistance and withstands thermal shock due to hot liquids and aggressive cleaning procedures. Areas may be quickly returned to service within hours of installation, depending on temperature and humidity. Ultra-Tread S is a self-priming base coat that can be applied to 10 day old concrete. It can withstand moisture vapor transmission up to 20 lbs (per ASTM F 1869) and relative humidity up to 99% (per ASTM F 2170).

COLORS

Gray and Red. **Note:** Additional lead times may apply when ordering Beige, Black, Blue, Green, Off White and Yellow. Aromatic urethanes chalk and yellow with age, extended exposure to UV and artificial lighting. **Note:** Colored quartz or decorative flake may be broadcast to refusal into the system, creating a multi-colored or tweed look. A variance in color may be noticeable and require a second broadcast layer of colored quartz or decorative flake. A sample is recommended for color selection.

FINISH

Matte

SPECIAL QUALIFICATIONS

Formulated with antimicrobial properties. Does not support bacteria or fungal growth. Contact your Tnemec representative for specific test results.

Series 245 was tested in accordance with, and passed, the California Dept. of Public Health (CDPH) Standard Method v1.2 and meets the requirements of LEED v4.1 Low-Emitting Materials, Collaborative for High Performance Schools-Paints & Coatings, Living Building Challenge Materials Petal 10, and WELL Building Standard v2 X06 VOC Restrictions.

COATING SYSTEM

SURFACER/FILLER/PATCHER

Series 242 (extended with aggregate) or Series 243, 244. Patching should be allowed to cure a minimum of six hours prior to placement of the Series 245 to avoid blistering or doming of the Series 245. Series 215, or 201 or 208 mixed with fumed silica, may be used for small patches or crack repairs. Certain high-early strength, cementitious repair mortars are also acceptable. Contact Tnemec for further qualifications.

PRIMERS

Self-priming

INTERMEDIATE

Series 222, 233, 237, 238, 239, 252SC, 256, 257. **Note:** Series 245 must be broadcast to refusal with aggregate, colored quartz or decorative flake if topcoating. Broadcast aggregate or colored quartz at an approximate rate of 0.5 lb per sq ft or 4 to 5 sq ft per pound and decorative flake at an approximate rate of 0.25 lb per sq ft. The Series 245 base coat will account for approximately 1/8"-3/16" of the desired system thickness.

TOPCOATS

Series 222, 233, 237, 238, 239, 246, 247, 248, 252SC, 256, 257, 280, 280FC, 281, 282, 284, 285, 286, 290, 291, 294, 295, 296, 297. **Note:** These topcoats may only be used when recommended aggregate has been broadcast to refusal into the wet Series 245 or the cured surface of the Series 245 has been cleaned and thoroughly abraded by grinding prior to topcoating. **Note:** If Series 247 (tinted), 248 (tinted), 290, 291 or 297 is selected for the finish coat over a broadcast system, a grout coat of Series 222, 233, 237 or 238 (tinted), 256 (tinted), 257 (tinted), 280, 281 or 284 is required. If Series 247 (clear), 248 (clear), 285, 294, 295 or 296 is selected for the finish coat over a broadcast system, a grout coat of 237 or 238 (clear), 256 (clear), 257 (clear) or 284 is required.

SURFACE PREPARATION

CONCRETE

Prepare surfaces by method suitable for exposure and service.

Allow new poured-in-place concrete to cure a minimum of 10 days at 75°F (24°C). Verify concrete dryness in accordance with ASTM F 1869 "Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride" (moisture vapor transmission should not exceed 20 pounds per 1,000 square feet in a 24 hour period), F 2170 "Standard Test Method for Determining Relative Humidity in Concrete using in situ Probes" (relative humidity should not exceed 99%), or D 4263 "Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method" (no moisture present). **Note:** The testing listed above cannot guarantee avoidance of future moisture related problems particularly with existing concrete slabs. This is especially true if the use of an under slab moisture vapor barrier cannot be confirmed or concrete contamination from oils, chemical spills, unreacted silicates, chlorides or Alkali Silica Reaction (ASR) is suspected.

Prepare concrete surfaces in accordance with NACE No. 6/SSPC-SP13 Joint Surface Preparation Standards and ICRI Technical Guidelines. Abrasive blast, shot-blast, water jet or mechanically abrade concrete surfaces to remove laitance, curing compounds, hardeners, sealers and other contaminants and to provide a minimum ICRI-CSP 5 or greater surface profile. Large cracks, voids and other surface imperfections should be filled with a recommended filler or surfacer.

ALL SURFACES

Must be clean, dry and free of oil, grease and other contaminants. Do not apply over existing coatings. **Note:** Substrate conditions which can adversely affect the adhesion of Series 245 Ultra-Tread S include: concrete that is structurally unsound, wet, damp, contaminated, or inadequately profiled at the time of application, absent or inadequate under slab moisture vapor barrier, hydrostatic pressure, Alkali Silica Reaction (ASR), and migration of oils, chemicals, and other contaminants.

ULTRA-TREAD® S | SERIES 245

TECHNICAL DATA

VOLUME SOLIDS 100% (mixed)

RECOMMENDED DFT 3/16" to 1/4" (5 mm to 6 mm). Series 245 can be applied as a stand alone mortar (neat) at 3/16"-1/4" (5 mm - 6 mm). Broadcasting with aggregate to refusal at 3/16" (5 mm) neat will yield a total thickness of 1/4" (6 mm), at 1/4" (6 mm) neat will yield a total thickness of 5/16" (8 mm). **Important:** Series 245 should not exceed 1/2" (13 mm) thickness when applied neat. Refer to coverage rates table for more information. **Note:** Exceeding the recommended coating thickness may result in blistering of the product. Avoid excessive coating thickness by thoroughly filling voids, depressions and cracks with recommended filler or surfacer prior to Series 245 application.

CURING TIME

Temperature	Min. Recoat	Light Traffic	Place In Service †
75°F (24°C)	6 hours	8 hours	12 hours

† For full resistance to chemicals and steam cleaning, 24 hour cure is needed.

Curing time varies with surface temperature, air movement, humidity and film thickness. **Note:** For faster curing and low temperature applications, add No. 44-714 Ultra-Tread Accelerator, see separate product data sheet for cure information.

VOLATILE ORGANIC COMPOUNDS

Parts A & B: 0.16 lbs/gallon (19 grams/litre)
Parts A, B & C: 0.07 lbs/gallon (8 grams/litre)

THEORETICAL COVERAGE

23 sq ft per small kit at 1/4" 31 sq ft per small kit at 3/16"

NUMBER OF COMPONENTS

Three—Liquids: Part A & Part B, Aggregate: Part C

PACKAGING

	Part A (partially filled)	Part B	Part C (Aggregate)	Mixed Yield	Small Kit Equivalent
Extra Large Kit	1-tote	1-tote	300-42.5 lb. bags	1083.3 gallons (4100.7 L)	300
Medium Kit	1-5 gallon pail	1-5 gallon pail	5-42.5 lb. bags	17.9 gallons (67.8 L)	5
Small Kit	1-1 gallon jug	1-1 gallon jug	1-42.5 lb. bag	3.6 gallons (15.6 L)	1

Note: Empty measuring pails are available. Reference F100-H189-UT for the 2-gallon Part A pail and F100-H190-UT for the 2-gallon Part B pail. Empty measuring pails are only needed for breaking down Series 241, 242 and 245 part A & B components when mixing Medium and X-Large Kits. The measuring pails are not needed for Small Kits as the part A & B components are already prefilled at the correct fill amounts.

NET WEIGHT PER GALLON

16.28 ± 0.25 lbs (7.38 ± 0.11 kg) (mixed)

STORAGE TEMPERATURE

Minimum 35°F (2°C) Maximum 110°F (43°C)

Material should be stored at temperatures between 70°F and 90°F (21°C and 32°C) for at least 48 hours prior to use.

TEMPERATURE RESISTANCE

(Dry) Continuous 235°F (112°C). At thicknesses of ¼" or greater, resistant to aggressive chemical cleaning, thermal shock from steam or hot water, and occasional high temperature liquid spills or discharge at temperatures from -40°F (-40°C) to 250°F (121°C).

SHELF LIFE

Part A: 12 months Part B: 12 months Part C: 12 months

FLASH POINT - SETA

N/A

HEALTH & SAFETY

This product contains chemical ingredients which are considered hazardous. Read container label warning and Material Safety Data Sheet for important health and safety information prior to the use of this product.

Keep out of the reach of children.

APPLICATION

COVERAGE RATES

Before commencing, obtain and thoroughly read the *StrataShield Application Guide for Polyurethane Modified Concrete*.

Applied Neat	Broadcast To Refusal	Small Kit Coverage
3/16" (5 mm)	1/4" (6 mm)	31 sq ft (2.8 m²)
1/4" (6 mm)	5/16" (8 mm)	23 sq ft (2.1 m²)

Important: Series 245 should not exceed 1/2" (13 mm) thickness when applied neat. **Note:** Exceeding the recommended coating thickness may result in blistering of the product. Avoid excessive coating thickness by thoroughly filling voids, depressions and cracks with recommended filler or surfacer. Application below minimum or above maximum recommended thicknesses may adversely affect performance. Above rates are based on theoretical coverage. Actual coverage will vary based on condition of substrate.

ULTRA-TREAD® S | SERIES 245

MIXING

When mixing Small Kits use a variable speed 850-RPM drill and four-inch (4") dispersion blade, slowly mix the entire contents of both the A and B components for a minimum of one minute. Continue agitation and slowly add the Part C aggregate and mix until material is uniform and no dry aggregate is present. The entire mixing procedure should take approximately three minutes. **Note:** Part B is moisture sensitive. Do not open until ready to mix.

When mixing Medium and Extra-Large kits, mix 0.9117 gallons of Part A component with 0.7993 gallons of Part B component. **Note:** Empty mixing pails are available for measuring these kit sizes. Reference F100-H189-UT for the 2-gallon Part A pail and F100-H190-UT for Part B pail. Slowly mix the measured amount of both the part A and B components for a minimum of one minute. Continue agitation and slowly add one Part C aggregate and mix until material is uniform and no dry aggregate is present. The entire mixing procedure should take approximately three minutes. **Note:** Part B is moisture sensitive. Do not open until ready to mix.

The Medium Kits break down to equal five (5) Small Kits or units and the Extra-Large Kits break down to equal three hundred (300) Small Kits or units. Single batch mixes equal to one (1) Small Kit or unit are frequently mixed in five-gallon pails. Multiple batch mixes are frequently mixed in larger portable, Hippo style mixers and used for larger pours.

Accelerator: For accelerated cure on low temperature applications add Series 44-714 Ultra-Tread Accelerator to the Series 245 Part A prior to mixing. The proper amount of Series 44-714 is based upon ambient temperature; At 70°F (21°C) with 50% relative humidity 1 oz per small kit will result in a 9 hour maximum cure time, 2 oz per small kit will result in a 7.5 hour maximum cure time, 3 oz per small kit will result in a 6.5 hour maximum cure time. **Note:** Material will set up quickly if not applied immediately after mixing.

THINNING

DO NOT THIN.

POT LIFE

Without 44-714: 15 minutes at 75°F (24°C)
Higher material temperatures will significantly reduce the pot life and working time.

With 44-714 when using maximum amount (3 oz): 15 minutes at 60°F (16°C) 10 minutes at 70°F (21°C)

APPLICATION

This unique self-leveling mortar system is typically applied by trowel, screed rake or cam rake, backrolled with a loop roller and broadcast to refusal with 30/50 mesh aggregate, colored quartz or decorative flake. **Note:** Series 245 can be applied as a stand-alone mortar. If topcoating, the mortar, while still wet, **must** be broadcast to refusal with aggregate, color quartz or decorative flake typically completed within 10 to 15 minutes of application. Color quartz and/or decorative flake systems will require an additional broadcast layer using Series 222, 224, 237, 238, 256 or 257 clear to obtain a uniform appearance and texture before applying the desired clear finish coats. This will typically result in a total system thickness of 1/4"-5/16". **Note:** Series 245 **must** be broadcast to refusal with aggregate, colored quartz or decorative flake. Broadcast 30/50 aggregate or colored quartz at a rate of 0.5 lbs per sq ft and decorative flake at a rate of 0.25 lbs or 4-5 sq ft per lb.

APPLICATION EQUIPMENT

Apply: Trowel, screed rake or cam rake.
Finish: Porcupine roller or loop roller.

Note: For detailed instructions, refer to the StrataShield Application Guide for Polyurethane Modified Concrete.

SURFACE TEMPERATURE

Minimum of 40°F (4°C), optimum 65°F to 80°F (18°C to 27°C), maximum of 85°F (29°C). The substrate temperature should be at least 5°F (3°C) above the dew point. Coating will not cure below minimum surface temperature.

MATERIAL TEMPERATURE

For optimum application, handling and performance, the material temperature during application should be between 60°F and 80°F (16°C and 27°C). Temperature will affect the workability. Cool temperatures increase viscosity and decrease workability. Warm temperatures will decrease viscosity and significantly shorten pot life and working time.

AMBIENT HUMIDITY

Humidity must be below 85%.

CLEANUP

Flush and clean all equipment immediately after use with xylene or MEK.

WARRANTY & LIMITATION OF SELLER'S LIABILITY: Tnemec Company, Inc. warrants only that its coatings represented herein meet the formulation standards of Tnemec Company, Inc. THE WARRANTY DESCRIBED IN THE ABOVE PARAGRAPH SHALL BE IN LIEU OF ANY OTHER WARRANTY, EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. THERE ARE NO WARRANTIES THAT EXTEND BEYOND THE DESCRIPTION ON THE FACE HEREOF. The buyer's sole and exclusive remedy against Tnemec Company, Inc. shall be for replacement of the product in the event a defective condition of the product should be found to exist and the exclusive remedy shall not have failed its essential purpose as long as Tnemec is willing to provide comparable replacement product to the buyer. NO OTHER REMEDY (INCLUDING, BUT NOT LIMITED TO, INCIDENTAL OR CONSEQUENTIAL DAMAGES FOR LOST PROFITS, LOST SALES, INJURY TO PERSON OR PROPERTY, ENVIRONMENTAL INJURIES OR ANY OTHER INCIDENTAL OR CONSEQUENTIAL LOSS) SHALL BE AVAILABLE TO THE BUYER. Technical and application information herein is provided for the purpose of establishing a general profile of the coating and proper coating application procedures. Test performance results were obtained in a controlled environment and Tnemec Company makes no claim that these tests or any other tests, accurately represent all environments. As application, environmental and design factors can vary significantly, due care should be exercised in the selection and use of the coating.

RECOMMENDED USE DEFINITIONS

IMMERSION SERVICE (Most Severe) – IS

Suitable for continuous contact with chemical exposure up to specified temperature.

CARGO/TEMPORARY IMMERSION – CI

Suitable for 60 day continuous contact with chemical exposure up to specified temperature. The coating will show no effects, except slight softening or discoloration, possibly permanent, after 60 days or less continuous immersion. When used in transport or hauling conditions, the vessel must be completely drained to prevent puddling that would constitute continuous immersion.

SECONDARY CONTAINMENT – SC

Suitable for continuous contact up to 72 hours with chemical exposure or vapors using a mat-reinforced coating system or polymer concrete. The coating will show no effects, except slight softening or discoloration, after 72 hours exposure to chemical or vapors.

FREQUENT CONTACT – FC

Suitable for frequent splash or up to 72 hours exposure to concentrated vapors. The coating will show no effects, except slight softening or discoloration, possibly permanent, after eight hours continuous immersion in the liquid chemical or 72 hours exposure to the vapor.

OCCASIONAL CONTACT (Least Severe) – OC

Suitable for occasional splash and spillage or occasional exposure to concentrated vapors. The coating will show no effects, except slight softening or discoloration, following short exposure to splash or spillage which evaporates, is hosed off, or dried overnight, or 24 hours exposure to vapor.

NOT EVALUATED – NE

This chemical has not been evaluated for the listed chemical. Please contact Tnemec Technical Services for more information.

NOT RECOMMENDED – NR

This product is not recommended for the listed exposure.

IMPORTANT NOTES

The term “chemicals” is used broadly in this guide and can refer to various constituents including, but not limited to, acids, fatty acids, food and beverage materials, finished and unrefined hydrocarbons, as well as individual chemicals and chemical blends. Unless otherwise referenced, the concentrations listed are aqueous solutions of the chemicals.

Temperature can have a significant effect on a coating’s chemical resistance. Prior to coating selection, due care should be taken to determine the service temperature of stored chemicals, elevated temperature caused by natural environmental conditions (i.e. radiant heat from sun, weather), and temperature fluctuations during service (i.e. loading of cargo, service cycling).

Chemical mixtures and alternating chemical storage can aggressively degrade a coating or lining system. Prior to coating selection and application, the expected chemical exposures and sequence of chemical storage should be discussed with Tnemec Technical Service to ensure the proper coating is selected.

Proper surface preparation is always important to ensure optimum coating performance, but it is even more so for coatings that will undergo chemical exposure. Carefully read product data sheets along with related application guides to determine the required level of surface preparation and surface profile.

Structural designs of tanks, structures, and containment areas can greatly affect coating performance. Sharp angles, channels, edges, corners, pits, voids, defects, rough welds, and other similar conditions present areas that are either difficult to coat or achieve the required film thickness. Avoid skip welds in favor of continuous welds. A stripe coat on these areas, prior to full coating application, can help achieve needed film thickness and prevent premature coating failure. (Reference NACE SP0178-2007 for more information.)

The length of a coating system’s service life depends on surface cleanliness and preparation prior to application, proper application procedures, exposure conditions, physical abuse, cleaning techniques, and frequency of inspection, maintenance, and repair. No coating system has an unlimited service life. Regular inspection of the coating system can prolong service life by identifying areas in need of repair. Additionally, regular inspections can determine when the coating system is nearing its end of service and should be completely replaced.

Chemical resistance information is provided for the purpose of establishing a general profile of the coating and was obtained through laboratory testing, field experience, and industry knowledge. Test results were produced in a controlled environment and Tnemec makes no claim that any tests, or published chemical resistance information, accurately represent all environments or correlate to actual field performance. Application, environmental and design factors, chemical temperatures, chemical mixtures, sequence of storage, conditions of service, and cleaning procedures can significantly impact coating performance, so due care must be exercised in the selection and use of the coating. Tnemec disclaims responsibility for product use outside its published information. Contact Tnemec Technical Service to review full project details before the coating or coating system is selected and applied.

IMPORTANT: Definitions for the terms and acronyms used in this guide to describe the recommended exposures, along with other important information, can be found on the cover page of this guide or by contacting Tnemec Technical Service. Coatings should not be applied in a chemical exposure environment until the user has thoroughly read and understood the product information and full project details have been discussed with Tnemec Technical Service.

ULTRA-TREAD® S | SERIES 242

¹ Product is NOT suitable for direct or indirect food contact. Intended Use and temperature information relates to product's performance capabilities only.

² Product is suitable for direct or indirect food contact. Reference the product data sheet for more information.

Chemical	Intended Use (Maximum Temperature Listed)				
	Occasional Contact	Frequent Contact	Secondary Containment	Cargo Immersion	Immersion Service
1, 1, 1-Trichloroethane (Trichloroethane)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Acetaldehyde	100°F (38°C)	100°F (38°C)	NR	NR	NR
Acetic Acid					
5%	100°F (38°C)	NR	NR	NR	NR
10%	NR	NR	NR	NR	NR
30%	NR	NR	NR	NR	NR
Acetic Acid, Glacial	NR	NR	NR	NR	NR
Acetic Anhydride	100°F (38°C)	NR	NR	NR	NR
Acetone	NR	NR	NR	NR	NR
Adipic Acid					
25%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Allyl Alcohol	100°F (38°C)	100°F (38°C)	NR	NR	NR
Aluminum Bromide	100°F (38°C)	100°F (38°C)	NR	NR	NR
Aluminum Chloride					
50%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Aluminum Nitrate					
50% ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Aluminum Sulfate (Alum)					
49%	100°F (38°C)	NR	NR	NR	NR
Ammonium Chloride					
50%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ammonium Hydroxide (Aqua Ammonia)					
30%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ammonium Nitrate					
10% ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
20% ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR

IMPORTANT: Definitions for the terms and acronyms used in this guide to describe the recommended exposures, along with other important information, can be found on the cover page of this guide or by contacting Tnemec Technical Service. Coatings should not be applied in a chemical exposure environment until the user has thoroughly read and understood the product information and full project details have been discussed with Tnemec Technical Service.

ULTRA-TREAD® S | SERIES 242

¹ Product is NOT suitable for direct or indirect food contact. Intended Use and temperature information relates to product's performance capabilities only.

² Product is suitable for direct or indirect food contact. Reference the product data sheet for more information.

Chemical	Intended Use (Maximum Temperature Listed)				
	Occasional Contact	Frequent Contact	Secondary Containment	Cargo Immersion	Immersion Service
38% ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
50% ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
65% ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
83% ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ammonium Persulfate					
10%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ammonium Sulfate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ammonium Sulfide	100°F (38°C)	100°F (38°C)	NR	NR	NR
Amyl Acetate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Amyl Alcohol	100°F (38°C)	100°F (38°C)	NR	NR	NR
Aniline Hydrochloride	100°F (38°C)	100°F (38°C)	NR	NR	NR
Aqua Regia	100°F (38°C)	NR	NR	NR	NR
Barium Sulfate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Barium Sulfide	100°F (38°C)	100°F (38°C)	NR	NR	NR
Beer ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Benzaldehyde	100°F (38°C)	100°F (38°C)	NR	NR	NR
Benzene	100°F (38°C)	NR	NR	NR	NR
Benzene Sulfonic Acid	100°F (38°C)	100°F (38°C)	NR	NR	NR
Bromine Gas (Dry)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Bromine Water, Sat'd	100°F (38°C)	100°F (38°C)	NR	NR	NR
Butyl Acrylate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Butyric Acid	100°F (38°C)	100°F (38°C)	NR	NR	NR
Cadmium Chloride	100°F (38°C)	100°F (38°C)	NR	NR	NR
Calcium Bisulfite	100°F (38°C)	100°F (38°C)	NR	NR	NR
Calcium Bromide	100°F (38°C)	100°F (38°C)	NR	NR	NR
Calcium Chloride	100°F (38°C)	100°F (38°C)	NR	NR	NR
Calcium Nitrate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Calcium Nitrite	100°F (38°C)	100°F (38°C)	NR	NR	NR

IMPORTANT: Definitions for the terms and acronyms used in this guide to describe the recommended exposures, along with other important information, can be found on the cover page of this guide or by contacting Tnemec Technical Service. Coatings should not be applied in a chemical exposure environment until the user has thoroughly read and understood the product information and full project details have been discussed with Tnemec Technical Service.

ULTRA-TREAD® S | SERIES 242

¹ Product is NOT suitable for direct or indirect food contact. Intended Use and temperature information relates to product's performance capabilities only.

² Product is suitable for direct or indirect food contact. Reference the product data sheet for more information.

Chemical	Intended Use (Maximum Temperature Listed)				
	Occasional Contact	Frequent Contact	Secondary Containment	Cargo Immersion	Immersion Service
Calcium Sulfate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Carbon Dioxide (gas)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Carbon Tetrachloride	100°F (38°C)	100°F (38°C)	NR	NR	NR
Castor Oil ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Chloroacetic Acid					
20%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Chlorobenzene	100°F (38°C)	100°F (38°C)	NR	NR	NR
Chloroform	100°F (38°C)	NR	NR	NR	NR
Chromic Acid					
10%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Citric Acid	100°F (38°C)	100°F (38°C)	NR	NR	NR
Corn Oil ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Cottonseed Oil ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Crude Oil (Sour)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Cyclohexane	100°F (38°C)	100°F (38°C)	NR	NR	NR
Cyclohexanone	100°F (38°C)	100°F (38°C)	NR	NR	NR
Dichloroacetic Acid					
20%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Diesel Fuel (Fuel Oil, Diesel Oil)	80°F (27°C)	80°F (27°C)	NR	NR	NR
Dimethyl Formamide	NR	NR	NR	NR	NR
Dimethylaniline	100°F (38°C)	100°F (38°C)	NR	NR	NR
Dinitrobenzene	100°F (38°C)	NR	NR	NR	NR
Ethanol (Denatured Alcohol, Ethyl Alcohol)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ethyl Acetate	100°F (38°C)	NR	NR	NR	NR
Ethyl Chloride	100°F (38°C)	NR	NR	NR	NR
Ethyl Sulfate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ethylamine					

IMPORTANT: Definitions for the terms and acronyms used in this guide to describe the recommended exposures, along with other important information, can be found on the cover page of this guide or by contacting Tnemec Technical Service. Coatings should not be applied in a chemical exposure environment until the user has thoroughly read and understood the product information and full project details have been discussed with Tnemec Technical Service.

ULTRA-TREAD® S | SERIES 242

¹ Product is NOT suitable for direct or indirect food contact. Intended Use and temperature information relates to product's performance capabilities only.

² Product is suitable for direct or indirect food contact. Reference the product data sheet for more information.

Chemical	Intended Use (Maximum Temperature Listed)				
	Occasional Contact	Frequent Contact	Secondary Containment	Cargo Immersion	Immersion Service
20%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ethylene Dichloride	100°F (38°C)	NR	NR	NR	NR
Ethylene Glycol	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ferric Chloride	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ferric Nitrate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Ferric Sulfate					
20%	100°F (38°C)	100°F (38°C)	NR	NR	NR
60%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Fluorosilicic Acid (Hydrofluorosilicic Acid)					
10%	100°F (38°C)	NR	NR	NR	NR
25%	NR	NR	NR	NR	NR
Formaldehyde					
37%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Furfuryl Alcohol	100°F (38°C)	100°F (38°C)	NR	NR	NR
Gasoline (Unleaded)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Glycerin	100°F (38°C)	100°F (38°C)	NR	NR	NR
Glycolic Acid	100°F (38°C)	100°F (38°C)	NR	NR	NR
Gold Plating (Cyanide)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Gold Plating Solution	100°F (38°C)	100°F (38°C)	NR	NR	NR
Grape Juice ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Heptane	100°F (38°C)	100°F (38°C)	NR	NR	NR
Hexane	100°F (38°C)	100°F (38°C)	NR	NR	NR
Hydrochloric Acid					
37%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Hydrofluoric Acid					
10%	NR	NR	NR	NR	NR
20%	NR	NR	NR	NR	NR

IMPORTANT: Definitions for the terms and acronyms used in this guide to describe the recommended exposures, along with other important information, can be found on the cover page of this guide or by contacting Tnemec Technical Service. Coatings should not be applied in a chemical exposure environment until the user has thoroughly read and understood the product information and full project details have been discussed with Tnemec Technical Service.

ULTRA-TREAD® S | SERIES 242

¹ Product is NOT suitable for direct or indirect food contact. Intended Use and temperature information relates to product's performance capabilities only.

² Product is suitable for direct or indirect food contact. Reference the product data sheet for more information.

Chemical	Intended Use (Maximum Temperature Listed)				
	Occasional Contact	Frequent Contact	Secondary Containment	Cargo Immersion	Immersion Service
Hydrogen Peroxide					
30%	100°F (38°C)	NR	NR	NR	NR
Hypochlorous Acid	100°F (38°C)	100°F (38°C)	NR	NR	NR
Isopropyl Alcohol (Isopropanol)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Isopropyl Ether	100°F (38°C)	100°F (38°C)	NR	NR	NR
Jet A Fuel	100°F (38°C)	100°F (38°C)	NR	NR	NR
Kerosene	100°F (38°C)	100°F (38°C)	NR	NR	NR
Lactic Acid					
85%	NR	NR	NR	NR	NR
Lard ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Lead Acetate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Linseed Oil ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Maleic Acid					
50%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Malic Acid	100°F (38°C)	NR	NR	NR	NR
Methyl Acetate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Methyl Chloride	100°F (38°C)	NR	NR	NR	NR
Methyl Ethyl Ketone	100°F (38°C)	NR	NR	NR	NR
Methyl Isobutyl Ketone	100°F (38°C)	NR	NR	NR	NR
Methylene Chloride	NR	NR	NR	NR	NR
Milk ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Mineral Oil	100°F (38°C)	100°F (38°C)	NR	NR	NR
Mineral Spirits	100°F (38°C)	100°F (38°C)	NR	NR	NR
Molasses ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Naphthalene	100°F (38°C)	100°F (38°C)	NR	NR	NR
Nitric Acid					
5%	100°F (38°C)	100°F (38°C)	NR	NR	NR

IMPORTANT: Definitions for the terms and acronyms used in this guide to describe the recommended exposures, along with other important information, can be found on the cover page of this guide or by contacting Tnemec Technical Service. Coatings should not be applied in a chemical exposure environment until the user has thoroughly read and understood the product information and full project details have been discussed with Tnemec Technical Service.

ULTRA-TREAD® S | SERIES 242

¹ Product is NOT suitable for direct or indirect food contact. Intended Use and temperature information relates to product's performance capabilities only.

² Product is suitable for direct or indirect food contact. Reference the product data sheet for more information.

Chemical	Intended Use (Maximum Temperature Listed)				
	Occasional Contact	Frequent Contact	Secondary Containment	Cargo Immersion	Immersion Service
10%	100°F (38°C)	100°F (38°C)	NR	NR	NR
25%	100°F (38°C)	NR	NR	NR	NR
70%	NR	NR	NR	NR	NR
Nitrobenzene	100°F (38°C)	NR	NR	NR	NR
Perchloric Acid					
30%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Perchloroethylene (Tetrachloroethylene)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Phosphoric Acid					
43%	100°F (38°C)	100°F (38°C)	NR	NR	NR
85%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Picric Acid					
10%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Bicarbonate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Bromide	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Carbonate					
25%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Chlorate	NR	NR	NR	NR	NR
Potassium Chloride	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Cyanide	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Fluoride	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Hydroxide					
50%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Nitrate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Permanganate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Persulfate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Potassium Sulfate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Propionic Acid					

IMPORTANT: Definitions for the terms and acronyms used in this guide to describe the recommended exposures, along with other important information, can be found on the cover page of this guide or by contacting Tnemec Technical Service. Coatings should not be applied in a chemical exposure environment until the user has thoroughly read and understood the product information and full project details have been discussed with Tnemec Technical Service.

ULTRA-TREAD® S | SERIES 242

¹ Product is NOT suitable for direct or indirect food contact. Intended Use and temperature information relates to product's performance capabilities only.

² Product is suitable for direct or indirect food contact. Reference the product data sheet for more information.

Chemical	Intended Use (Maximum Temperature Listed)				
	Occasional Contact	Frequent Contact	Secondary Containment	Cargo Immersion	Immersion Service
50%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Propylene Glycol	100°F (38°C)	100°F (38°C)	NR	NR	NR
Pyridine					
20%	100°F (38°C)	100°F (38°C)	NR	NR	NR
100%	100°F (38°C)	NR	NR	NR	NR
Salicylic Acid	100°F (38°C)	100°F (38°C)	NR	NR	NR
Silver Nitrate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Skydrol	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Acetate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Bicarbonate ¹ (Baking Soda)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Bisulfate					
30%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Bisulfite					
38%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Borate (Borax)	NR	NR	NR	NR	NR
Sodium Chloride (sat'd) (Brine, Water (Sea), Salt Brine)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Dichromate (all)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Fluoride	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Hydroxide (Caustic Soda)					
50%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Oxalate	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Peroxide	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Sulfide (all)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sodium Sulfite	100°F (38°C)	100°F (38°C)	NR	NR	NR
Stannic Chloride (all)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Stearic Acid (conc)	100°F (38°C)	100°F (38°C)	NR	NR	NR

IMPORTANT: Definitions for the terms and acronyms used in this guide to describe the recommended exposures, along with other important information, can be found on the cover page of this guide or by contacting Tnemec Technical Service. Coatings should not be applied in a chemical exposure environment until the user has thoroughly read and understood the product information and full project details have been discussed with Tnemec Technical Service.

ULTRA-TREAD® S | SERIES 242

¹ Product is NOT suitable for direct or indirect food contact. Intended Use and temperature information relates to product's performance capabilities only.

² Product is suitable for direct or indirect food contact. Reference the product data sheet for more information.

Chemical	Intended Use (Maximum Temperature Listed)				
	Occasional Contact	Frequent Contact	Secondary Containment	Cargo Immersion	Immersion Service
Stoddard Solvent	100°F (38°C)	100°F (38°C)	NR	NR	NR
Styrene	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sugars ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sulfur Trioxide (wet)	100°F (38°C)	100°F (38°C)	NR	NR	NR
Sulfuric Acid (Sulphuric Acid)					
30%	100°F (38°C)	100°F (38°C)	NR	NR	NR
50%	100°F (38°C)	NR	NR	NR	NR
70%	NR	NR	NR	NR	NR
98%	NR	NR	NR	NR	NR
Tartaric Acid ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Tetrachloroethane	100°F (38°C)	100°F (38°C)	NR	NR	NR
Toluenesulfonic Acid	100°F (38°C)	100°F (38°C)	NR	NR	NR
Trichloroacetic Acid					
20%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Trichlorobenzene	100°F (38°C)	100°F (38°C)	NR	NR	NR
Trichloroethylene	100°F (38°C)	100°F (38°C)	NR	NR	NR
Triethylenetetramine	100°F (38°C)	NR	NR	NR	NR
Trisodium Phosphate (Sodium Phosphate (Tribasic))					
20%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Turpentine	100°F (38°C)	100°F (38°C)	NR	NR	NR
Urea					
50%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Urea Ammonium Nitrate					
32%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Vegetable Oil ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Vinegar ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Water (deionized, non-potable) ¹ (Water (Demineralized, Non-potable))	100°F (38°C)	100°F (38°C)	NR	NR	NR

ULTRA-TREAD® S | SERIES 242

¹ Product is NOT suitable for direct or indirect food contact. Intended Use and temperature information relates to product’s performance capabilities only.

² Product is suitable for direct or indirect food contact. Reference the product data sheet for more information.

	Intended Use (Maximum Temperature Listed)				
Chemical	Occasional Contact	Frequent Contact	Secondary Containment	Cargo Immersion	Immersion Service

IMPORTANT: Definitions for the terms and acronyms used in this guide to describe the recommended exposures, along with other important information, can be found on the cover page of this guide or by contacting Tnemec Technical Service. Coatings should not be applied in a chemical exposure environment until the user has thoroughly read and understood the product information and full project details have been discussed with Tnemec Technical Service.

ULTRA-TREAD® S | SERIES 242

¹ Product is NOT suitable for direct or indirect food contact. Intended Use and temperature information relates to product's performance capabilities only.

² Product is suitable for direct or indirect food contact. Reference the product data sheet for more information.

Chemical	Intended Use (Maximum Temperature Listed)				
	Occasional Contact	Frequent Contact	Secondary Containment	Cargo Immersion	Immersion Service
Water (distilled, non-potable) ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Wine (alcohol by volume)					
10% ¹	100°F (38°C)	100°F (38°C)	NR	NR	NR
Xylene	100°F (38°C)	100°F (38°C)	NR	NR	NR
Zinc Chloride					
40%	100°F (38°C)	100°F (38°C)	NR	NR	NR
Zinc Sulfate	100°F (38°C)	100°F (38°C)	NR	NR	NR

IMPORTANT: Definitions for the terms and acronyms used in this guide to describe the recommended exposures, along with other important information, can be found on the cover page of this guide or by contacting Tnemec Technical Service. Coatings should not be applied in a chemical exposure environment until the user has thoroughly read and understood the product information and full project details have been discussed with Tnemec Technical Service.



TNEME-GLAZE SERIES 280

PRODUCT PROFILE

GENERIC DESCRIPTION Modified Polyamine Epoxy

COMMON USAGE A glaze-like corrosion resistant coating for walls, ceilings, floors and other surfaces; resistant to frequent pressurized hot water and detergent cleaning. Used as a topcoat/sealer for heavy duty wall and floor systems or in a stand-alone high-performance function. Excellent chemical, stain- and abrasion-resistance for a variety of substrates.

COLORS Available in the 16 standard StrataShield colors. Special colors available, please contact your Tnemec representative.
Note: Epoxies chalk and yellow with age, extended exposure to UV and artificial lighting. Caution should be taken when selecting white and light pastel colors. Lack of ventilation, incomplete mixing, miscatalyzation or the use of heaters that emit carbon dioxide and carbon monoxide during application and initial stages of curing may cause amine blush, possibly affecting adhesion of subsequent topcoats.

FINISH Gloss. (Roller application provides an orange peel finish.)

SPECIAL QUALIFICATIONS Series 280 meets the requirements of LEED-Low-Emitting Materials, Collaborative for High Performance Schools-Paints & Coatings, WELL Building Standard-VOC Restrictions, and Living Building Challenge-Healthy Interior Performance. Contact your Tnemec representative for more information.

COATING SYSTEM

SURFACER/FILLER/PATCHER Series 130, 215, 218, 1254. **Note:** A repair kit of 201, 208 or 233 mixed with fumed silica, is available for small patching/surfacing repairs. For more extensive repairs and additional information, contact your Tnemec representative or Tnemec Technical Services.

PRIMERS **Concrete:** Self-priming or Series 27WB, 201, 205, 208, 233, 237, 238, 241.
CMU: Self-priming over filled CMU

Wall board, Wood & Drywall: Self-priming or Series 151, 201, 233. **Note:** For taping joints on wall board or drywall in areas that will be frequently wet, subject to chemical cleaning, thermal shock, impact, and VHP (or similar) cleaning, use Sheetrock brand Durabond 90. For taping joints on wood or cement board, use Series 273 Part D fiberglass tape and Series 215 as taping compound. Reference Technical Bulletin 21-118.

INTERMEDIATE Series 206, 210, 233, 237, 237SC, 238, 241, 242, 245, 270, 273, 280

TOPCOATS Series 73, 247, 248, 280, 290, 291, 297, 1074, 1075, 1080, 1081

SURFACE PREPARATION

Prepare surfaces by method suitable for exposure and service. Refer to the appropriate primer data sheet for specific recommendations.

HORIZONTAL CONCRETE Allow new poured-in-place concrete to cure a minimum of 28 days at 75°F (24°C). Verify concrete dryness in accordance with ASTM F 1869 "Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride" (moisture vapor transmission should not exceed three pounds per 1,000 square feet in a 24 hour period), F 2170 "Standard Test Method for Determining Relative Humidity in Concrete using in situ Probes" (relative humidity should not exceed 80%), or D 4263 "Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method" (no moisture present). **Note:** The testing listed above cannot guarantee avoidance of future moisture related problems particularly with existing concrete slabs. This is especially true if the use of an under slab moisture vapor barrier cannot be confirmed or concrete contamination from oils, chemical spills, unreacted silicates, chlorides or Alkali Silica Reaction (ASR) is suspected.

Prepare concrete surfaces in accordance with NACE No. 6/SSPC-SP13 Joint Surface Preparation Standards and ICRI Technical Guidelines. Abrasive blast, shot-blast, water jet or mechanically abrade concrete surfaces to remove laitance, curing compounds, hardeners, sealers and other contaminants and to provide a minimum ICRI-CSP 3 or greater surface profile. Large cracks, voids and other surface imperfections should be filled with a recommended filler or surfer. **Note:** For moisture content exceeding 3 lbs per 1,000 sq ft or relative humidity in excess of 80%, Series 208 or 241 may be substituted for the primer. Refer to the Series 208 or 241 product data sheet for more information.

VERTICAL CONCRETE When self-priming: Allow new concrete to cure 28 days. Abrasive blast or mechanically abrade concrete to remove laitance, form release agents, curing compounds, hardeners, sealers and other contaminants and to provide surface profile. (Reference SSPC-SP13)

CMU When self-priming: Allow new mortar to cure 28 days. Surfaces must be clean, dry, sound and free of all contaminants. Level all protrusions and mortar spatter. For pinhole free surface, use recommended surfer/filler/patcher.

WALL BOARD, WOOD & DRYWALL Must be clean, dry and free of oil, grease and other contaminants. **Note:** When using moisture resistant and/or high impact wall board or cement board in wet environments, utilize Series 215 and fiberglass tape or compound suitable for wet environments.

ALL SURFACES Must be clean, dry and free of oil, grease and other contaminants.

TECHNICAL DATA

VOLUME SOLIDS 100% (mixed) †

RECOMMENDED DFT **Horizontal:** 6.0 to 12.0 mils (150 to 305 microns) per coat.
Vertical: 4.0 to 8.0 mils (100 to 205 microns) per coat
Additional coats may be required for appearance or hiding.

CURING TIME

Temperature	To Topcoat	To Place in Service
75°F (24°C)	8-24 hours	24 hours

Note: If more than 24 hours have elapsed between coats, the coated surface must be mechanically abraded before topcoating.

VOLATILE ORGANIC COMPOUNDS

Unthinned: 0.19 lbs/gallon (22 grams/litre)
Thinned 5% (No. 2 Thinner): 0.52 lbs/gallon (63 grams/litre)
Thinned 5% (No. 42 Thinner): 0.50 lbs/gallon (59 grams/litre) †

TNEME-GLAZE | SERIES 280

THEORETICAL COVERAGE	1,604 mil sq ft/gal (39.4 m ² /L at 25 microns). See APPLICATION for coverage rates. †			
NUMBER OF COMPONENTS	Two: Part A and Part B (2 Parts A to 1 Part B by volume)			
PACKAGING		PART A	PART B	When Mixed
	Large Kit	2-5 gallon pails	1-5 gallon pail	15 gallons (56.8 L)
	Small Kit	2-1 gallon cans	1-1 gallon pail	3 gallons (11.4 L)
NET WEIGHT PER GALLON	11.85 ± 0.25 lbs (5.37 ± 0.11 kg) mixed †			
STORAGE TEMPERATURE	Minimum 40°F (4°C) Maximum 90°F (32°C) Note: Material should be stored at temperatures between 70°F and 90°F (21°C and 32°C) for at least 48 hours prior to use.			
TEMPERATURE RESISTANCE	(Dry) Continuous 250°F (121°C) Intermittent 275°F (135°C)			
SHELF LIFE	12 months at recommended storage temperature.			
FLASH POINT - SETA	N/A			
HEALTH & SAFETY	This product contains chemical ingredients which are considered hazardous. Read container label warning and Material Safety Data Sheet for important health and safety information prior to the use of this product. Keep out of the reach of children.			

APPLICATION

COVERAGE RATES Before commencing, obtain and thoroughly read the StrataShield Installation and Application Guide for floors.

	Dry Mils (Microns)	Wet Mils (Microns)	Sq Ft/Gal (m ² /Gal)
Horizontal	6.0-12.0 (150-305)	6.0-12.0 (150-305)	134-267 (12.4-24.8)
Vertical	4.0-8.0 (100-205)	4.0-8.0 (100-205)	200-401 (18.6-37.3)

Allow for overspray, surface irregularities and waste. Film thickness is rounded to the nearest 0.5 mil or 5 microns. Application of coating below minimum or above maximum recommended dry film thicknesses may adversely affect coating performance. †

MIXING Use a variable speed drill with a PS Jiffy blade. Slowly mix 2 parts A component, and while under agitation add 1 part B component and mix for a minimum of two minutes. Ensure that all Part B is blended with Part A by scraping the pail walls with a flexible spatula. Apply the mixed material within pot life limits after agitation.
Note: A large volume of material will set up quickly if not applied or reduced in volume.

Caution: Do not reseal mixed material. An explosion hazard may be created.

THINNING Normally not required. May thin up to 5% or 6.4 ounces (190 mL) per gallon to improve application properties. Brush and roll application use No. 2 Thinner. Spray application use No. 42 Thinner.

POT LIFE 25 to 30 minutes at 70°F (21°C) 15 to 20 minutes at 80°F (27°C) 8 to 10 minutes at 90°F (32°C)
Increasing material temperatures will significantly reduce the pot life.

APPLICATION EQUIPMENT Brush, roller, squeegee and airless spray.

Airless Spray

Pump	Tip Orifice	Atomizing Pressure	Mat'l Hose ID	Manifold Filter
Graco "King" 45:1 or 56:1	0.019"-0.033" (485-840 microns)	4,000-5,000 psi (275-344 bar)	3/8" to 1/2" (9.5 to 12.7 mm)	60 mesh (250 microns)

Roller: Use high quality 3/8" to 1/2" shed resistant, synthetic woven nap roller cover.

Brush: Use high quality synthetic or nylon bristle brush.

Horizontal: Squeegee and backroll. Brush small areas only.

Vertical: Roll or spray and backroll. Brush small areas only. **Spraying should only be considered as a means to transfer the material to the surface and should be followed by backrolling.**

SURFACE TEMPERATURE Minimum of 55°F (13°C), optimum 65°F to 80°F (18°C to 27°C), maximum of 90°F (32°C). The substrate temperature should be at least 5°F (3°C) above the dew point. To avoid outgassing, concrete temperature should be stabilized or in a descending temperature mode. Material should not be applied in direct sunlight.

MATERIAL TEMPERATURE For optimum application, handling and performance, the material temperature during application should be between 70°F and 90°F (21°C and 32°C). Temperature will affect the workability. Cool temperatures increase viscosity and decrease workability. Warm temperatures will decrease viscosity and shorten pot life.

CLEANUP Flush and clean all equipment immediately after use with xylene or MEK.

† Values may vary with color.

WARRANTY & LIMITATION OF SELLER'S LIABILITY: Tnemec Company, Inc. warrants only that its coatings represented herein meet the formulation standards of Tnemec Company, Inc. THE WARRANTY DESCRIBED IN THE ABOVE PARAGRAPH SHALL BE IN LIEU OF ANY OTHER WARRANTY, EXPRESSED OR IMPLIED, INCLUDING BUT NOT LIMITED TO, ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. THERE ARE NO WARRANTIES THAT EXTEND BEYOND THE DESCRIPTION ON THE FACE HEREOF. The buyer's sole and exclusive remedy against Tnemec Company, Inc. shall be for replacement of the product in the event a defective condition of the product should be found to exist and the exclusive remedy shall not have failed its essential purpose as long as Tnemec is willing to provide comparable replacement product to the buyer. NO OTHER REMEDY (INCLUDING, BUT NOT LIMITED TO, INCIDENTAL OR CONSEQUENTIAL DAMAGES FOR LOST PROFITS, LOST SALES, INJURY TO PERSON OR PROPERTY, ENVIRONMENTAL INJURIES OR ANY OTHER INCIDENTAL OR CONSEQUENTIAL LOSS) SHALL BE AVAILABLE TO THE BUYER. Technical and application information herein is provided for the purpose of establishing a general profile of the coating and proper coating application procedures. Test performance results were obtained in a controlled environment and Tnemec Company makes no claim that these tests or any other tests, accurately represent all environments. As application, environmental and design factors can vary significantly, due care should be exercised in the selection and use of the coating.

PRODUCT DATA SHEET

Sika® Armatec®-110 EpoCem

BONDING PRIMER AND REINFORCEMENT CORROSION PROTECTION

PRODUCT DESCRIPTION

Sika® Armatec®-110 EpoCem is a cementitious epoxy resin compensated 3-component, solvent-free, coating material with corrosion inhibitor, used as bonding primer and reinforcement corrosion protection.

USES

- Suitable in concrete repair as corrosion protection for reinforcement
- Suitable as a bonding primer on mortar, steel, and on placing fresh, plastic concrete to existing hardened concrete
- Protection to reinforcing steel in areas of thin concrete cover

CHARACTERISTICS / ADVANTAGES

- Contains EpoCem® technology - improved bonding agent
- Extended open times for repair mortars
- Excellent adhesion to concrete and steel
- Contains corrosion inhibitor
- Good resistance to water and chloride penetration
- High shear strength
- Long pot life
- Can be brushed on or applied using spray gun
- Can be used exterior on-grade
- Excellent bonding bridge for cement or epoxy based repair mortars
- High strength, unaffected by moisture when cured
- Non-flammable, solvent free

PRODUCT INFORMATION

Chemical Base	Portland cement, epoxy resin, selected aggregates and additives.				
Packaging	Unit	A	B	C	ABC
	3.5 gal (13.2 L)	47.6 oz (1.4 L)	122.1 oz (3.6 L)	46.82 lb (21.3 kg)	A + B in carton, C in bag
	1.65 gal (6.2 L)	22.7 oz (0.67 L)	57.6 oz (1.7 L)	5.5 lb (2.5 kg) (4 bags)	Factory- proportioned units in a pail
Appearance / Color	Component A			White liquid	
	Component B			Colorless liquid	
	Component C			Gray powder	
Shelf Life	12 months from date of production if stored properly in original, unopened and undamaged sealed packaging				
Storage Conditions	Store dry at 40–95 °F (4–35 °C)				

Protect Component A and B from freezing. If frozen, discard.
Protect Component C from moisture. If damp, discard.

TECHNICAL INFORMATION

Compressive Strength	3 days	4,500 psi (31.0 MPa)	(ASTM C-109) 73 °F (23 °C) 50 % R.H.
	7 days	6,500 psi (44.8 MPa)	
	28 days	8,500 psi (58.6 MPa)	
Flexural Strength	28 days	1,250 psi (8.6 MPa)	(ASTM C-348) 73 °F (23 °C) 50 % R.H.
Splitting Tensile Strength	28 days	600 psi (4.1 MPa)	(ASTM C-496) 73 °F (23 °C) 50 % R.H.
Tensile Adhesion Strength	Bond of steel reinforcement on concrete		
	Sika® Armatec® 110	625 psi (4.3 MPa)	(ASTM C-1583) 73 °F (23 °C) 50 % R.H.
	EpoCem coated		
	Epoxy coated	508 psi (3.5 MPa)	
	Plain reinforcement	573 psi (4.0 MPa)	
Slant Shear Strength	Bonding agent properties (14 d. moist cure, plastic to hardened concrete)		
	Wet on wet	2,800 psi (19.3 MPa)	(ASTM C-882) 73 °F (23 °C) 50 % R.H.
	24 hr. open time	2,600 psi (17.9 MPa)	
Permeability to Water Vapor	Control	7.32 x 10 ⁻¹⁰ ft/sec	
	145 psi (10 bar)	8.92 x 10 ⁻¹⁵ ft/sec	
Diffusion Resistance to Water Vapor	μ H ₂ O ~100		
Permeability to CO ₂	μ CO ₂ ~14,000		
Corrosion Test	Time-to-Corrosion Study <ul style="list-style-type: none"> Sika® Armatec®-110 EpoCem more than tripled the time to corrosion Reduced corrosion rate by over 40 % 		

APPLICATION INFORMATION

Fresh Mortar Density	A+B+C ~125 lb/ft³ (~2.0 kg/l)		
Coverage	Bonding agent	80 ft²/gal (7.4 m²/l)	
	Corrosion Protection	40 ft²/gal (3.7 m²/l)	
	(Coverage figures do not include allowance for surface profile and porosity or material waste)		
Layer Thickness		Min. thickness of 1 coat	Coat
	Bonding agent	20 mils	1
	Corrosion Protection	20 mils	2
Product Temperature	65°-75°F (18°-24°C)		
Ambient Air Temperature	40–95 °F (5–35 °C)		
Substrate Temperature	40–95 °F (5–35 °C)		
Pot Life	~ 90 minutes		
Waiting / Recoat Times	Sika repair mortars and non-fast setting concrete can be applied on Sika® Armatec®-110 EpoCem within a maximum time of:		

Temperature	Maximum Waiting Time
80°- 95 °F (26°- 35 °C)	6 hours
65°-79 °F (18°- 26 °C)	12 hours
50°- 64° F (10°- 17° C)	16 hours
40°- 49° F (4°- 9° C)	wet-on-wet

APPLICATION INSTRUCTIONS

SURFACE PREPARATION

Concrete

- Free from dust, loose material, surface contamination and materials which reduce bond or prevent suction or wetting by repair materials.
- Delaminated, weak, damaged and deteriorated concrete and where necessary sound concrete shall be removed by suitable means.
- Substrate must be Saturated Surface Dry (SSD) with no standing water.

Steel reinforcement

- Rust, scale, mortar, concrete, dust and other loose and deleterious material which reduces bond or contributes to corrosion shall be removed by blast cleaning or other means of mechanical abrasion and reinforcement.
- Should be fully exposed and have all corrosion removed.

MIXING

- Sika® Armatec®-110 EpoCem can be mixed with a low-speed (< 250 rpm) electric drill mixer.
- Shake components A and B thoroughly before opening.
- Pour liquid components A and B into a suitable mixing vessel and mix for 30 seconds.
- While still mixing components A and B slowly add powder component C.
- Mix the three components together for a minimum 3 minutes until blend is uniform and free of lumps, minimizing addition of air.
- Mix only the quantity that you can be applied within the pot life.
- DO NOT ADD WATER.

APPLICATION

As reinforcement corrosion protection

- Apply by stiff-bristle brush or spray at 80 ft² /gal.
- Take special care to properly coat the underside of the totally exposed steel.
- Allow coating to dry 2-3 hours at 73 °F, then apply a second coat at the same coverage.
- Allow to dry again before the repair mortar or concrete is applied.
- Pour or place repair within 7 days

As a bonding primer

- Apply using a stiff-bristle brush or broom. To achieve good bond, Sika® Armatec®-110 EpoCem must be applied well into the substrate, filling all pores and ensure complete coverage of all surface irregularities (minimum layer thickness 1/64" (0.5 mm).
- Spray apply with Goldblatt Pattern Pistol or equal equipment.
- Apply the freshly mixed patching mortar or concrete wet on wet, or up to the maximum recommended open time, onto the bonding slurry.

CURING TREATMENT

Sika® Armatec®-110 EpoCem must be protected against contamination and rain until application of the repair mortar.

CLEANING OF TOOLS

Clean all tools and application equipment with water immediately after use. Hardened material can only be mechanically removed.

LIMITATIONS

- Avoid application in direct sun and/or strong wind and/or rain.
- Do not add water.
- Not a vapor barrier.
- Apply only to sound, prepared substrates.
- Not recommended for use with expansive grouts and SikaQuicks
- Use of semi-dry mortars onto Sika® Armatec®-110 EpoCem must be applied "wet on wet"
- When used in overhead applications with hand placed patching mortars, use "wet on wet" for maximum mortar built thickness.
- Substrate profile as specified by the overlay or repair material is still required.
- As with all cement based materials, avoid contact with aluminum to prevent adverse chemical reaction and possible product failure. Insulate potential areas of contact by coating aluminum bars, rails, posts etc. with an appropriate epoxy such as Sikadur® Hi-Mod 32.

BASIS OF PRODUCT DATA

Results may differ based upon statistical variations depending upon mixing methods and equipment, temperature, application methods, test methods, actual site conditions and curing conditions.

OTHER RESTRICTIONS

See Legal Disclaimer.

ENVIRONMENTAL, HEALTH AND SAFETY

For further information and advice regarding transportation, handling, storage and disposal of chemical products, user should refer to the actual Safety Data Sheets containing physical, environmental, toxicological and other safety related data. User must read the current actual Safety Data Sheets before using any products. In case of an emergency, call CHEMTREC at 1-800-424-9300, International 703-527-3887.

DIRECTIVE 2004/42/CE - LIMITATION OF EMISSIONS OF VOC

A+B+C combined _____ 50 g/l

LEGAL DISCLAIMER

- KEEP CONTAINER TIGHTLY CLOSED
- KEEP OUT OF REACH OF CHILDREN
- NOT FOR INTERNAL CONSUMPTION
- FOR INDUSTRIAL USE ONLY
- FOR PROFESSIONAL USE ONLY

Prior to each use of any product of Sika Corporation, its subsidiaries or affiliates ("SIKA"), the user must always read and follow the warnings and instructions on the product's most current product label, Product Data Sheet and Safety Data Sheet which are available at usa.sika.com or by calling SIKA's Technical Service Department at 1-800-933-7452. Nothing contained in any SIKA literature or materials relieves the user of the obligation to read and follow the warnings and instructions for each SIKA product as set forth in the current product label, Product Data Sheet and Safety Data Sheet prior to use of the SIKA product.

SIKA warrants this product for one year from date of installation to be free from manufacturing defects and to meet the technical properties on the current Product Data Sheet if used as directed within the product's shelf life. User determines suitability of product for intended use and assumes all risks. User's and/or buyer's sole remedy shall be limited to the purchase price or replacement of this product exclusive of any labor costs. **NO OTHER WARRANTIES EXPRESS OR IMPLIED SHALL APPLY INCLUDING ANY WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. SIKA SHALL NOT BE LIABLE UNDER ANY LEGAL THEORY FOR SPECIAL OR CONSEQUENTIAL DAMAGES. SIKA SHALL NOT BE RESPONSIBLE FOR THE USE OF THIS PRODUCT IN A MANNER TO INFRINGE ON ANY PATENT OR ANY OTHER INTELLECTUAL PROPERTY RIGHTS HELD BY OTHERS.**

Sale of SIKA products are subject to the Terms and Conditions of Sale which are available at <https://usa.sika.com/en/group/SikaCorp/termsandconditions.html> or by calling 1-800-933-7452.

Sika Corporation
201 Polito Avenue
Lyndhurst, NJ 07071
Phone: +1-800-933-7452
Fax: +1-201-933-6225
usa.sika.com

Sika Mexicana S.A. de C.V.
Carretera Libre Celaya Km. 8.5
Fracc. Industrial Balvanera
Corregidora, Queretaro
C.P. 76920
Phone: 52 442 2385800
Fax: 52 442 2250537



Product Data Sheet
Sika® Armatec®-110 EpoCem
March 2020, Version 01.02
020302020050000003

SikaArmatec-110EpoCem-en-US-(03-2020)-1-2.pdf



PRODUCT DATA SHEET

SikaTop®-122 Plus

Two-component, polymer-modified, cementitious, trowel-grade mortar plus Sika FerroGard® 901 penetrating corrosion inhibitor

PRODUCT DESCRIPTION

SikaTop®-122 Plus is a two-component, polymer-modified, portland cement based, fast-setting, trowel-grade mortar. It is a high-performance repair mortar for horizontal and vertical surfaces and offers the additional benefit of Sika FerroGard® 901, a penetrating corrosion inhibitor.

USES

- On grade, above and below grade on concrete and mortar.
- On horizontal surfaces.
- As a structural repair material for parking structures, industrial plants, walkways, bridges, tunnels, dams, ramps, floods, etc.
- To level concrete surfaces.
- As an overlay system for topping/resurfacing concrete.

CHARACTERISTICS / ADVANTAGES

- Extremely low shrinkage **proven by four industry standard test methods**
- High compressive and flexural strengths
- High abrasion resistance
- Increased freeze/thaw durability and resistance to deicing salts
- Compatible with coefficient of thermal expansion of concrete - Passes ASTM C-884
- Increased density - improved carbon dioxide resistance (carbonation) without adversely affecting water vapor transmission (not a vapor barrier)
- Sika FerroGard® 901, a penetrating corrosion inhibitor - reduces corrosion even in the adjacent concrete

APPROVALS / STANDARDS

- USDA certifiable for the food industry
- ANSI/NSF Standard 61 potable water compliant
- Tested per ICRI guideline for inorganic repair material data sheet protocol guideline n°320.3R

PRODUCT INFORMATION

Packaging	Component A 1 gal (3.78 L) jug 4/carton	Component B 61.5 lb (28.9 kg) bag
Appearance / Color	Concrete gray when mixed	
Shelf Life	12 months from date of production if stored properly in original, unopened and undamaged sealed packaging	
Storage Conditions	Store dry at 40–95 °F (4–35 °C) Protect Component A from freezing. If frozen, discard.	

Protect Component B from moisture. If damp, discard.

Density	136 lbs/ft ³ (2.18 kg/L)	(ASTM C-138)
---------	-------------------------------------	--------------

TECHNICAL INFORMATION

Compressive Strength	1 day	2,500 psi (17.2 MPa)	(ASTM C-109) 73 °F (23 °C) 50 % R.H.
	7 days	5,300 psi (36.5 MPa)	
	28 days	7,000 psi (48.3 MPa)	
Modulus of Elasticity in Compression	28 days	3.0x10 ⁶ psi	(ASTM C-469) 73 °F (23 °C) 50 % R.H.
Flexural Strength	28 days	1,500 psi (10.3 MPa)	(ASTM C-293) 73 °F (23 °C) 50 % R.H.
Splitting tensile strength	28 days	500 psi (3.4 MPa)	(ASTM C-496) 73 °F (23 °C) 50 % R.H.
Tensile Strength	28 days	2,000 psi (13.8 MPa)	(ASTM C-882 modified)*
* Mortar scrubbed into substrate at 73 °F (23 °C) and 50 % R.H.			
Pull-Out Resistance	7 days	>300 psi (2.1 MPa)	(ASTM C-1583) 73 °F (23 °C) 50 % R.H.
	28 days	400 psi (2.8 MPa)	
Shrinkage	28 days	1"x1"x11-1/4" specimen	(ASTM C-157 modified (mod. ICRI 320.3R)) 73 °F (23 °C) 50 % R.H.
		3"x3"x11-1/4" specimen	
		< 0.021 %	
Ring test	Duration	>70 days	(ASTM C-1581) 73 °F (23 °C) 50 % R.H.
	Average Max Strain	-9 µstrain	
	Average Stress Strain	0.49 psi/day	
	Potential for Cracking	Low	
Baenziger block	90 days	No cracking	
Freeze-Thaw Stability	300 cycles	98 %	(ASTM C-666)
Rapid Chloride Permeability	28 days	< 500 C	(ASTM C-1202 AASHTO T-277)

APPLICATION INFORMATION

Mixing Ratio	Plant-proportioned kit, mix entire unit.		
Fresh mortar density	136 lbs/ft³ (2.18 kg/l)		(ASTM C-138)
Coverage	Neat	0.51 ft³ (0.02 m³) per unit	
	Extended with 42 lb (19 kg) of 3/8" (9.5 mm) gravel	0.75 ft³ (0.03 m³) per unit	
(Coverage figures do not include allowance for surface profile and porosity or material waste)			

Layer Thickness		Min.	Max. in one lift
	Neat	1/8" (3.2 mm)	1" (25 mm)
	Extended	1" (25.4 mm)	4" (101.6 mm)
Product Temperature	65–75 °F (18–24 °C)		
Ambient Air Temperature	> 45 °F (7 °C)		
Substrate Temperature	> 45 °F (7 °C)		
Set Time	35–70 minutes		(ASTM C-266)
Final set time	> 90 minutes		(ASTM C 266) 73° F (23° C), 50% R.H.
Finishing time	50–120 minutes		
Note: All times start after adding Component 'B' to Component 'A' and are highly affected by temperature, relative humidity, substrate temperature, wind, sun and other job site conditions.			

BASIS OF PRODUCT DATA

Results may differ based upon statistical variations depending upon mixing methods and equipment, temperature, application methods, test methods, actual site conditions and curing conditions.

ENVIRONMENTAL, HEALTH AND SAFETY

For further information and advice regarding transportation, handling, storage and disposal of chemical products, user should refer to the actual Safety Data Sheets containing physical, environmental, toxicological and other safety related data. User must read the current actual Safety Data Sheets before using any products. In case of an emergency, call CHEMTREC at 1-800-424-9300, International 703-527-3887.

LIMITATIONS

- Do not use solvent-based curing compound.
- Size, shape and depth of repair must be carefully considered and consistent with practices recommended by ACI or ICRI. For additional information, contact Technical Service.
- For additional information on substrate preparation, refer to ICRI Guideline No.310.2R Coatings, Polymer Overlays, and Concrete Repair.
- If aggressive means of substrate preparation is employed, substrate strength should be tested in accordance with ACI 503 Appendix A prior to the repair application.
- As with all cement based materials, avoid contact with aluminum to prevent adverse chemical reaction and possible product failure. Insulate potential areas of contact by coating aluminum bars, rails, posts etc. with an appropriate epoxy such as Sikadur 32 Hi-Mod.
- Refer to Sika® Antisol®-250 W product data sheet for use.

APPLICATION INSTRUCTIONS

SURFACE PREPARATION

- Concrete, mortar, and masonry products must be clean and sound.
- Remove all deteriorated concrete, dirt, oil, grease, and other bond-inhibiting materials from the area to be repaired.
- Be sure repair area is not less than 1/8" (3.2mm) in depth.
- Preparation work should be done by high pressure water blast, scabbler or other appropriate mechanical means to obtain an exposed aggregate surface profile of $\pm 1/16''$ -1/8" (1.6-3.2 mm) (CSP-5-6).
- To ensure optimum repair results, the effectiveness of decontamination and preparation should be assessed by a pull-off test.
- Saw cutting of edges is preferred and a dovetail is recommended.
- Substrate should be Saturated Surface Dry (SSD) with clean water prior to application. No standing water should remain during application.

PRIMING

- Reinforcing steel: Steel reinforcement should be thoroughly prepared by mechanical cleaning to remove all traces of rust. Where corrosion has occurred due to the presence of chlorides, the steel should be high pressure washed with clean water after mechanical cleaning. For priming of reinforcing steel use Sika® Armatec® 110 EpoCem (consult PDS).
- Concrete Substrate: Prime the prepared substrate with a brush or sprayed applied coat of Sika® Armatec® 110 EpoCem (consult PDS). Alternately, a scrub coat of SikaTop®-122 Plus can be applied prior to placement of the mortar. The repair mortar has to be applied into the wet scrub coat before it dries.

MIXING

- Pour approximately 7/8 of Component 'A' into the mixing container.
- Add Component 'B' (powder) while mixing continuously.
- Mix mechanically with a low-speed drill (400–600 rpm) and mixing paddle or mortar mixer.
- Add remaining Component 'A' (liquid) to mix if a more loose consistency is desired.
- Mix to a uniform consistency, maximum 3 minutes.
- Thorough mixing and proper proportioning of the two components is necessary.
- Refer to ACI 306 Guidelines when there is a need to place this product in cold & hot temperatures. Thinner application will be more sensitive to the temperature

EXTENSION WITH AGGREGATES

- For applications greater than 1" (25.4 mm) in depth, add 3/8" (9.5 mm) coarse aggregate.
- Pour all of Component 'A' into mixing container.
- Add all of Component 'B' while mixing, then introduce 3/8" (9.5 mm) coarse aggregate at desired quantity.
- Mix to uniform consistency, maximum 3 minutes.
- The aggregate must be non-reactive (reference ASTM C-1260, C-227 and C-289), clean, well graded, Saturated Surface Dry (SSD), have low absorption and high density, and comply with ASTM C-33 size number 8 per Table 2.
- Do not use limestone aggregate.
- Variances in the quality of the aggregate will affect the physical properties of SikaTop®-122 Plus and may result in different strengths.
- The addition rate is 42 lb (19 kg) of aggregate per bag. It is approximately 3.0-4.5 gallons (11.3-17.0 L) by loose volume of aggregate.

APPLICATION

- SikaTop®-122 Plus must be scrubbed into the substrate, filling all pores and voids.
- Force material against edge of repair, working toward center.
- After filling repair, consolidate, then screed.
- Allow mortar or concrete to set to desired stiffness, then finish with wood or sponge float for a smooth surface, or broom or burlap-drag for a rough finish.

CURING TREATMENT

- As per ACI recommendations for Portland cement concrete, curing is required.

- Moist cure with wet burlap and polyethylene, a fine mist of water or a water Sika® Antisol®-250 W* compatible curing compound meeting ASTM C-309.
- Curing compounds adversely affect the adhesion of following lifts of mortar, leveling mortar or protective coatings.
- Moist curing should commence immediately after finishing.
- Protect freshly applied mortar from direct sunlight, wind, rain and frost.
- To prevent from freezing, cover with insulating material.

* Pretesting of curing compound is recommended.

OTHER RESTRICTIONS

See Legal Disclaimer.

LEGAL DISCLAIMER

- KEEP CONTAINER TIGHTLY CLOSED
- KEEP OUT OF REACH OF CHILDREN
- NOT FOR INTERNAL CONSUMPTION
- FOR INDUSTRIAL USE ONLY
- FOR PROFESSIONAL USE ONLY

Prior to each use of any product of Sika Corporation, its subsidiaries or affiliates ("SIKA"), the user must always read and follow the warnings and instructions on the product's most current product label, Product Data Sheet and Safety Data Sheet which are available at usa.sika.com or by calling SIKA's Technical Service Department at 1-800-933-7452. Nothing contained in any SIKA literature or materials relieves the user of the obligation to read and follow the warnings and instructions for each SIKA product as set forth in the current product label, Product Data Sheet and Safety Data Sheet prior to use of the SIKA product.

SIKA warrants this product for one year from date of installation to be free from manufacturing defects and to meet the technical properties on the current Product Data Sheet if used as directed within the product's shelf life. User determines suitability of product for intended use and assumes all risks. User's and/or buyer's sole remedy shall be limited to the purchase price or replacement of this product exclusive of any labor costs. **NO OTHER WARRANTIES EXPRESS OR IMPLIED SHALL APPLY INCLUDING ANY WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. SIKA SHALL NOT BE LIABLE UNDER ANY LEGAL THEORY FOR SPECIAL OR CONSEQUENTIAL DAMAGES. SIKA SHALL NOT BE RESPONSIBLE FOR THE USE OF THIS PRODUCT IN A MANNER TO INFRINGE ON ANY PATENT OR ANY OTHER INTELLECTUAL PROPERTY RIGHTS HELD BY OTHERS.**

Sale of SIKA products are subject to the Terms and Conditions of Sale which are available at <https://usa.sika.com/en/group/SikaCorp/termsandconditions.html> or by calling 1-800-933-7452.

Sika Corporation
201 Polito Avenue
Lyndhurst, NJ 07071
Phone: +1-800-933-7452
Fax: +1-201-933-6225
usa.sika.com

Sika Mexicana S.A. de C.V.
Carretera Libre Celaya Km. 8.5
Fracc. Industrial Balvanera
Corregidora, Queretaro
C.P. 76920
Phone: 52 442 2385800
Fax: 52 442 2250537



Product Data Sheet
SikaTop®-122 Plus
November 2020, Version 01.04
020302040070000021

SikaTop-122Plus-en-US-(11-2020)-1-4.pdf

